

29 August 2022

WHENUAPAI BUSINESS PARK

69 AND 71 TRIG AND 151, 155 TO 157 BRIGHAM CREEK ROADS

GEOTECHNICAL INVESTIGATION REPORT

Neil Construction Limited

AKL2019-0040AM Rev.0

AKL2019-0040AM					
Date	Revision	Comments			
7 June 2022	A	Initial draft for internal review			
29 August 2022	0	Final issue			

	Name	Signature	Position
Prepared by	Jasmine Walden	A	Project Engineering Geologist
Reviewed by	Andrew Linton	AA	Principal Geotechnical Engineer CMEngNZ, CPEng
Authorised by	Richard Knowles	kjT knowles	Principal Geotechnical Engineer CMEngNZ, CPEng



EXECUTIVE SUMMARY

This report represents the geotechnical investigations, recommendations and works completed to date within the sites at 69 and 71 Trig Road and 151, 155 to 157 Brigham Creek Road, Whenuapai for the formation of residential and commercial subdivision.

These combined addresses give an approximate site area of 22.5 hectares with the properties located directly to the south of Brigham Creek Road and the east of Trig Road, Whenuapai. The sites are characterised by alluvial terraces of the Puketoka Formation and further detailed descriptions are outlined in Section 2.

Earthworks within 69 Trig Road and 151 and 155 to 157 Brigham Creek Road began in 2020. Bulk earthworks within 69 Trig Road to date are nearly completed and much of the area has been topsoiled. Works within 151, 155 to 157 Brigham Creek are still ongoing.

Bulk earthworks within 71 Trig Road began at the beginning of the 2022 season and are generally complete. The site currently sits with all lots topsoiled and road gullets left exposed for trimming.

Design details for geotechnical aspects of the development are summarised as follows:

- The combined site is underlain by alluvial soils of the Puketoka Formation. The main geotechnical hazards within this strata are low bearing capacity and settlement from soft/organic soils.
- Groundwater impact assessment was completed for the combined sites including groundwater monitoring within 71 Trig Road. Following review of the groundwater levels recorded in the investigation boreholes against the proposed cuts and fills within the above-mentioned earthworks plans, the proposed works within the sites are considered to be compliant against the AUP standards E7.6.1.6 and E7.6.1.10.
- Preliminary geotechnical ultimate bearing pressure of 300kPa should be available for shallow strip and pad foundations constructed within both the natural cut ground and engineered fill areas.
- Due to the presence of softer alluvial deposits underlying the stiffer surficial crust, subsoils may be subject to consolidation settlements due to the proposed loadings from industrial buildings. Site specific investigation and analysis would be required to confirm what settlements may occur based on specific development proposals.
- Specific plasticity index laboratory testing was undertaken within 69 Trig Road and showed that the soils tested returned plasticity indices of much greater than 12 and are therefore not considered liquefiable.
- Based on the ground conditions observed during this investigation, combined with experience working in the surrounding area, the seismic site subsoil category is assessed as being Class C (shallow soil site) in accordance with NZS1170.5.
- Initially it was envisaged that settlement monitoring would be required within the south-eastern gully in 69 Trig Road during earthworks due to the soils encountered in the investigation, as well as analysis results. However during site stripping and observations (as detailed in the earthworks to date Section 4 of this report) significant quantities of the subsoils underlying the topsoil were undercut and replaced with compacted engineered fill. In conjunction with the adjusted earthworks plans that required less filling within the gully, settlement monitoring was considered unnecessary and was therefore not undertaken.
- All of the soils at this site are clayey in nature and have very low coefficients of permeability.

TABLE OF CONTENTS

E	XECUTIVE	SUMMARY	.iii
1	INTROD	UCTION	1
	1.1 Proj	ect Brief	1
	1.2 Sco	pe of Work	1
2	SITE DE	SCRIPTION	2
	2.1 Site	Location	2
	2.2 Land	dform	2
	2.2.1	69 Trig Road, 151 and 155-157 Brignam Creek Road	2 ?
2			د د
ۍ ۲	PROPUS		ə
4	INVEST	GATION SCOPE	3
	4.1 Des	ktop Study	3
	4.2 Field	1 Investigation	4 1
	4.2.1	71 Trig Road	4 5
	4.3 Lab	pratory Testing	5
F	CROUN	R MOREI	E
Э	GROUN	D MODEL	
	5.1 Pub	lished Geology	5
	5.2 Stra	tigraphic Units	0 6
	522	I Incertified Fill	0 6
	5.2.3	Buried Topsoil	7
	5.2.4	Alluvium	7
	5.2.5	Residual Waitemata Group Soils	7
	5.2.6	Waitemata Group (Weathering) Transition Zone	7
	5.2.7	Waitemata Group Bedrock	7
	5.2.8	Summary	8
	5.3 Labo	pratory Test Results	8
	5.4 GIO		9
6	GEOHA	ZARDS ASSESSMENT	10
	6.1 Con	text	10
	6.2 Liqu	efaction	10
	6.2.1	General	10
	6.2.2	Geological Age	11
	0.2.3 6.3 Slor	SOII FADIIC	11 11
	6.3.1	Design Criteria	11
	6.3.2	Shear Strength Parameters	11
	6.3.3	Slope Stability Analyses	12
	6.4 Eros	sion	12
	6.5 Load	d Induced Settlement	13
	6.5.1	71 Trig Road	13
	0.5.2	by Irig Koad, 151 and 155-157 Brigham Creek Road	13
	6.5.2.1 6.5.2.2	Settlement Predictions	.13
	6.5.2.3	Time Rate of Settlement	14
	6.5.2.4	Monitoring and Approval	.14

(6.6	Expansive Soils	15
(6.7	Groundwater Impact Assessment	15
	6.7.	1 69 Trig Road, 151 and 155-157 Brigham Creek Road	15
	6.7.	2 71 Trig Road	15
7	GEO	OTECHNICAL RECOMMENDATIONS	16
-	7.1	Seismic Site Subsoil Category	16
-	7.2	Ground Improvement for Static Settlement (69 Trig Road)	16
	7.2.	1 Ground Improvement Options	16
	7.2.	2 Ground Improvement Design	16
	7.2.	3 Settlement Monitoring	17
-	7.3	Earthworks	17
	7.3.	1 General	17
	7.3.	2 Non-Engineered Fill	17
	7.3.	3 Excavatability	17
	7.3.	4 Subgrade Preparation	17
	7.3.	5 Stockpiles	18
	7.3.	6 Underfill Drainage	18
	7.3.	7 Compaction	18
	7.3.	8 Temporary Sediment Retention Ponds	18
	7.3.	9 Quality Control	18
-	7.4	Civil Works	19
	7.4.	1 Subgrade CBR	19
	7.4.	2 Service Trenches	19
	7.4.	3 Retaining Walls	19
	7.4.	4 Stormwater Soakage	20
-	7.5	Foundations	21
	7.5.	1 Residential Building Platforms	21
	7.5.	2 Industrial Building Platforms	21
-	7.6	Proposed Bridges and Retaining Walls	21
8	Ear	thworks SUmmary to date	22
8	3.1	151, 155 to 157 Brigham Creek Road and 69 Trig Road	22
8	3.2	71 Trig Road	22
9	FUF	RTHER WORK	23
US	E OF	THIS REPORT	24

Appendices

- Appendix A: CMW Drawings
- Appendix B: Supplied Development Plans
- **Appendix C: Investigation Data**
- Appendix D: Laboratory Test Results
- Appendix E: Natural Hazards Risk Assessment
- Appendix F: Stability Analyses Results
- Appendix G: Groundwater Impacts Assessment
- **Appendix H: Geotechnical Works Specification**
- Appendix I: Soakage Testing Results

1 INTRODUCTION

1.1 Project Brief

CMW Geosciences (CMW) was engaged by Neil Construction Limited to form a combined report of the geotechnical investigation and analysis/reporting/construction completed to date of the sites located at 69 and 71 Trig and 151, 155 to 157 Brigham Creek Roads, which is currently under construction to form a combination of commercial and residential lots.

The scope of work and associated terms and conditions of our engagement were detailed in our email agreement from 11 May 2022.

This report is to support a fast-tracked Consenting process to be submitted to the Ministry for the Environment.

1.2 Scope of Work

As detailed in our email agreement on the 11 May 2022, the agreed scope of work to be conducted by CMW was to form a Geotechnical Report that outlines all the investigation/reporting and recommendations to date on the subject site including all currently completed and ongoing earthworks operations.

The data supplied within this report is a compilation of the reports outlined below:

- Geotechnical Investigation Report for Trig & Brigham Creek Road, referenced AKL2019-0040AB Rev.0, dated 29 March 2019;
- Geotechnical Investigation Report for Trig & Brigham Creek Road, referenced AKL2019-0040AD Rev.0, dated 15 January 2020;
- CMW Geosciences Natural Hazards Risk Assessment for Land Subdivision at Trig & Brigham Creek Road, referenced AKL2019-0040AE Rev.0, dated 15 January 2020;
- CMW Geosciences Land Development Geotechnical Works Specification for Trig & Brigham Creek Road, referenced AKL2019-040AF Rev.0, dated 15 January 2020;
- Section 92 Response Letter for Trig & Brigham Creek Road, referenced AKL2019-0040AG Rev.1, dated 9 July 2020;
- Falling Head Soakage Test Letter for Trig & Brigham Creek Road, referenced AKL2019-0040AH Rev.0, dated 1 June 2021;
- Geotechnical Investigation Report for 71 Trig Road, referenced AKL2020-0231AB Rev.1, dated 24 June 2021;
- Infiltration Memorandum for 71 Trig Road, referenced AKL2020-0231AC Rev.0, dated 25 June 2021;
- Groundwater Assessment Letter for 71 Trig Road, referenced AKL2020-0231AD Rev.0, dated 13 October 2021;
- Bridge Abutment Pile Parameters for Trig & Brigham Creek Road, referenced AKL2019-0040AJ Rev.0, dated 22 December 2021.

2 SITE DESCRIPTION

2.1 Site Location

The site comprises a combined total area of approximately 22.45 hectares, formed from the combination of 151, 155 to 157 Brigham Creek Road and 69 and 71 Trig Road, Whenuapai as illustrated in *Figure 1* below.



Figure 1: Site Location Plan (Auckland Council GIS)

2.2 Landform

The general landform, together with associated features located within and adjacent to the site is presented on the attached Site Investigation Plans in *Appendix A*, and is summarised below based on property addresses. Descriptions are based on the site conditions prior to any works commencing.

2.2.1 69 Trig Road, 151 and 155-157 Brigham Creek Road

These properties are characterised by an alluvial terrace that grades moderately from approximately RL35m on the southern boundary to RL15m at the south-eastern and RL13m at the north-eastern corners of the site.

Two gullies with associated overland flow paths and streams are present towards the north and southeastern sections of the site.

The site is bound to the north by Brigham Creek Road, and to the south, east and west by neighbouring rural residential properties. An existing residential dwelling is located on 149 Brigham Creek Road, which is incorporated in the northern corner of 151 Brigham Creek Road.

There are no residential dwellings present on 69 Trig Road or 155-157 Brigham Creek Road, however there is an existing culvert crossing located on 155-157 Brigham Creek Road.

The site has historically been used for agricultural purposes.

2.2.2 71 Trig Road

The property at 71 Trig Road is roughly rectangular in shape, stretching in a west to east direction.

The gradient across the site is generally consistent, falling gradually from the south at approximately RL42.0m down to RL25.5.0m in the north-eastern corner with an approximate gradient of 1(V):15(H) across most of the site.

Auckland Council GIS maps a possible creek exiting the north-eastern corner of the site with numerous contributary overland flow paths mapped across the site.

The site itself previously comprised mostly pasture and overgrown, historic horticultural patches. Tall trees run along most of the paddock fence lines as well as being scattered in the north and north-eastern areas of the property. An existing structure is located along the northern boundary.

The site is bound to the north by residential dwellings in the form of larger lifestyle blocks and to the west and south by farmland. The eastern boundary backs onto the wider Trig and Brigham Creek Road development site.

3 PROPOSED DEVELOPMENT

For the proposed development, the combined properties described above are referred to as Whenuapai Business Park.

The current development plans supplied by Cato Bolam Consultants are outlined below:

- Finished Contour Plans referenced 44315-DR-C-2000 to 2005 (Sheets 1 to 5), dated 13 July 2022.
- Cut Fill Contours (Existing Surface to Finished Surface) referenced 44315-DR-C-2100 to 2105 (Sheets 1 to 5), dated 15 July 2022.
- Sediment and Erosion Control Plan referenced 44315-DR-C-2200 to 2202 (Sheets 1 to 3), dated 20 July 2022.

The Cato Bolam plans depict the formation of 21 industrial lots/superlots of varying size, and 2 balance lots (referenced Lots 200 and 300) along the northern boundary for future residential development.

Cuts and fills are proposed across the entire site. Cuts of up to 1.5m depth are proposed through the centre of 69 Trig Road and 151 Brigham Creek Road, as well as along the southern half of 71 Trig Road with an approximate total of 11,900m³. Fills will range up to approximately 2.0m depth and will largely be located in the south-eastern corner of 69 Trig Rd. Fills are also proposed adjacent to the existing creek alignment along the northern perimeter of 151 Brigham Creek Road and part of 157 Brigham Creek Road.

The plans also depict 2 proposed bridges and associated abutments/retaining walls. The main, larger, bridge is proposed as part of the new intersection of the subdivisions Road 1 with Brigham Creek Road and the neighbouring development. A smaller bridge to the north-west is proposed to create access to 155 Brigham Creeks future residential development from 151 Brigham Creek Road. Approximately 7 retaining walls are proposed as part of these works to support the new proposed levels.

Supplied development plans are attached to this report in *Appendix B*.

4 INVESTIGATION SCOPE

4.1 Desktop Study

A desktop study was carried out before commencing fieldwork for all properties. This included online research through Auckland Council Geo Maps, Dial Before You Dig, aerial photographs and an underground services search, as well as a number of documents provided by Neil Construction from the Auckland Council property file.

Based on the historical use of the site as agricultural land and surrounding land levels, inferred from aerial photographs and recorded history, some reasonable depths of fill should be anticipated as a result of soft

landscaping and historic earthworks across the site. We understand that uncontrolled fill has been placed in the south-eastern part of 69 Trig Road, dating back to 2001.

A review of historic and recent aerial photographs between 1959 and 2017 indicated the following activity on 71 Trig Road:

- Between 1959 and 1996 the subject site was developed from agricultural land for horticultural purposes. The existing structure on site appears to have been constructed around the same time as the development of the land.
- From 2003 to approximately 2012 the sites horticultural development appears to have been let go and the area returned to farmland.
- From approximately 2015 onwards the site appears to have been returned to horticultural activities, however, to date the site is currently unattended.

Previous reports as described in Section 1.2 above were also reviewed and compiled.

4.2 Field Investigation

The approximate locations of the respective investigation sites referred to below are shown on the Site Investigation Plans appended to this report. Test locations were measured using a handheld GPS. Elevations were inferred from the existing Auckland Council GIS contours.

4.2.1 69 Trig Road, 151 and 155-157 Brigham Creek Road

The field investigation for these properties was carried out between 18 March 2019 and 22 March 2019, and 25 November 2019 and 27 November 2019. All fieldwork was carried out under the direction of CMW Geosciences in general accordance with the NZGS guidance¹. The scope of fieldwork completed was as follows:

- A walkover survey of the site was undertaken to assess the general landform, site conditions and adjacent structures / infrastructure;
- An on-site services search was carried out by a specialist contractor to identify the presence of any underground obstructions or hazards prior to the field investigation program commencing;
- Seven Cone Penetrometer Tests (CPT), denoted CPT01 to CPT07, were pushed to depths of up to 16.5m to define the ground model through the underlying zone of influence of future building foundations and to provide preliminary parameters for retaining wall and foundation design. Results of the CPT's, presented as traces of tip resistance (qc), friction resistance (fs) and friction ratio are presented in *Appendix C*;
- Two machine boreholes, denoted MH01-19 and MH02-19, were drilled using HQ3 diamond coring drilling techniques to depths of up to 20m to determine the ground model through and below the proposed earthworks profile. Engineering logs and photographs of the boreholes are provided in *Appendix C*;
- Seven test pits, denoted TP01-19 to TP07-19, were excavated using a 20-tonne hydraulic excavator fitted with a 2m wide blade bucket to depths of between 1.2m and 3.0m below existing ground levels to determine the quality and extent of the fill within the south-eastern corner of 69 Trig Road. TP02-19 was terminated due to encountering an old drainage pipe, while TP01-19 and TP03-19 to TP07-19 were terminated at target depth, below any fill materials. Engineering logs and photographs of the test pits are presented in *Appendix C*;
- Twenty two hand auger boreholes, denoted HA01-19 to HA022-19, were drilled using a 50mm diameter auger to target depths of up to 5.0m below existing ground levels to visually observe the

¹ NZ Geotechnical Society (2005), Field Description of Soil and Rock, Guideline for the field classification and description of soil and rock for engineering purposes.

near surface soil profile and to facilitate vane shear strength testing. Refusal was met in HA01-19 at 1.6m due to the presence of gravel fill. Engineering logs of the hand auger boreholes, together with peak and remoulded vane shear strengths are presented in *Appendix C*.

• Additional hand augers and machine boreholes are currently being undertaken to support design of the bridges and retaining walls within 151 and 155 - 157 Brigham Creek Road.

4.2.2 71 Trig Road

The field investigation for this property was carried out on 16 September 2020. All fieldwork was carried out under the direction of CMW Geosciences in general accordance with the NZGS guidelines¹. The scope of the fieldwork was as follows:

- A walkover survey of the site to assess the general landform, site conditions and adjacent structures / infrastructure. The site walkover generally confirmed the existing contours of the area and there was no evidence of any recent change in the site conditions.
- Ten hand auger boreholes, denoted HA01-20 to HA10-20, were drilled using a 50mm diameter auger to target depths of up to 5.0m below existing ground levels to observe the near surface soil profile and to facilitate vane shear strength testing. All ten hand auger boreholes reached the target depth of 5.0m. Engineering logs of the hand augers, together with peak and remoulded vane shear strengths can be found appended to this report in *Appendix C*.

4.3 Laboratory Testing

Laboratory testing was carried out generally in accordance with the requirements of NZS4402² (where applicable). Where a test was not covered by a New Zealand standard, a local or International standard was adopted and noted on the laboratory test certificate.

All testing was scheduled by CMW and carried out by Roadtest and Babbage Geotechnical Laboratory, both of which are IANZ registered Testing Authorities.

The extent of testing carried out to provide the geotechnical parameters required for this study are presented in Table 1.

Table 1: Laboratory Testing Schedule					
Type of Test	Test Method	Quantity			
Water Content	NZS4402 – 1986 2.1	3			
Atterberg Limits	NZS4402 – 1986 2.3 / 2.4 / 2.5	1			
One Dimensional Consolidation	NZS4402 – 1986 7.1	2			

Certificates for the test results outlined above are presented in Appendix D.

5 GROUND MODEL

5.1 Published Geology

Published geological maps³ for the area depict the regional geology as comprising Late Pliocene to Mid Pleistocene alluvial deposits of the Puketoka Formation (Pup) as illustrated in *Figure 2* below.

² New Zealand Standard NZS4402 (1986), Methods of testing soils for civil engineering purposes.

³ Edbrooke, S. W. (compiler) 2001: Geology of the Auckland area. Institute of Geological & Nuclear Sciences 1:250 000 geological map 3. 1 sheet +74 p. Lower Hutt, New Zealand. Institute of Geological & Nuclear Sciences.



Figure 2: Regional Geology (GNS Science Geology Map)

These alluvial deposits include pumiceous mud, sand and gravel with muddy peat and lignite, rhyolitic pumice (including non-welded ignimbrite, tephra and alluvial pumice deposits) and massive micaceous sand beds. Below these upper soil layers, the deeper geological formation is reported to comprise, interbedded muddy sandstones and siltstones of the East Cast Bays Formation (Mwe) within the Waitemata Group.

The main geotechnical hazards within the Puketoka Formation strata are low bearing capacity and settlement from soft/organic soils.

We understand that uncertified fill is present across some areas of the development site.

5.2 Stratigraphic Units

The ground conditions encountered and inferred from the investigation were considered to be generally consistent with the published geology for the area and can be generalised according to the following subsurface sequences.

5.2.1 Topsoil

Topsoil was encountered in all test pits and boreholes, excluding HA12-19, to depths of between 0.05m and 0.4m. Topsoil was generally dry to moist across the site.

5.2.2 Uncertified Fill

Historic uncontrolled/uncertified fill was encountered as expected in the southeast corner of 69 Trig Road and the northern portion of 155-157 Brigham Creek Road, with a thin veneer also encountered in the central portion of 151 Brigham Creek Road. Uncertified fill was encountered in all recent test pits and boreholes, excluding TP04-19, TP06-19, HA17-19, HA21-19, HA22-19, and MH02-19.

Fill encountered in the south eastern corner of 69 Trig Road generally comprised grey, brown, orange and black, clays, gravels, clay/gravel mixtures and clay/silt mixtures, with organic material, concrete, old drainage pipes and plastic throughout. Testing throughout this material demonstrated peak shear strengths of between 48kPa and >217kPa.

A thin layer (0.1m) of buried topsoil was encountered at the base of this fill in TP05-19 and TP07-19.

Fill encountered in the northern portion of 155-157 Brigham Creek Road generally comprised stiff to very stiff, orange, brown, yellow, grey, and black, clay/silt mixtures, with trace gravel and sand. Testing throughout this fill demonstrated peak shear strengths of between 61kPa and greater than 178kPa.

A thin lens of up to approximately 200mm depth of non-engineered fill was encountered below the topsoil in HA19-19 and HA20-19. This comprised stiff, dark brown, yellow, orange and grey silty clay.

5.2.3 Buried Topsoil

A layer of buried topsoil was also encountered underlying some of the uncertified fill in 69 Trig Road and 155-157 Brigham Creek Road. This topsoil layer was generally encountered from depths of 0.4m up to depths of 2.6m, was generally 50mm to 400mm in thickness, and firm and brown with some gravel throughout.

5.2.4 Alluvium

Alluvial deposits of the Puketoka Formation were encountered in all test pits, hand augers and machine boreholes (excluding HA01-19) and generally comprised yellow, brown, and grey mottled orange and black, clays and clay/silt and clay/sand mixtures, with some organics and organic staining.

Alluvium was encountered from depths of 0.2m to depths of 10.3m and was generally firm to hard, with peak shear strengths quite variable and ranging from 25kPa to 224kPa.

Outlier vane shear strengths of 40kPa in HA02-20, 52kPa in HA06-20 and 39kPa in HA08-20 were generally encountered where the groundwater was sitting or within organic stained material.

SPT testing demonstrated N values ranging from 6 to 20 throughout this stratum.

5.2.5 Residual Waitemata Group Soils

Residual soils of the East Coast Bays Formation (Waitemata Group) were encountered in all hand auger boreholes and both machine boreholes (excluding HA03-19, HA04-19 and HA12-19 and all boreholes within 71 Trig Road). Residual soils generally comprised grey, orange and dark grey, clays, clay/silt mixtures, sand/silt mixtures and clay/sand mixtures.

Residual soils were encountered from depths of 2.2m up to 12.7m, and were generally stiff to hard, with peak shear strengths ranging from 58kPa to greater than 224kPa.

SPT testing demonstrated N values ranging from 15 to 50+ throughout this stratum.

5.2.6 Waitemata Group (Weathering) Transition Zone

Transitional soils of the East Coast Bays Formation (Waitemata Group) were encountered in MH01-19 and MH02-19.

Transition zone soils were encountered from depths of 11.5m to depths greater than 20m and generally comprised completely to highly weathered, grey, extremely weak, siltstones and sandstones, weathered to sand/silt mixtures.

SPT testing demonstrated N values of 50+ throughout this stratum.

5.2.7 Waitemata Group Bedrock

Highly to moderately weathered, interbedded siltstones and sandstones of the East Coast Bays Formation (Waitemata Group) were encountered in MH02-19.

This Waitemata Group bedrock was encountered from depths of 13.8m to depths greater than 15.5m and was generally grey and very weak to weak.

SPT testing demonstrated N values of 50+ throughout this stratum.

5.2.8 Summary

The distribution of these units is illustrated on the appended Geological Sections A to D and presented below in *Table 2*.

Table 2: Summary of Strata Encountered							
	Depth to	base (m)	Thickness (m)⁵				
Unit	Min	Max	Min	Max			
Topsoil	0.05	0.40	0.05	0.40			
Uncertified Fill¹ – firm to very stiff, orange, brown, yellow, grey, and black, clays and clay/silt mixtures, with trace gravel, sand, organics and unsuitables.	0.20	2.60	0.20	2.45			
Buried Topsoil ²	0.45	2.70	0.05	0.40			
Alluvium – firm to hard, yellow, brown, and grey mottled orange and black, clays and clay/silt and clay/sand mixtures, with some organics and organic staining.	2.20	>5.00	0.50	10.05			
Residual Waitemata Group Soils³ – stiff to hard, grey, orange and dark grey, clays, clay/silt mixtures, sand/silt mixtures and clay/sand mixtures.	11.50	12.70	1.20	5.20			
Waitemata Group Transition Zone³ – completely to highly weathered, grey, extremely weak, siltstones and sandstones, weathered to sand/silt mixtures.	13.80	>20.00	2.30	7.30			
Waitemata Group Bedrock ^{3,4} – highly to moderately weathered, grey, interbedded siltstones and sandstones, very weak to weak. >15.50 >15.50 - ⁵							
 Notes: ¹ Strata not encountered in TP04-19, TP06-19, HA03-19-HA11-19, HA17-19, HA21-19, HA22-19 and MH02-19, or HA01-20 to HA10-20. ² Strata only encountered in TP05-19, TP07-19, HA12-19, HA13-19 and HA15-19. ³ Strata not encountered in test pits, HA03-19, HA04-19 and HA12-19, or HA01-20 to HA10-20. ⁴ Strata only encountered in MH02-19. 							

⁵ Thickness only recorded were base of strata has been confirmed.

5.3 Laboratory Test Results

Results of the civil engineering laboratory tests are provided in *Appendix D* and summarised in Table 3.

Table 3: Summary of Civil Engineering Laboratory Test Results							
Test Location	Depth (mbgl)	LL (%)	PL (%)	PI (%)	MC (%)		
MH01-19	2.5 – 3.0	95	28	67	51.8		
MH01-19	5.0 – 5.5	-	-	-	33.2		
MH02-19 3.45 - 3.95 45.1							
Note: LL =	Note: LL = liquid limit, PL = plasticity limit, PI = plasticity index, MC = Natural Moisture Content.						

5.4 Groundwater

During the investigation, which was completed in late spring conditions (November 2019 and September 2020), groundwater was encountered within the boreholes at the depths provided in Table 4 below.

Table 4: Groundwater Monitoring Data							
Investigation	18 Ma	18 March 2019		25 November 2019 & 26 November 2019		16 September 2020	
Location	Depth (mbgl)	Elevation (m RL)	Depth (mbgl)	Elevation (m RL)	Depth (mbgl)	Elevation (m RL)	
HA01-19	NE	NE	-	-	-	-	
HA02-19	2.9	15.1	-	-	-	-	
HA03-19	NE	NE	-	-	-	-	
HA04-19	NE	NE	-	-	-	-	
HA05-19	NE	NE	-	-	-	-	
HA06-19	3.1	23.9	-	-	-	-	
HA07-19	3.0	21.5	-	-	-	-	
HA08-19	3.6	18.9	-	-	-	-	
HA09-19	2.8	20.7	-	-	-	-	
HA10-19	NE	NE	-	-	-	-	
HA11-19	NE	NE	-	-	-	-	
HA12-19	-	-	2.8	20.7	-	-	
HA13-19	-	-	2.9	20.1	-	-	
HA14-19	-	-	2.5	18.7	-	-	
HA15-19	-	-	2.2	18.0	-	-	
HA16-19	-	-	2.0	18.1	-	-	
HA17-19	-	-	2.0	15.5	-	-	
HA18-19	-	-	2.0	16.6	-	-	
HA19-19	-	-	2.0	19.4	-	-	
HA20-19	-	-	2.6	20.8	-	-	
HA21-19	-	-	2.8	22.2	-	-	
HA22-19	-	-	2.6	26.0	-	-	
TP01-19	-	-	NE	NE	-	-	
TP02-19*	-	-	1.0	24.5	-	-	
TP03-19	-	-	NE	NE	-	-	
TP04-19	-	-	1.2	21.8	-	-	
TP05-19	-	-	2.6	18.8	-	-	
TP06-19	-	-	NE	NE	-	-	
TP07-19	-	-	NE	NE	-	-	
HA01-20	-	-	-	-	4.0	29.0	
HA02-20	-	-	-	-	2.2	32.6	

Table 4: Groundwater Monitoring Data						
Investigation	18 March 2019		25 November 2019 & 26 November 2019		16 September 2020	
Location	Depth (mbgl)	Elevation (m RL)	Depth (mbgl)	Elevation (m RL)	Depth (mbgl)	Elevation (m RL)
HA03-20	-	-	-	-	4.4	35.6
HA04-20	-	-	-	-	3.2	29.5
HA05-20	-	-	-	-	4.5	31.0
HA06-20	-	-	-	-	2.5	29.3
HA07-20	-	-	-	-	1.0	28.8
HA08-20	-	-	-	-	2.7	26.7
HA09-20	-	-	-	-	4.8	31.1
HA10-20	-	-	-	-	2.2	29.7
Notes: mbgl = metre Elevations are approx	es below ground	level. NE = Not	Encountered. * kland Council G	= Perched Grou IS.	ndwater Encour	itered.

Although groundwater was measured at the above elevations during investigations, it should be noted that groundwater levels will vary seasonally and with rainfall.

Given the presence of a variable and clayey soil profile, it is also possible that perched groundwater may occur during and following periods of rainfall.

6 GEOHAZARDS ASSESSMENT

6.1 Context

Section 106 of the Resource Management Act⁴ (RMA) requires an assessment of the risk from natural hazards to be carried out when considering the granting of a subdivision consent. S106 RMA specifically states that the assessment must consider the combined effect of the natural hazard likelihood and material damage to land or structures (consequence).

The following sections of this report provide an assessment of the geohazards relevant to this site and provide the basis for the Natural Hazards Risk Assessment presented in *Appendix E*.

6.2 Liquefaction

6.2.1 General

Soil liquefaction is a process where typically saturated, granular soils develop excess pore water pressures during cyclic (earthquake) loading that exceed the effective stress of the soil. In loose soils, some dilation can occur during this process, which can lead to individual soil grains moving into suspension. Following the onset of liquefaction, the shear strength and stiffness of the liquefied soil is effectively lost causing excessive differential settlement of the ground surface, bearing capacity failure and collapse of structures and low-angle lateral spreading of slopes in liquefiable soils.

In accordance with NZGS guidance⁵ the liquefaction susceptibility of the soils at this site has been considered with respect to geological age and soil fabric.

⁴ Resource Management Act (1991), as at 29 October 2019

⁵ Earthquake Geotechnical Engineering Practice, Module 3: Identification, assessment and mitigation of liquefaction hazards", (May 2016)

6.2.2 Geological Age

The vast majority of case history data compiled in empirical charts for liquefaction evaluation comes from Holocene deposits or man-made fills (Seed and Idriss, 1971). Youd and Perkins, 1978 also state that young Holocene age (15,000 years) sediments and man-made fills are susceptible to liquefaction. Table 1 of Idriss and Boulanger (extracted from Youd and Perkins (1978)), presents the susceptibility of soil deposits to liquefaction based on geological age, which states that Pleistocene aged alluvium (>12,000 years) has a very low to low risk of liquefaction.

Across the elevated terraces, soils below the water table comprise alluvial deposits of the Puketoka Formation. These soils are defined as being of Late Pliocene to Mid Pleistocene in geological age with a dated age at 71k to 3.6Ma old. These deposits are therefore significantly older than what case history data would suggest as being susceptible to liquefaction.

6.2.3 Soil Fabric

Soils are also classified with respect to their grain size and plasticity to assess liquefaction susceptibility. Based on more recent case histories, there is general agreement that sands, non-plastic silts, gravels and their mixtures form soils that are susceptible to liquefaction. Clays, although they may significantly soften under cyclic loading, do not exhibit liquefaction features, and therefore are not considered liquefiable. NZGS guidance⁵ sets out the plasticity index (PI) criteria for liquefaction susceptibility as follows:

PI < 7: Susceptible to Liquefaction

 $7 \le PI \ge 12$: Potentially Susceptible to Liquefaction

 $PI \ge 12$: Not Susceptible to Liquefaction

The fines content of the sands beneath the site also has a significant impact on their liquefaction susceptibility.

Specific plasticity index laboratory test results are presented in Section 5.3 above and show that the soils tested provided plasticity indices of much greater than 12 and are therefore not considered liquefiable.

6.3 Slope Stability

6.3.1 Design Criteria

The stability of cut batters and fill embankments under a range of design conditions is expressed in terms of a factor of safety, which is defined as the ratio of forces resisting failure to the forces causing failure. The following performance standards are recommended for slope stability assessment:

Table 5: Slope Stability Factor of Safety Criteria				
Condition	Required Factor of Safety			
Static long-term conditions (normal groundwater)	1.5			
Transient short-term conditions (elevated groundwater)	1.3			
Ultimate Limit State (ULS) seismic condition	1.2			

6.3.2 Shear Strength Parameters

Drained shear strength parameters for the various geological units that underlie the site were inferred from the field investigation and experience, and are summarised in Table 6 below.

Geological Unit	Unit Weight (kN/m ³)	n ³) Effective Stress Paramete		
		Back Analysis		
		c' (kPa)	Ø' (deg)	
Engineered Fill	18	5	30	
Uncertified Fill	17	2	27	
Puketoka Formation Alluvium	17	2	27	
Residual Waitemata Group Soils	18	3	30	
Waitemata Group Transition Zone	18	10	30	
Waitemata Group Bedrock	18	10	40	

6.3.3 Slope Stability Analyses

Four cross sections (Sections A, B, C and D) were analysed at 69 Trig Road, 151 and 155-157 Brigham Creek Road, as indicated on the appended Site Investigation Plan (referenced AKL2019-0040, Drawing 01).

Slope stability analyses were undertaken using the Morgenstern-Price method of slices under both circular and translational failure mechanisms using the proprietary software SLIDE Version 8.0. Earthquake loads were calculated in accordance with NZS 1170.5 and NZTA Bridge Manual (BM) Section 6.2.2 for earthquake loads for the assessment of slope stability. An ULS design earthquake return period of 150 years as recommended within the Auckland Council Code of Practice (ACCoP) has been assumed in the assessment. The peak ground acceleration (PGA) for stability analyses was calculated as 0.115g.

Table 7: Slope Stability Analyses Results						
Location	Slope Stability Factor of Safety (Proposed Profile)					
	Prevailing Transient Seismic					
Geological Section A-A	2.8	2.4	1.7			
Geological Section B-B	2.3	1.6	1.7			
Geological Section C-C	2.3	1.7	1.6			
Geological Section D-D	1.8	1.4	1.4			

Selected stability printouts are attached in *Appendix F* and summarised as follows:

Results show that the slope stability factor of safety criteria are achieved for the proposed landform and assessed ground model conditions described above. However, detailed design of future developments will need to take into account the potential for soil creep on any steep batters, and proposed working loads. If loads greater than 20kPa are proposed, further analyses will be required.

We note that Section A-A analyses previously assumed the existing non-engineered fill would remain in place. While acceptable factors of safety are achieved for slope stability, there would be an inherent risk of settlement occurring within this fill if it is not reworked as part of the earthworks operations. This non-engineered fill has since been removed and replaced with engineered fill (see Section 8 below) which is considered to have low risk of settlement.

6.4 Erosion

Erosion of cut and fill batters during earthworks is considered to be a high-risk natural hazard and easily addressed during construction. Erosion around batters may subsequently contribute to slope instability and

falling debris. This hazard can be controlled during the design phase by limiting batters to a maximum of 1V:3H gradients and during earthworks via benches, geotextiles and stormwater control.

6.5 Load Induced Settlement

6.5.1 71 Trig Road

Based on the materials observed in our boreholes, settlement is considered to be a low risk for light weight commercial or industrial buildings. The soft materials within the creek/gully uncovered as part of earthworks operations (see Section 8 below) have been undercut to competent ground and replaced with compacted engineered fill.

Soft subsoils may be subject to consolidation settlements due to potential loadings from industrial buildings and floor slabs. Pre-loading of soft soils, general ground improvement during earthworks and possibly piling, or reinforced fill rafts and basal reinforcements may be necessary to mitigate any significant settlement hazards across the industrial zones.

Depending on the future proposed development plans, settlement analyses may need to be undertaken as part of any future detailed investigation and design. This will allow for the development of appropriate ground remediation options if necessary.

6.5.2 69 Trig Road, 151 and 155-157 Brigham Creek Road

6.5.2.1 Design Parameters

The ground conditions around the northern stream are stiff and considered unlikely to be subject to significant settlements under the proposed fill heights and future development loads.

Proposed fill embankments and / or future building loads in the area of the southern gully in 69 Trig Road will induce settlements within the underlying subsoils, as well as across adjacent areas of the site subject to minimal excavation to form the final subgrade levels. CPT and oedometer laboratory testing were carried out to assess the soil modulus parameters for load induced settlement analyses.

Results of the laboratory oedometer testing show that the soils are over-consolidated meaning that for the proposed fill embankment / foundation pressures, these soils are not expected to settle significantly, with settlement expected to follow the unload-reload compression (Cr) line.

A summary of the parameters adopted for preliminary design is summarised as follows:

Table 8: Summary of Consolidation Design Parameters			
Parameter	Test Range	Design Value	
Compression Index (Cc)	0.24 - 0.47	0.24	
Recompression Index (Cr)	0.06	0.06	
Initial void ratio (e₀)	0.88 - 1.303	0.88	
Secondary / Primary Compression Index ratio (Cα/ Cc)	0.05	0.05	
Coefficient of vertical consolidation (Cv – m²/year)	10 - 20	15	

6.5.2.2 Settlement Predictions

The construction of earthfill embankments over weak alluvial soils will induce consolidation and post construction creep settlements. An assessment of static settlements was completed for the proposed range of fill embankment heights. For the range of proposed fill heights, it is assessed that the imposed loads will be less than the pre-consolidation pressure of the subgrade materials where they will behave in an over-consolidated state following the Cr compression line.

Primary consolidation settlements were assessed using a CMW in house spreadsheet in accordance with the following Terzaghi 1-dimensional consolidation theory for over-consolidated soils:

$$S_{consol} = \frac{C_r}{1+e_0} \cdot H \cdot \log\left(\frac{\sigma'_v + \Delta \sigma_v}{\sigma'_v}\right)$$

Where S_{consol} = consolidation settlement, Cr and e0 are defined in Table 8 above, H = thickness of compressible layer, $\sigma v'$ = initial vertical stress and $\Delta \sigma v$ = change in vertical stress or load applied. In construction practice, 90% of the consolidation settlement (t90) is often targeted during the construction phase.

On the basis that t90 settlements are achieved during earthworks construction, subsequent post construction settlements were also estimated, which are made up of the remaining 10% consolidation settlement, additional consolidation due to subsequent building loads and secondary creep settlements due to the original fill embankment loads. Creep settlements (S_{creep}) were estimated in accordance with the following relationship:

$$S_{creep} = \frac{C_{\alpha}}{1+e_0} \cdot H \cdot \log\left(\frac{t}{t_l}\right)$$

Where C α and e_0 are defined in Table 8 above, H = thickness of compressible layer, t = design life (50 years), t_l = t₉₀ or construction period, whichever is greatest.

Table 9: Estimated Fill Induced Static Settlements – Southern Gully				
Embankment Height (m)	Construction Settlement (t _{90,} mm)	Additional Settlement due to 20kPa floor load (mm)	Post Construction Settlement (mm)	
1	25	20	30	
3	55	15	35	
5	80	10	40	
Notes: Post construction not include floor lo	settlements made up of secon bad induced consolidation.	idary creep + remaining 10%	% fill induced consolidation, do	
Fill construction us settlements will or	sing available borrow material ccur if using imported rockfill o	s (compacted unit weight = r sand.	18kN/m ³) assumed, greater	

Estimated static settlements are summarised as follows:

The combination of predicted post construction ground settlements and settlements from the anticipated future floor loads are considered as generally appropriate for the proposed development, however specific ground improvement measures may be considered, as discussed in Section 7.2 below, to reduce post construction settlement magnitudes.

6.5.2.3 Time Rate of Settlement

Static settlements are expected to be predominantly elastic (immediate) and are therefore considered to be largely built out during construction, with an estimated time to t₉₀ consolidation of approximately 6 months.

Time rates of settlement are notoriously difficult to estimate due to their depositional environment where there is inherent material composition lateral and depth variability and presence of intermediate sand lenses. Reference to coefficient of vertical consolidation (Cv) laboratory data shows a wide scatter of data although a value of 15m²/year looks to provide a reasonable lower bound estimate for preliminary design purposes.

It is noted that Cv values measured in the lab represent a particularly small volume of soil and can therefore be conservative as they don't take into account thin sand lenses and other discontinuities within the soil mass. Actual settlement timeframes may therefore be less than those tabulated above.

6.5.2.4 Monitoring and Approval

Monitoring of the rate and quantum of settlement must be completed during the construction of the works as described in Section 7.2.3 below. Review of the results and approval is to be described by the Geotechnical Engineer and incorporated into the Geotechnical Completion Report.

6.6 Expansive Soils

Seasonal shrinking and swelling results in vertical surface ground movement which can cause significant cracking of floor slabs and walls. There have been instances of concrete floors and/ or foundations that have been poured on dry, desiccated subgrades in summer months on expansive soils and have undergone heaving and cracking requiring extensive repairs or re-building once the soil moisture contents have returned to higher levels. This hazard is addressed by a combination of careful foundation design and site preparation.

NZS 3604:2011⁶ excludes from the definition of 'good ground', soils with a liquid limit of more than 50% and a linear shrinkage of more than 15% due to their potential to shrink and swell as a result of seasonal fluctuations in water content. For soils exceeding these limits, NZS 3604 has historically referenced AS 2870⁷. for foundation design advice. However the November 2019 update of Acceptable Solution B1/AS1⁸ provides amendments to NZS 3604 that define a method for testing and classifying the soils and provides foundation designs for specific, simple house configurations across the range of expansive soil conditions.

Nevertheless, there is evidence⁹ indicating that the use of the B1/AS1 method of assessment of expansiveness may be inaccurate. Accordingly, our assessments herein have been made in line with our experience, BRANZ Report SR120A¹⁰ and AS2870.

Additional commentary based on our knowledge of this geology and experience with local soils is provided in Section 7.5 below.

6.7 Groundwater Impact Assessment

An assessment has been made of the impact of the proposed works on groundwater conditions in accordance with the requirements of Section E7 of the Auckland Unitary Plan (AuP).¹¹ The assessment has considered the impacts of the proposals for diversion activities and the results are contained in the table presented in *Appendix G*.

6.7.1 69 Trig Road, 151 and 155-157 Brigham Creek Road

Following review of the groundwater levels recorded in the investigation boreholes against the proposed cuts and fills within the above-mentioned earthworks plans, the proposed works within the site are considered to be compliant against the AUP standards E7.6.1.6 and E7.6.1.10.

6.7.2 71 Trig Road

Two hand auger boreholes were drilled inside the southern boundary of the site, in the location of the proposed deepest cuts which range up to 3m depth. The borehole locations are shown on the appended Groundwater Assessment Investigation Location Plan. The hand augers were drilled to depths of 5m below the existing ground surface and then a standpipe piezometer was installed in each hole.

Groundwater monitoring has been undertaken periodically and the results are presented in Table 10 below.

⁶ Standards New Zealand (2011) Timber-framed buildings, NZS 3604:2011, NZ Standard

⁷ Standards Australia Limited (2011) Residential slabs and footings, AS 2870-2011, Australian Standard, NSW

⁸ Ministry of Business, Innovation and Employment (2019) *Acceptable Solutions and Verification Methods for NZ Building Code Clause B1 Structure,* B1/AS1, Amendment 19

⁹ Rogers, N., McDougall, N., Twose, G., Teal, J. & Smith, T. (2020) The Shrink Swell Test: A Critical Analysis, *NZ Geomechanics News*, Issue 99, pages 66-80.

¹⁰ Fraser Thomas Limited (2008) - Addendum Study Report (BRANZ SR120A), Soil Expansivity in the Auckland Region – Final Report

¹¹ Auckland Unitary Plan Operative in Part (Updated 12 June 2020)

Table 10: Groundwater Monitoring Results				
Hand Auger	Groundwater Depth Below Ground Surface (m)			
	Date			
	22/09/2021	01/10/2021	06/10/2021	13/10/2021
HA01-21	0.60	0.64	0.85	0.77
HA02-21	0.50	0.53	0.65	0.44

Following review of the groundwater levels recorded in the investigation boreholes against the proposed cuts and fills, the proposed works within the site are considered to be non-compliant against the AUP standards E7.6.1.6 and E7.6.1.10, and a Groundwater Take and /or Diversion Consent is likely to be required. However, due to the proposed batter slopes adjacent to the site boundary, and the distance from the site boundary of the proposed maximum cuts, we do not anticipate any significant effect on groundwater levels beyond the site boundary. As such, the effects of such a diversion are expected to be negligible.

7 GEOTECHNICAL RECOMMENDATIONS

7.1 Seismic Site Subsoil Category

Based on those ground conditions observed during this investigation, combined with experience working in the surrounding area, the seismic site subsoil category is assessed as being Class C (shallow soil site) in accordance with NZS1170.5.

7.2 Ground Improvement for Static Settlement (69 Trig Road)

7.2.1 Ground Improvement Options

To minimise post construction static ground settlements, a range of options are often considered, including the following:

- Construction of a temporary surcharge or pre-load fill embankment above design finished ground level, to over-consolidate the compressible soils and minimise post construction embankment settlements;
- Use of lightweight geofoam, such as EPS-block materials for embankment construction to keep embankment pressures below pre-consolidation pressures within the compressible soil unit thereby reducing consolidation settlements;
- Undertake ground improvement beneath the embankment footprint, such as stone columns, soil mixed columns, CFA piles, Rammed Aggregate Piers (RAP's) or similar rigid inclusions to transfer loads from the embankment to more competent underlying soils at depth.

7.2.2 Ground Improvement Design

It was expected that pre-loading or surcharging was likely to be the preferred ground improvement technique for this project to reduce post construction static settlements to acceptable magnitudes, in conjunction with underfill drains where appropriate.

Preliminary pre-load designs were carried out using laboratory derived / best estimate consolidation parameters from our database and knowledge of these typical ground conditions across the region.

Resulting creep settlement magnitudes were estimated using the method described in Mesri et al (1994) based on the following:

• Weak alluvium zone – widespread floor loads = 20kPa, post construction settlement ≤ 50mm;

 90% consolidation plus additional consolidation from future 20kPa floor loads achieved during preload.

Based on those requirements, a 1m surcharge above design building platform level across the southern gully fill and adjacent areas where proposed cuts are less than 1m depth were initially recommended. However, as detailed below due to slight changes in proposed earthworks volumes and review of the soil composition on site during earthworks, it was decided that this preload was not necessary.

7.2.3 Settlement Monitoring

The above settlement magnitude and time rate estimates were preliminary and only based on a limited amount of laboratory test data and have been averaged across the length of the project.

It was initially envisaged that regular settlement monitoring would be required during earthworks due to the values recorded above, however full undercutting and removal of the non-engineered fill and particularly soft alluvial soils within the gully alignment was undertaken (as detailed in the earthworks to date Section 8 below) during the earthworks operations. Along with review of the soil composition, and the slight changes in proposed earthworks volumes, it was decided on site during earthworks that settlement monitoring was no longer required.

7.3 Earthworks

7.3.1 General

All earthworks activities must be carried out in general accordance with the requirements of NZS4431 and the requirements of the Auckland Council Infrastructure Development Code under the guidance of a Chartered Professional Geotechnical Engineer.

A Geotechnical Works Specification is provided as **Appendix H** and standard detail drawings are provided as **Drawings 06** to **07**. Between them, these documents provide the requirements for site preparation, fill placement, subsoil drainage, compaction requirements, quality assurance testing and as-built requirements.

Those requirements are summarised below.

7.3.2 Non-Engineered Fill

Uncontrolled existing fills were observed in the southeast corner of 69 Trig Road, the northern portion of 151 Brigham Creek Road and the northern portion of 155-157 Brigham Creek Road. These existing uncertified fills will need to be inspected by the Geotechnical Engineer following site stripping. It is anticipated that the fill will need to be undercut, reworked and placed to engineering standards, due to the presence of buried topsoil beneath the fill and unsuitable inclusions. Once reworked, the fill material should generally be suitable for placement as engineered fill.

7.3.3 Excavatability

Given the stiffness of the units that will be encountered within the proposed earthworks cuts, it is expected that excavation of these materials will be readily achieved with normal earthworks plant, such as scrapers and bulldozers with scoops.

7.3.4 Subgrade Preparation

Preparation of the subgrade beneath the proposed fill areas should comprise stripping of all vegetation, topsoil, any pre-existing fill materials or soft soils followed by benching of the exposed subgrade where natural slopes beneath the fill exceed gradients of nominally 1:5 (vertical to horizontal). The subgrade should then be scarified and moisture conditioned where necessary, and then proof rolled to verify the subgrade stiffness and consistency.

Where any particularly weak materials are encountered that weave excessively during the proof rolling process, they should be undercut and removed prior to placing engineered fill.

7.3.5 Stockpiles

Careful consideration must be given to the location of temporary topsoil / unsuitables stockpiles to ensure that they are not located immediately above steep or unstable slopes or immediately above proposed stormwater pond excavations.

The location of all temporary stockpiles must be approved by the Geotechnical Engineer prior to placement. Where stockpiles cannot be avoided above sloping ground, they should be placed over a wide area with the height restricted under the direction of the Geotechnical Engineer.

7.3.6 Underfill Drainage

Underfill drains will need to be installed beneath new fills within low lying tributaries and gully inverts to allow for the continued release of groundwater seepages.

We have provided approximate positions of the underfill drainage network required for the subdivision works based on existing contour data. Details are in the Geotechnical Works Specification (*Appendix H*), Underfill Drainage Plan (*Drawings 06*) and in the Typical Underfill Drain Detail (*Drawing 07*).

Underfill drain locations should be confirmed onsite by the Geotechnical Engineer, particularly once existing uncertified fill has been removed from the south eastern gully area.

7.3.7 Compaction

Earthfill must be placed, spread and compacted in controlled 250mm to 300mm thick (loose) lifts under the direction of a Geotechnical Engineer. The fill may comprise either granular or cohesive material subject to being free of any organic material and having no particles greater than 150mm diameter.

Most of the proposed cut material, including the natural and existing fill materials should be suitable for reuse as Engineer Certified Fill. Soil textures and moisture contents will however vary widely, and careful management, conditioning and compaction control will be required.

All earthfill must be placed to ensure adequate knitting of successive fill lifts by ripping any natural subgrade or fill surfaces that have become dry prior to placing the following fill lift.

7.3.8 Temporary Sediment Retention Ponds

Temporary sediment retention ponds may be required to store stormwater for significant periods (several months to years) and therefore their construction should be subject to design and observation input from the geotechnical engineer. As a minimum, the following input is recommended from the project geotechnical engineer:

- Advise on pond locations with respect to land stability and seepage potential;
- Structural design of pond fill embankments including key and compaction specification;
- Observe embankment subgrade conditions and advise on undercut requirements;
- Earthfill QA / QC testing of all embankment materials to ensure compliance with specification.

When decommissioning temporary sediment ponds, all water softened material in the bases and sides of the ponds shall be removed and undercut to the satisfaction of the Geotechnical Engineer. Backfilling of temporary ponds shall be to the compaction standard for general filling unless otherwise specified.

7.3.9 Quality Control

The stripping of existing topsoil, cutting of pre-existing fill materials and undercutting of organic soils (if encountered), where required from across the site as well as the gully areas must be subject to observation by the project Geotechnical Engineer to ensure that all unsuitable materials have been removed.

The source and / or type of material used for engineered fill will dictate the type of quality control testing undertaken.

The recommended specification for the proposed development is presented in the Geotechnical Works Specification in *Appendix H*.

The source of the fill should be discussed with and approved by the project Geotechnical Engineer to verify its appropriateness and quality control testing requirements.

7.4 Civil Works

7.4.1 Subgrade CBR

The subdivision roading is shown as being constructed in a combination of both cut and fill areas, although given the requirement to over-excavate exposed rock deposits, the vast majority will be formed in engineered fills. Typical CBR values of between 5% and 6% should be available in fills. In areas of cut natural ground, CBR values as low as 2% or 3% are likely.

As described for the fills, subgrade improvement with lime (if desired) is expected to provide better results than the use of cement due to the clayey nature of the soils.

7.4.2 Service Trenches

All of the materials to be exposed during the excavation of service trenches should be readily removed using an excavator.

Services trenches excavated along contour in areas of steep ground may need to be backfilled with engineered filling and if in natural ground, may require a drain coil in the base of the trench connected to the stormwater system. Identification of critical service lines must be made once drawings are available.

At the completion of the development, Specific Design Zones for services will be applied in the Geotechnical Completion Report to protect future foundations from settlement from poorly compacted trench backfill and to prevent new loads crushing service pipes. This is a restriction on building foundations within the 45 degree zone of influence from pipe inverts as depicted in Auckland Council's drawing SW22 from their Code of Practice for Land Development and Subdivision.

7.4.3 Retaining Walls

Table 11: Retaining Wall Design Parameters				
Soil Unit	Ƴ (kN/m³)	Ø′(deg)	c′ (kPa)	Su (kPa)
Engineered Fill	18	30	5	100
Uncertified Fill	17	27	2	60
Puketoka Formation Alluvium	17	27	2	60
Residual Waitemata Group Soils	18	30	3	70
Waitemata Group Transition Zone	18	30	10	100
Waitemata Group Bedrock	18	40	10	200

Design parameters for permanent retaining walls are summarised in Table 11.

Notes:

1. Refer to Table 2 for definition of soil unit levels

2. Υ – soil unit weight; \emptyset' - angle of internal soil friction; c' – effective cohesion; Su – undrained shear strength.

Table 11: Retaining Wall Design Parameters				
Soil Unit	Ƴ (kN/m³)	Ø′(deg)	c′ (kPa)	Su (kPa)
 The above parameters are based on the condition of a horizontal ground surface behind the retaining structure. Applicable surcharge loads behind the wall must also be considered in the design. 				

During detailed design of the walls, allowance must be made for the additional earth pressure due to the surcharges from structures (i.e. any existing or proposed retaining structures and/or buildings) behind the wall.

Retaining walls should be designed with appropriate toe drainage and be backfilled with free-draining aggregate.

Temporary stability of any site cuts must also be considered in the construction methodology. This work should not be undertaken in poor or unfavourable weather conditions and cuts/excavations should be backfilled as soon as possible.

Careful consideration of underfill drainage locations should be made during retaining wall construction. Underfill drains should be clearly marked out onsite and piles should be positioned to avoid damaging the draincoil.

If any draincoil is intercepted by excavations or building works, it must be reinstated under the direction of a Chartered Professional Engineer to ensure the integrity of the drainage system. Removal of a portion of the drainage scoria is not expected to be problematic provided the draincoil and a quantum of surrounding scoria remains intact.

At the completion of the development, **Specific Design Zones (retaining)** are expected to be applied in the Geotechnical Completion Report to protect retaining walls from future overloading at the crest or undermining at the toe that could lead to instability. These zones typically extend the same distance as the wall height and where they are present above a wall, require deepening of foundations unless the wall has been designed for future foundation loads. Where they are present below a wall, careful consideration needs to be given to location, depth and timing of any future excavations.

7.4.4 Stormwater Soakage

Three falling head tests were carried out at 69 and 71 Trig Road, and 151 Brigham Creek Road, as shown on the appended site plan in *Appendix I*, where test results are also presented.

The falling head percolation testing methodology is in accordance with the Auckland Council Technical Report 2013/040: Stormwater Disposal Via Soakage in the Auckland Region dated October 2016.

Based on test data, we have estimated the percolation rates with the followings methods:

- Ciria 113 Appendix 4, Control of Groundwater for Temporary Works
- Auckland Council Technical Report 2013/040, Stormwater Disposal via Soakage in the Auckland Region.

The percolation rate estimates are summarised in Table 12 below.

Table 12: Percolation Rate Estimates				
Location	Calculation Method	Percolation Rate		
		m/s	mm/hour	
HA01-21	Ciria 113	8.67x10 ⁻⁷	3.12	

	Auckland Council Technical Report	8.46x10 ⁻⁷	3.04
HA02-21	Ciria 113	1.65x10 ⁻⁷	0.59
	Auckland Council Technical Report	5.25x10 ⁻⁷	1.89
HA03-21	Ciria 113	3.51x10⁻ ⁶	12.6
	Auckland Council Technical Report	6.91x10 ⁻⁶	24.9

All of the soils at this site are clayey in nature and have very low coefficients of permeability, particularly in HA01-21 and HA02-21. Accordingly, rain gardens are not expected to provide any significant ground soakage function.

7.5 Foundations

7.5.1 Residential Building Platforms

Once bulk earthworks are completed in accordance with the recommendations provided in Section 7.3 above, a preliminary geotechnical ultimate bearing pressure of 300kPa should be available for shallow strip and pad foundations constructed within both the natural cut ground and engineered fill areas.

There may be areas where localised variations in shear strength within the natural cut ground occur, particularly where the depth of cut varies across the building platforms, and where the depth of excavation exceeds 1.5m so that the stiff overburden crust is significantly reduced or removed. Further confirmation of available bearing pressures will be addressed at the time of post earthworks soil testing and preparation of the Geotechnical Completion Report (GCR) for the development.

NZS3604 recommends that sites with expansive soils are classified according to AS2870 "Residential Slabs and Footings – Construction". AS2870 describes a range of Classes having different levels of characteristic surface movement and provides acceptable foundation solutions for each Class, depending on the construction typology and materials.

While no site specific laboratory testing has been undertaken, on the basis of our visual / tactile assessment we anticipate that the AS2870 Site Class for the development site to be M (moderate) to H1 (high). Foundation design may be selected in accordance with appropriate solutions for this Class from AS2870 or may be undertaken by specific engineering design.

Mitigation of the expansive soil hazard is undertaken by a combination of appropriate foundation design selection at Building Consent stage and appropriate moisture control within subgrade soils during construction. Foundation contractors must be aware of this issue and the need to maintain appropriate moisture contents in the footings and building platform subgrade between the time of excavation and pouring concrete.

7.5.2 Industrial Building Platforms

Due to the presence of softer alluvial deposits underlying the stiffer surficial crust, subsoils may be subject to consolidation settlements due to the proposed loadings from industrial buildings. Site specific investigation and analysis would be required to confirm what settlements may occur based on any particular development proposal, and to develop appropriate ground remediation options as necessary.

7.6 Proposed Bridges and Retaining Walls

As detailed in the proposed development plans outlined in Section 3 above, 2 bridges (with associated abutments) and 7 retaining walls are proposed as part of the subdivision. Based on the investigation to date within this area we are satisfied that the proposed location of this infrastructure is satisfactory provided it is designed appropriately to accommodate the existing ground conditions.

Currently detailed investigation is underway for the proposed retaining wall alignments and bridge locations, and this will be used to support the detailed design of these structures.

8 EARTHWORKS SUMMARY TO DATE

8.1 151, 155 to 157 Brigham Creek Road and 69 Trig Road

The siteworks within Brigham Creek and Trig Road (above addresses) began in September 2020 with the removal of all trees by Treescape, followed by the installation of appropriate sediment controls.

Earthworks began in the 155-157 Brigham Creek Road site in early November 2020. The site stripping and installation of a sediment pond uncovered historic farm drains and uncontrolled fill. The location of Sediment Pond B had to be revised due to the soft soils and uncontrolled fill that was encountered in its initially proposed location.

A large sediment retention pond within Stage 2 of the Trig Road site (south of Brigham Creek, within 157 Brigham Creek Road) was constructed in February 2021 and this subsequently allowed for the site stripping and cut/fill within the Stage 2 area. During the site stripping a number of soft organic areas were encountered and these were appropriately undercut and replaced with engineered fill.

There was a surplus of topsoil on site from the site stripping and this was stockpiled along the western boundary of 69 Trig and was being screened and removed from site at the same time as the site earthworks was being undertaken.

The main gully muck out within Stage 3 of the site (69 Trig Road) began in March 2021. This involved both the muck out of the uncertified fill material (which was encountered during the site investigation and is detailed in this report) and also the installation of a subsoil drain and drainage blanket.

A vertical cut was excavated along the north-eastern boundary of the site during the site stripping in Stage 2 and this area was subsequently remediated with engineered fill placed to a batter gradient of 1(V):3(H) to ensure no instability occurred along this boundary.

The bulk earthworks within Stage 2 was completed in April 2021 and was covered in topsoil. The road gullet within the main proposed road through Stage 2 was cut out and left approximately 200mm above finished level in preparation for the future formation of this road.

The 2021 earthworks season ended in May 2021, and this saw the close out of both 69 Trig and Brigham Creek Road sites for winter. The sediment pond within the main gully of 69 Trig Road had been finished in preparation for the future earthworks season.

Earthworks for the 2022 season restarted in early November 2021 within 69 Trig Road. These works consisted of the ongoing filling within the main gully, extension of the underfill drain/drainage blanket and the site stripping of the remainder of the topsoil within Stage3. An undercut at the toe of the proposed batter within the main gully was observed in late November 2021 and this was to ensure the new batter fills were appropriately benched into the existing ground.

Following the completion of the works within the main gully of 69 Trig Road, earthworks restarted within 155-157 Brigham Creek Road in early February 2022. This involved the stripping of unsuitable material, installation of underfill drainage and bulk filling. These works were undertaken in conjunction with the bulk earthworks within 69 and 71 Trig Road. From late February 2022 works within 69 Trig Road and Brigham Creek were put on hold and all attention was focused within 71 Trig Road as outlined in Section 8.2 below.

8.2 71 Trig Road

The clearing of trees and installation of silt controls were completed in mid-January 2022 in preparation for the start of bulk earthworks.

Following the construction of the sediment pond, bulk earthworks begin in early February 2022. This involved the undercutting of unsuitable material encountered around the existing creek and overland flow path and included the installation of a subsoil drain within an existing drainage channel.

Bulk earthworks within 71 Trig Road continued through to the end of May 2022 when the site was closed up for the winter season. All lots were topsoiled with only the road gullets left open.

9 FURTHER WORK

The recommendations provided in Section 8 above are based on the supplied development plans appended to this report. If development plans change significantly from the current development proposal, the matter should be referred back to CMW or a Chartered Professional Geotechnical Engineer familiar with the contents of this report, who should be given the opportunity to review any changes against recommendations provided within this report.

USE OF THIS REPORT

Site subsurface conditions cause more construction problems than any other factor and therefore are generally the largest technical risk to a project. These notes have been prepared to help you understand the limitations of your geotechnical report.

Your geotechnical report is based on project specific criteria

Your geotechnical report has been developed on the basis of our understanding of your project specific requirements and applies only to the site area investigated. Project requirements could include the general nature of the project; its size and configuration; the location of any structures on or around the site; and the presence of underground utilities. If there are any subsequent changes to your project you should seek geotechnical advice as to how such changes affect your report's recommendations. Your geotechnical report should not be applied to a different project given the inherent differences between projects and sites.

Subsurface conditions can change

Subsurface conditions are created by natural processes and the activity of man. For example, water levels can vary with time, fill may be placed on a site and pollutants may migrate with time. Because a report is based on conditions which existed at the time of subsurface investigation, the conditions may have changed, particularly when large periods of time have elapsed since the investigations were performed.

Interpretation of factual data

Site investigations identify actual subsurface conditions at points where samples are taken. Additional geotechnical information (e.g., literature and external data source review, laboratory testing on samples, etc) are interpreted by geologists, engineers or scientists to provide an opinion about overall site conditions, their likely impact on the proposed development and recommended actions. Actual conditions may differ from those inferred to exist, because no professional, no matter how qualified, can exactly predict what is hidden by earth, rock and time. The actual interface between materials may be far more gradual or abrupt than assumed based on the facts obtained. Nothing can be done to change the actual site conditions which exist, but steps can be taken to reduce the impact of unexpected conditions.

Your report's recommendations require confirmation during construction

Your report is based on the assumption that the site conditions as revealed through selective point sampling are indicative of actual conditions throughout an area. This assumption cannot be substantiated until project implementation has commenced. For this reason, you should retain geotechnical services throughout the construction stage, to identify variances, conduct additional tests if required, and recommend solutions to problems encountered on site. A geotechnical designer, who is fully familiar with the background information, is able to assess whether the report's recommendations are valid and whether changes should be considered as the project develops. An unfamiliar party using this report increases the risk that the report will be misinterpreted.

Interpretation by other design professionals

Costly problems can occur when other design professionals develop their plans based on misinterpretations of a geotechnical report. Read all geotechnical documents closely and do not hesitate to ask any questions you may have. To help avoid misinterpretations, retain the assistance of geotechnical professionals familiar with the contents of the geotechnical report to work with other project design professionals who need to take account of the contents of the report. Have the report implications explained to design professionals who need to take account of them, and then have the design plans and specifications produced reviewed by a competent Geotechnical Engineer.

Appendix A: CMW Drawings

Title	Reference No.	Date	Revision
Site Investigation Plan	AKL2019-0040	06/12/2019	1
Site Investigation Plan	AKL2020-0231	21/09/2020	0
Section A	AKL2019-0040	28/11/2019	1
Section B	AKL2019-0040	28/11/2019	0
Section C	AKL2019-0040	28/11/2019	0
Section D	AKL2019-0040	28/11/2019	0
Underfill Drainage Plan	AKL2019-0040	09/12/2019	0
Typical Underfill Drain Detail	AKL2019-0040	09/12/2019	0



X:\01 PROJECTS\AKL\AKL2019\AKL2019-0001 TO 0050\AKL2019-0040 TRIG AND BRIGHAM CREEK ROAD\07 DRAWINGS\CAD\AKL2019-0040- FIG01 SITE PLAN REV 1.DWG

ON LIMITED	DRAWN:	FMS	PROJECT No: AKL2019-0040	
REEK ROAD	CHECKED:	TG	DRAWING: 01	
	REVISION:	1	SCALE: 1:2500	
ION PLAN	DATE:	06/12/2019	SHEET: A3	



C:\USERS\WINNIEPJ\CMW GEOSCIENCES PTY LTD\CMW CONNECT - AKL\2020\AKL2020-0231 71 TRIG ROAD, WHENUAPAI\DRAWINGS\AKL2020-0231 SI PLAN REVA.DWG

ON LIMITED	DRAWN: WPJ	PROJECT No: AKL2020-0231	
AD,	CHECKED: JW	DRAWING: 01	
AI	REVISION: 0	SCALE: 1:1500	
ION PLAN	DATE: 21/09/2020	SHEET: A3	



DN LIMITED	DRAWN: FMS	PROJECT No: AKL2019-0040
REEK ROAD	CHECKED: TG	DRAWING: 02
	REVISION: 1	SCALE: 1:500
A	DATE: 28/11/2019	SHEET: A3



SITE BOUNDARY	150 155		
ON LIMITED	DRAWN: FMS	PROJECT No: AKL2019-0040	
ON LIMITED	CHECKED:	DRAWING:	
CREEK ROAD	TG REVISION: 0	03 SCALE: 1:500	
P	DATE: 28/11/2010	SHEET:	
в	28/11/2019	A3	



N LIMITED	DRAWN: FMS	PROJECT No: AKL2019-0040
REEK ROAD	CHECKED: TG	DRAWING: 04
	REVISION: 0	SCALE: 1:500
c	DATE: 28/11/2019	SHEET: A3


DRAWN: FMS	PROJECT No: AKL2019-0040
CHECKED: TG	DRAWING: 05
REVISION: 0	SCALE: 1:500
DATE: 28/11/2019	SHEET: A3
	DRAWN: FMS CHECKED: TG REVISION: 0 DATE: 28/11/2019



X:01 PROJECTS\AKL\AKL2019\AKL2019-0001 TO 0050\AKL2019-0040 TRIG AND BRIGHAM CREEK ROAD\07 DRAWINGS\CAD\AKL2019-0040- FIG01 SITE PLAN REV 1.DWG

ON LIMITED	DRAWN:	FMS	PROJECT No: AKL2019-0040
	CHECKED:	TG	DRAWING: 06
REEK ROAD	REVISION:	0	SCALE: 1:2500
IAGE PLAN	DATE:	09/12/2019	SHEET: A3



ON LIMITED	DRAWN:	FMS	PROJECT: AKL2019-0040
	CHECKED:	TG	DRAWING: 07
REEN ROAD	REVISION:	0	SCALE: NTS
DRAIN DETAIL	DATE:	09/12/2019	SHEET: A3

Appendix B: Supplied Development Plans





en	TBC	SURVEYED			-	-
		DESIGNED		N	A.Chen	17/09/2021
		DRAWN			B.Nel	13/07/2022
		DATE	ORIGINAL SCALE		ORIGIN	AL SIZE
		13/07/2022	1:30	00		A3
FNT		DRAWING NO.	1915 ND (20	nn	REVISION
		44	1312-DK-C	-20	00	А



PLANNERS | SURVEYORS | ENGINEERS ARCHITECTS | ENVIRONMENTAL

or amended without the written permission of Cato Bolam Consultants Ltd. No liability shall be accepted for unauthorised use of this drawing and design.



NSENT						
		13/07/2022	1:1000		A3	
		DATE	ORIGINAL SCALE	ORIGI	NAL SIZE	
		DRAWN		B.Nel	13/07/2022	
		DESIGNED		M.Chen	17/09/2021	
M.Chen	TBC	SURVEYED		-	-	
NAME	DATE			NAME	DATE	



creating great places PLANNERS | SURVEYORS | ENGINEERS ARCHITECTS | ENVIRONMENTAL

This drawing and design remains the property of, and may not be reproduced or amended without the written permission of Cato Bolam Consultants Ltd. No liability shall be accepted for unauthorised use of this drawing and design. Neil Construction Limited Brighams Creek Road Whenuapai

Finished Contour Enlarged Layout Plan Sheet 2

C:\12dS	ynergy\Workspace\data	\CATOAPP1\44315-N	Neil Construction Limited_61309\Techi	nical\Drawings\44315-DR-C-	2000-2005 - Proj	posed Contours Plans
ION (DESCRIPTIONS)	NAME	DATE			NAME	DATE
For Resource Consent	M.Chen	TBC	SURVEYED		-	-
			DESIGNED		M.Chen	17/09/2021
			DRAWN		B.Nel	13/07/2022
			DATE	ORIGINAL SCALE	ORIGI	NAL SIZE
.C	K		13/07/2022	1:100	0	A3
			DRAWING NO.	.		REVISION
FOR RESOURCE CONSENT			44	2002	A	









or amended without the written permission of Cato Bolam Consultants Ltd. No liability shall be accepted for unauthorised use of this drawing and design.





creating great places PLANNERS | SURVEYORS | ENGINEERS ARCHITECTS | ENVIRONMENTAL

This drawing and design remains the property of, and may not be reproduced or amended without the written permission of Cato Bolam Consultants Ltd. No liability shall be accepted for unauthorised use of this drawing and design.

Neil Construction Limited Brighams Creek Road Whenuapai

Finished Contour Enlarged Layout Plan Sheet 4





NSENT		4	4315-DR-C-2	004	A
			1.1000		
		13/07/2022	1.1000		۵3
		DATE	ORIGINAL SCALE	ORIGI	NAL SIZE
		DRAWN		B.Nel	13/07/2022
		DESIGNED		M.Chen	17/09/2021
M.Chen	TBC	SURVEYED		-	-
NAME	DATE	1	(NAME	DATE
\Workspace\data	CATOAPP1\44315-	Neil Construction Limited_61309\Tech	nical\Drawings\44315-DR-C-20	00-2005 - Proj	oosed Contours Plans
	/	[
	Ť				





This drawing and design remains the property of, and may not be reproduced or amended without the written permission of Cato Bolam Consultants Ltd. No liability shall be accepted for unauthorised use of this drawing and design. leil Construction Limited Brighams Creek Road Whenuapai

Finished Contour Enlarged Layout Plan Sheet 5



 DRAWN
 B.Nel

 DATE
 ORIGINAL SCALE
 ORIG

 13/07/2022
 1:1000
 DRAWING NO.

 DRAWING NO.
 44315-DR-C-2005

 B.Nel
 13/07/2023

 ORIGINAL SIZE
 0

 0
 A3

 2005
 A





NSENI		44315-DR-C-2100		-2100	A
		DRAWING NO.			REVISION
		15/07/2022	1:30	00	A3
		DATE	ORIGINAL SCALE	ORIGI	NAL SIZE
		DRAWN		S.Baby	15/07/2022
		DESIGNED		M.Chen	17/09/2021
M.Chen	TBC	SURVEYED		-	-
NAME	DATE			NAME	DATE



ARCHITECTS | ENVIRONMENTAL

ynergy\Workspac	e\data\CATOAPP1\4	4315-Neil Construction Limited_61309	NTechnical\Drawings\44315-D	R-C-2100 - Pro	posed Cut to Fill Plan
NAME	DATE			NAME	DATE
M.Chen	TBC	SURVEYED		-	-
		DESIGNED		M.Chen	17/09/2021
		DRAWN		S.Baby	15/07/2022
		DATE	ORIGINAL SCALE	ORIGI	NAL SIZE
		15/07/2022	1:1000		A3
		DRAWING NO.	DRAWING NO.		
NSENT		44315-DR-C-2101			Α



PLANNERS | SURVEYORS | ENGINEERS ARCHITECTS | ENVIRONMENTAL

This drawing and design remains the property of, and may not be reproduced or amended without the written permission of Cato Bolam Consultants Ltd. No liability shall be accepted for unauthorised use of this drawing and design. Whenuapai

Sheet 2



NSENT		DRAWING NO.	1315-DR-C	-2102	revision A
		15/07/2022	1:10	00	A3
		DATE	ORIGINAL SCALE	ORIGI	NAL SIZE
		DRAWN		S.Baby	15/07/2022
		DESIGNED		M.Chen	17/09/2021
M.Chen	TBC	SURVEYED		-	-
NAME	DATE			NAME	DATE











creating great places PLANNERS | SURVEYORS | ENGINEERS ARCHITECTS | ENVIRONMENTAL

This drawing and design remains the property of, and may not be reproduced or amended without the written permission of Cato Bolam Consultants Ltd. No liability shall be accepted for unauthorised use of this drawing and design.

Neil Construction Limited Brighams Creek Road Whenuapai

Finished Cut to Fill Enlarged Layout Plan Sheet 4





INSENI		44	1315-DR-C-2	2104	Α
		DRAWING NO.			REVISION
		15/07/2022	1:1000)	A3
		DATE	ORIGINAL SCALE	ORIGI	NAL SIZE
		DRAWN		S.Baby	15/07/2022
		DESIGNED		M.Chen	17/09/2021
M.Chen	TBC	SURVEYED			
NAME	DATE	1		NAME	DATE
ynergy\Workspace	data\CATOAPP1	14315-Neil Construction Limited_61309	\Technical\Drawings\44315-D	0R-C-2100 - Pro	posed Cut to Fill Plan
	\mathbf{i}				
	j	\sim			
	9 :1+				

auriRoad





This drawing and design remains the property of, and may not be reproduced or amended without the written permission of Cato Bolam Consultants Ltd. No liability shall be accepted for unauthorised use of this drawing and design. Brighams Creek Road Whenuapai

Enlarged Layout Plan Sheet 5









This drawing and design remains the property of, and may not be reproduced or amended without the written permission of Cato Bolam Consultants Ltd. No liability shall be accepted for unauthorised use of this drawing and design.







This drawing and design remains the property of, and may not be reproduced or amended without the written permission of Cato Bolarn Consultants Ltd. No liability shall be accepted for unauthorised use of this drawing and design. Neil Construction Ltd 151,155-157 Brigham Creek Road 69 & 71Trig Road, Whenuapai

Sediment and Erosion Control Plan Sheet 3 of 3

FOR RESOURCE CONS

No. REVISION (DESCRIPTIONS)

A Issued For Resource Consent

	drawing no. 44315-DR-C-2202			REV	ISIOI	١	
	20/07/2022	1:20	00				43
	DATE	ORIGINAL SCALE		ORIGIN	IAL S	IZE	
	DRAWN			M.Chen	2	20/07	/2022
	DESIGNED			M.Chen	2	20/07	/2022
07/2022	SURVEYED			-			
DATE				NAME		DA	TE
	DATE 07/2022	DATE 07/2022 SURVEYED DESIGNED DRAWN DATE 20/07/2022 DRAWING NO.	DATE 07/2022 SURVEYED DESIGNED DRAWN DATE ORIGINAL SCALT 20/07/2022 1:20 DRAWING NO.	DATE 07/2022 SURVEYED DESIGNED DRAWN DATE 20/07/2022 1:2000 DRAWING NO.	DATE NAME 07/2022 SURVEYED - DESIGNED M.Chen DRAWN M.Chen DATE ORIGINAL SCALE ORIGIN 20/07/2022 1:2000 -	DATE NAME 07/2022 SURVEYED - DESIGNED M.Chen 2 DRAWN M.Chen 2 DATE ORIGINAL SCALE ORIGINAL SCALE DATE 01/2022 1:2000 DRAWING NO. REV	DATE NAME DA 07/2022 SURVEYED - - DESIGNED M.Chen 20/07 DRAWN M.Chen 20/07 DATE ORIGINAL SCALE ORIGINAL SIZE 20/07/2022 1:2000 M

Appendix C: Investigation Data

BOREHOLE LOG - HA01-19



	orei				SILE	piai										20		Sheet 1 01 1
	oggeo hecke	d by: JN ed by: T	IJ G	Position: Survey S	E. Source	.174 e:	524	8.4m N.5925965.4m Measured onsite	Elevatior Datum:	n: NZ	RL 20 TM	6.00)m		H A	lole Ingle	Diam e from	ieter: 50mm n horizontal: 90°
Well	Groundwater	Samp	oles & Insitu Test Type & Resu	s Ltr (m) Lts	Depth (m)		Graphic Log	Material Description Soil: Soil symbol; soil type; colour; structure; bedding; sensitivity; additional comments. (origin/geological Rock: Colour; fabric; rock name; additional comments. (orig unit)	plasticity; l unit) gin/geological	Moisture Condition	Consistency/ Relative Density	Recovery	Drilling Method/ Support	E (E	Dynam Penetr Blows/ 5 1	ic Co romet 100m] 0	ne er im) 15	Structure & Other Observations Discontinuities: Depth; Defect Number; Defect Type; Dip; Defect Shape; Roughness; Aperture; Infili; Seepage; Spacing; Block Size;
				26.0 25.8				OL: TOPSOIL CL: Gravelly CLAY: brown and orange. Low plast (Fill)	ticity.		Ľ							Block Shape; Remarks
		0.4	Peak = UTF							D to M	н							-
		0.8	Peak = UTF	>	1			at 0.90m, with trace topsoil.					HA					
		1.2	Peak = 204+k	Pa 24.6	;			GC: GRAVEL with some clay: black and grey.		м								
		1.0	Pock - LT	,			•••	(Fill)			MD							-
	24.6 1.6 Peak = UTP 2 - 3 - 4 -							Borehole terminated at 1.6 m										
					5	-												
Torr	ninati		on: Un	able to r			Fur	ther							<u> </u>	1	1	<u> </u>
Ren	narks:	Ground	dwater not e	able to F	ed.	ate	run	urer										
			This report is	s based	on the	e atta	ache	ed field description for soil and rock, CMW G	Geoscience	s - Fie	eld Lo	ggiı	ng Gu	iide,	Revi	sion	3 - A	pril 2018.

BOREHOLE LOG - HA02-19



necked by:	TG	Survey S	Sourc	1740. ce:	Measured onsite	Datum: N	NZT	M				A	Angle	e fron	n horizontal: 90°
Sa Depth	mples & Insitu Tes	ts (E) JIts	Death (m)	Graphic Log	Material Description Soii: Soii symbol: soii type; colour; structure; bec sensitivity; additional comments. (origin/geo Rock: Colour; fabric; rock name; additional comment unit)	lding; plasticity; logical unit) s. (origin/geological	Condition	Consistency/ elative Density	Recovery	rilling Method/ Support	E (E	ynam Penetr Blows/	nic Co romet /100m] 10	ne er im) 15	Structure & Other Observation Discontinuities: Depth; Defec Number; Defect Type; Dip; Defi Shape; Roughness; Aperture; Ir Seepage: Spacing: Block Siz
		18.0)		OL: TOPSOIL			ς Ψ.		٥					Block Shape; Remarks
0.4	Peak = 217+	17.7 kPa	,		CL: CLAY with some silt: dark brown, grey n orange. Low plasticity. (Fill)	nottled		н							
0.8	Peak = 124 Residual = 5	(Pa 3kPa	1			м	1	VSt							-
1.2	Peak = 56k Residual = 3	Pa 16.8 5kPa	3		CH: CLAY: grey streaked blackish brown. H (Puketoka Formation) from 1.20m to 1.40m, organic stained with inclusions.	ligh plasticity.	to /	St							
1.6	Peak = 46k Residual = 2	Pa 3kPa			at 1.50m, with trace fine sand.	w	,								
2.0	Peak = 28k Residual = 1	16.1 Pa 5kPa 15.9	2		OH: CLAY: blackish grey. High plasticity. Wi decomposing wood inclusions. (Puketoka Formation) CH: CLAY: grey streaked blackish brown. H (Puketoka Formation)	ith fibrous,		F							
2.4	Peak = 40k Residual = 2	Pa 3kPa				W I S	to			НА					
2.8	Peak = 62k Residual = 1	Pa 5kPa	3				-	St							
3.2	Peak = UT	P 14.8	3		SM: Sandy SILT with minor clay: grey. Low is fine grained. (Waitemata Group)	plasticity. Sand									
3.6	Peak = 124 Residual = 5	⊱a 4kPa 14.3	5		CH: CLAY with minor fine sand: grey. High (Waitemata Group)	plasticity.		VSt							
4.0	Peak = 96k Residual = 5	Pa 9kPa	4					St							
4.4	Peak = 186i Residual = 6	(Pa 5kPa				wi S	to								
4.8	Peak = 112 Residual = 5	:Pa)kPa						VSt							

BOREHOLE LOG - HA03-19



	orer				site	pian									.20		Sheet I OF I
	oggeo	d by: RE		Position:	E	.17453	16.0m N.5926078.6m	Elevation	n: N7	RL 2	6.00	Dm			Hole Angl	e Diar	neter: 50mm
	HECK		6 ·	Survey C		.	measured onsite	Datum.			1	5		Dvnar	nic C		Structure & Other Observations
Well	undwater	Samp	oles & Insitu Test	" "	(m)	phic Log	Material Description Soil: Soil symbol; soil type; colour; structure; bedding; sensitivity; additional comments. (origin/geological	plasticity; I unit)	oisture	sistency/ ve Densit	scovery	g Method upport	(Pene Blows	trome /100r	eter mm)	Discontinuities: Depth; Defect Number; Defect Type; Dip; Defect
	Grot	Depth	Type & Resu	ts	B	Gra	unit)	igin/geological	Ξŏ	Con Relati	l w	Drillin S		5 	10 I	15 	Snape; Roughness; Aperture; Infili; Seepage; Spacing; Block Size; Block Shape: Remarks
				26.0		-	OL: TOPSOIL									+	
				25.7					_								
		0.4	Peak = 77kP	a		F	CH: CLAY with minor silt: light grey streaked oral plasticity.	nge. High		St							-
			Residual = 23	(Pa		<u>+</u>	(Puketoka Formation)										-
						F											
			Deale ACCU			F											
		0.8	Residual = 65	va 25.2 KPa		F	CH: CLAY with minor silt trace fine sand: light gre streaked orange. High plasticity.	еу									
					1	£	(Puketoka Formation)										
				24.9		F	CL: CLAY with some silt trace fine sand: grey mo	ottled	-								
		1.2	Peak = 170k	Pa (Pa		<u>+</u>	orange. Low plasticity.	Stilea									-
			Residual – TT	u a		£											
						ŧ											
		16	Peak = 124ki	2		1			м	VSt							-
		1.0	Residual = 65	Pa		<u></u>			IVI	VOL							-
						1											
						1											
		2.0	Peak = 103k Residual = 62	Pa KPa	2	+										-	
						±											-
				23.8			CL: Clayey SILT with minor fine sand: whitish gre	ey mottled									
		2.4	Peak = 93kP	a			(Puketoka Formation)										-
			Residual = 59	«Ра								НА					-
																	-
		2.8	Peak = 77kP Residual = 46	a kPa													-
		3.2	Peak = 93kP	a													-
			Residual = 54	<pa< td=""><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td><td></td></pa<>													
										St							
																	-
		3.6	Peak = 77kP Residual = 62	a kPa													
									vv								
		4.0	Peak = 77kP	a	4											-	
			Residual - 44	Та													-
		4.4	Deak = 12/k	2													
			Residual = 46	Pa													-
									W to								
										VSt	1						
		4.8	Peak = 100k Residual = 50	Pa kPa							1						
					_												
					5	-	Borehole terminated at 5.0 m				-						-
Terr	ninati	on reas	on: Tar	get Dep	th Re	ached											
Ren	narks	Ground	dwater not er	ncounter	ed.												
			This report is	based	on the	e attach	ed field description for soil and rock, CMW G	Geoscience	es - Fi	eld Lo	oggi	ng Gι	iide,	Rev	visio	n 3 - /	April 2018.

BOREHOLE LOG - HA04-19



				Position			174516	52 1m N 5026000 1m	Elovation	. .		0 50)m				Diam	otor: 50mm
	ogged beck	a by. Jiv ad by: T	1J	SURVAV	Soi		17451:	Measured onsite		I. N7	KL J TM	0.50	711			ule i nale	from	borizontal: 90°
		50 Dy. 1	0	Survey	1				Datum.			1	5	Dvr	nami	c Cor	non	Structure & Other Observations
	ater	Sam	oles & Insitu Tes	sts		Ê	Log	Material Description	plaatioit/:	e G	ncy/ ensit	2	thod	Per	netro	omete	er	Discontinuition: Donth: Defect
Well	Mpur					pth (phic	sensitivity; additional comments. (origin/geologica	l unit)	oistu inditi	siste ve D	COVE	g Me	(BIO	ws/1	UUIII	(II)	Number; Defect Type; Dip; Defect
	Grot	Depth	Type & Res	ults		De	Gra	Rock: Colour; fabric; rock name; additional comments. (or unit)	igin/geological	žΰ	Con	R R	UIII.	5	10	0 1	5	Shape; Roughness; Aperture; Infill; Seepage; Spacing; Block Size;
				30	5						<u> </u>	-	-		\dashv			Block Shape; Remarks
				30	2			CH: CLAX with minor silt: orange. High plasticity										
		0.4	Peak = 160	kPa			<u></u>	(Puketoka Formation)										
			Residual = 3	5kPa		_	=											-
							£-	at 0.60m, becoming light grey with grange stre	ake									
							<u> </u>	at 0.00m, becoming light grey with orange site	ans.									
		0.8	Peak = 204+	kPa			<u>1-</u>											
				29	6		<u>L</u>											
						1 -		(Puketoka Formation)							_			
		1.2	Peak = 175	kPa		•	<u>ŕ </u>											
			Residual = 8	8kPa														
							<u>×</u>											
							×_×											
		1.6	Book = 152	k Bo														
		1.0	Residual = 10	02kPa			Ê×											
							¥,											
							<u>1</u> ––				vSt							
				_			<u>+</u> ×_×											
		2.0	Peak = 143 Residual = 11	kPa I4kPa		2 -	<u> </u>	at 2.00m, becoming with pinkish staining.										-
							+											
							<u>×–</u>											
		2.4	Peak = 160 Residual = 11	kPa I7kPa		•	<u>×_</u>											
						-				м			HA					-
							$+ \times$											
		2.8	Peak = 140	kPa 3kPa														
			i tesiddai - 5	27	6			CH: Silty CLAY: dark brownish grey with pink an	d orange	-								
						3 —	×_×	streaks. High plasticity.	Ū						-			
								(Fukeloka Formation)										
		3.2	Peak = 111	kPa 27	3		E×	CH: Silty CLAY: light pinkish orange. High plastig	city.									
			Residual = 7	экга			$+ - \times$	(Puketoka Formation)										
							<u>×–</u>											
						-	<u> </u> ××											-
		3.6	Peak = 99k	Pa			<u> </u>	at 3.60m, becoming light brown with orange st	tainina									
1			Residual = 8	zkPa				at electrin, seconding light brown with ordinge st	y.									
1							$\frac{1}{1}$											
1							1×]											
		4.0	Peak = 85k	:Pa		4 —	<u>×_</u> ^								_			
			Residual = 7	3kPa			××											
							Ê×				St							
		4.4	Peak = 82k	Pa														
			Residual = 7	0kPa			<u> </u>											-
1							<u>*</u> _*											:
1							<u> </u>											
1		4.9	Peak = 79k	Pa														
		0	Residual = 5	8kPa			<u> </u>											
							<u> </u>						L					
						5 -	-	Borehole terminated at 5.0 m				-				_		
Terr	ninati	on reas	on: Ta	arget De	oth	Rea	ched					-						
1																		
Ren	narks	Groun	dwater not e	encounte	red	1.												
1			T 1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.1.														<u>.</u>	
1			I his report	is based	on	the	attach	ied field description for soil and rock. CMW (Jeoscience	es - Fi	eid Lo	baai	ng Gu	lide, Re	evis	sion	3 - A	Jorii 2018.

BOREHOLE LOG - HA05-19



	.ogge	d by: JN	1J	Positio	n:	E.1	74522	27.8m N.5926193.3m	Elevation	1:	RL 2	8.00)m		F	lole	Dian	neter: 50mm
c	heck	ed by: T	G	Survey	So	urce:		Measured onsite	Datum:	NZ	ТМ				A	ngle	e fron	n horizontal: 90°
=	Iwater	Sam	ples & Insitu Tes	ts	Ê	(m) r	c Log	Material Description Soil: Soil symbol; soil type; colour; structure; bedding;	; plasticity;	ture ition	tency/ Density	very	Aethod/ oort	D F (B	ynam Peneti Iows/	nic Co romet 100m	ne er ım)	Structure & Other Observations Discontinuities: Depth; Defect
Ň	Ground	Depth	Type & Res	ilts	r F	Dept	Graph	Rock: Colour; fabric; rock name; additional comments. (or unit)	ai unit) rigin/geological	Mois Cond	Consis Relative	Reco	Drilling P Supl	5	; 1] 0 	15 	Shape; Roughness; Aperture; Infill; Seepage; Spacing; Block Size; Block Shape; Remarks
				28	3.0	-		OL: TOPSOIL										
						-				D to M								
				27	7.7			CL: CLAY: orange. Low plasticity.										
		0.4	Peak = UT	Р		-		(Puketoka Formation)										
						-												-
						-												
		0.8	Peak = 190k Residual = 12	Pa 0kPa		1												
				ond d		-												
						1 -												-
		1.2	Peak = 175k	Pa		-												
			Residual = 13	1kPa		-												
						-												
		1.6	Peak = 196k	Pa 26	5.4	-												-
			Residual = 16	0kPa			×	(Puketoka Formation)	licity.									
						-	×			М	VSt							
		2.0	Peak = 143k	Pa 26	5.1	2		ML: Clayey SILT : greyish white. Low plasticity. behavior.	No dilatant									
			Residual = 8	ikPa			XXX	(Puketoka Formation)										
						-												
		24	Book = 114k	Po		-	X X X X X X											
		2.4	Residual = 50)kPa		-	$\times \times$						НА					
						-												
		2.8	Peak = 117k Residual = 44	Pa IkPa		-												
						3 —	×××											
						-	$(X \times X)$											
		3.2	Peak = 128k Residual = 90	Pa)kPa		-	$\times \times$											
				24	+./	-	×	CH: Silty CLAY: light whitish orange. (Puketoka Formation)										
						-	×											
		3.6	Peak = 67k Residual = 44	Pa IkPa		-	×											
						-	×_ ×				St							
				24	¥.1	-	×	CL: Silty CLAY with trace fine sand: light orange	e. Low									
		4.0	Peak = 111k Residual = 73	Pa 8kPa		4 -	××	plasticity. Sand is completely weathered siltston (Waitemata Group)	ne.									
							×			w								
						-	××											
		4.4	Peak = 105k Residual = 6	Pa /kPa		-	× ×				St to							
			i tooladai o	ia a		-	×				VSt							-
						-	××											
		4.8	Peak = 99k	Pa		-	××											
			Residual = 6	кга		-												
	-					5 _	¥	Borehole terminated at 5.0 m				_						-
Teri	minati	on reas	on: Ta	rget De	pth	Read	ched											
Ren	narks	Groun	dwater not e	ncounte	erec	d.												
			This report i	s based	d or	the a	attach	ed field description for soil and rock, CMW	Geoscience	s - Fi	eld Lo	oggi	ng Gı	iide, f	Revi	sion	3 - A	April 2018.

BOREHOLE LOG - HA06-19



		bv: JN		Position:	E	.17450	97.1m N.5926241.7m	Elevatior	ו:	RL 2	7.00)m		 	Hole	Dian	neter: 50mm
c	hecke	ed by: T	G	Survey S	ourc	e:	Measured onsite	Datum:	NZ	ТМ				A	Angle	e fror	n horizontal: 90°
	vater	Sam	oles & Insitu Tes	ts c	Ê	Log	Material Description Soil: Soil symbol: soil type: colour: structure: bedding:	: plasticity:	ion	ency/ bensity	ery	ethod/	D F (B	ynam eneti	nic Co romet	ne er	Structure & Other Observations Discontinuities: Depth: Defect
Wel	Groundv	Depth	Type & Resi	ults	Depth	Graphic	sensitivity; additional comments. (origin/geologica Rock: Colour; fabric; rock name; additional comments. (or unit)	al unit) rigin/geological	Moistu Condit	Consiste Relative D	Recov	Drilling M. Suppo	5	i 1] 10 	15 	Number; Defect Type; Dip; Defect Shape; Roughness; Aperture; Infill; Seepage; Spacing; Block Size; Block Shape: Remarks
				27.0			OL: TOPSOIL										
									D to								
		0.4	Peak = 204+	26.7 kPa			CL: CLAY: light brownish grey with orange strea plasticity.	iks. Low	M								
							(Puketoka Formation)										-
							at 0.60m, becoming moist and high plasticity.										
		0.8	Peak = 178k Residual = 82	Pa 2kPa													
					1	-E				VSt							
		1.2	Book = 117k	Po			-										
		1.2	Residual = 82	2kPa													
						<u>+</u>	-		м								_
		1.6	Peak = 102k Residual = 6	:Pa IkPa			-										
							-										
		2.0	Peak = 90k Residual = 6	Pa IkPa	2		-										-
						1											
		2.4	Peak = 88k	24.7 Pa			CH: Silty CLAY: dark brown with orange streaks plasticity.	. High									
			Residual = 4	кра						St		HA					-
						×			M to W								
		2.8	Peak = 90k Residual = 4	Pa ⁄kPa													
	_				3												-
		3.2	Peak = 175k	23.9 Pa		-×	CH: Silty CLAY: dark grey. High plasticity. (Waitemata Group)	· · · · · · · · · · · · · · · · · · ·									
			Residual = 96	6kPa													
																	-
		3.6	Peak = 178k Residual = 11	:Pa 1kPa													
										VSt							
		4.0	Peak = 181k	Pa	4												
			Residual = 11	1kPa					w								
		4.4	Peak = 204+	kPa													
																	-
		4.0	Deek = 204	1/De						н							
		4.0	Peak = 204+	кра													
	-				5	-	Borehole terminated at 5.0 m				L						
Terr	ninati	on reas	on: Ta	rget Dep	th Re	eached											
Ren	narks:	Ground	dwater enco	untered a	at 3.1	m											
			This report i	s based	on th	e attac	hed field description for soil and rock. CMW (Geoscience	s - Fi	eld La	ogai	ng Gi	uide. F	Revi	ision	3 - /	April 2018.

BOREHOLE LOG - HA07-19

Client: Neil Group Limited Project: Trig & Brigham Creek Road Site Location: Whenuapai Project No.: AKL2019-0040 Date: 18/03/2019 Borehole Location: Refer to site plan



1:25 Sheet 1 of 1 Logged by: RD E.1745366.0m N.5926247.1m Position: RI 24 50m Flevation: Hole Diameter: 50mm Checked by: TG Survey Source: Angle from horizontal: 90° Measured onsite Datum: N7TM Structure & Other Observations Consistency/ Relative Density Drilling Method/ Support Dynamic Cone Penetrometer Samples & Insitu Tests Material Description _og Moisture Condition Ē Recovery Soil: Soil symbol; soil type; colour; structure; bedding; plasticity; sensitivity; additional comments. (origin/geological unit) Rock: Colour; fabric; rock name; additional comments. (origin/geological unit) Ê (Blows/100mm) Discontinuities: Depth: Defect Graphic L Well Number; Defect Type; Dip; Defect Shape; Roughness; Aperture; Infill; Seepage; Spacing; Block Size; Block Shape; Remarks Ground Depth Ч 10 15 5 Depth Type & Results 24 5 OL: TOPSOIL 24 3 CH: CLAY: orange. High plasticity. (Puketoka Formation) 0.4 Peak = 217+kPa at 0.40m, becoming light grey streaked orange. 0.8 Peak = 217+kPa 1 М /St to Peak = 217+kPa 1.2 23.0 CL: Silty CLAY with minor fine sand: light grey streaked Peak = UTP orange. Low plasticity. 1.6 (Puketoka Formation) 2.0 Peak = >209kPa 2 Residual = 77kPa 22.4 CH: CLAY with minor silt: orange streaked light grey. High plasticity (Puketoka Formation) 2.4 Peak = 87kPa Residual = 47kPa НА M to W 2.8 Peak = 72kPa Residual = 46kPa ▼ 3 21.4 CH: CLAY with minor silt and minor fine sand: orange 3.2 Peak = 77kPa Residual = 41kPa brown. High plasticity. (Puketoka Formation) St 21.1 CL: CLAY with some fine to medium sand: orange and grey. Low plasticity. (Puketoka Formation) Peak = 66kPa Residual = 43kPa 3.6 W to 4.0 Peak = 118kPa 4 Residual = 38kPa 20.4 ML: Clayey SILT with minor fine sand: grey. Low plasticity. Dilatant. (Puketoka Formation) 20.2 ML: Sandy SILT: grey. Low plasticity. Sand is fine to medium grained Peak = 155kPa Residual = 65kPa 4.4 (Waitemata Group) VSt 4.8 Peak = 190kPa Residual = 87kPa 5 Borehole terminated at 5.0 m Termination reason: Target Depth Reached Remarks: Groundwater encountered at 3.0m. This report is based on the attached field description for soil and rock, CMW Geosciences - Field Logging Guide, Revision 3 - April 2018.

BOREHOLE LOG - HA08-19



							17450	20.0m N 5000005 4m	Elevetier			0 50			1.	20	D:	
	oggeo	a by: JM	G I	Positio	ו: פס	E.1	174523	32.3m N.5926335.4m	Elevation	ר: אס	RL 2	2.50	m		H A	nala	Diam	ieter: 50mm
F	TIECK	Suby. 1	0	Survey	1	uice.		measured onsite	Datum.				~		vnam	in Co		Structure & Other Observations
	ater	Samp	oles & Insitu Tes	ts		Ê	Cog	Material Description	nlastisitu	e u	ncy/	≥	thod	P	enetr	omete	er	Discentiouities: Denthy Defect
Well	Mpur					pth (ohic	sensitivity; additional comments. (origin/geologica	l unit)	oistur	sister /e D	cove	g Me	(В	IOWS/	100m]	m)	Number; Defect Type; Dip; Defect
	Grot	Depth	Type & Resi	ilts	2	De	Grag	Rock: Colour; fabric; rock name; additional comments. (ori unit)	igin/geological	ž₿	Conselativ	l a	Nillin Sullin	5	1	0 1	15	Shape; Roughness; Aperture; Infill; Seepage; Spacing; Block Size;
	_			2			V////				Ξ. Ω							Block Shape; Remarks
				24				OL: TOPSOIL										
				22	2.3													
							<u>+_</u> -	CL: Silty CLAY: light whitish grey with orange str plasticity.	eaks. Low									-
		0.4	Peak = 204+	Pa		-		(Puketoka Formation)										-
		0.1	1000 2011			-	<u> </u>											
										D to								-
							L-1			м								
			Deel. 004.			-	<u>}</u>											-
		0.8	Peak = 204+	кРа		-												
							<u>-</u>											
						1 -	F-1											
						-	t											
		1.2	Peak = 187k Residual = 82	Pa kPa				at 1.20m, becoming moist and highly plastic.										-
							上 二											
							<u>+</u>											:
						_	<u> </u>											-
		1.6	Peak = 111k	Pa		-	<u>L-</u>											-
			Residual = 6	kPa		-	<u>-</u>											
							<u> </u>											-
		2.0	Peak = 111k	Pa		2 -												- -
			Residual = 44	lkPa		- :	<u>+</u>											-
				20	12													
				-		-		CH: Silty CLAY: grey with brown orange staining plasticity	. High									
		24	Deek - 102k	De		-	+ -	(Puketoka Formation)										-
		2.4	Residual = 4	ikPa		-	<u>×–</u>			IVI								-
						-	×_~						HA					-
							<u> </u>				VSt							
						-												-
		2.8	Peak = 105k Residual = 50	Pa)kPa		-	\vdash	at 2.80m, becoming dark grey with orange stre	eaks.									-
							<u>×–</u>											
				19	9.5	3 —		CL: CLAY: dark grey. Low plasticity.										
						-	<u> </u>	(Waitemata Group)										
		3.2	Peak = 160k Residual = 7	Pa kPa		-												-
			i tesiddai - 7	Ki a		-	<u>+-</u>											
							<u> </u>											-
						-	<u>t-</u>											-
	▼	3.6	Peak = 160k	Ра		-	F	at 3.60m becoming wet										-
			Residual = 82	2kPa		-	1	at 5.00m, becoming wet.										.
							1											
						-	<u>1</u>											-
		4.0	Peak = 204+	кРа		4 —	<u>+</u>											
							1											
							上 二											
						-	<u> </u>			w								
		4.4	Book = 204+	(Bo		-	<u> </u>											-
		4.4	1 eak - 204 i	N a		-	Ł-1											-
						-	<u> </u>				н							
						-	1											
		4.8	Peak = 204+	кРа		-	F-1											
							1-1											
$\mid = \mid$						5 —		Borehole terminated at 5.0 m				1						1 -
Tern	ninati	on reas	on: Ta	rget De	pth	Rea	ched			1	1	L	1	1				1
				5														
Rem	narks:	unterec	at	3.6m	า.													
			This report i	s based	d or	the	attach	ed field description for soil and rock, CMW C	Geoscience	s - Fi	eld Lo	oggi	ng Gu	uide, F	Revi	sion	3 - A	pril 2018.

BOREHOLE LOG - HA09-19

Client: Neil Group Limited Project: Trig & Brigham Creek Road Site Location: Whenuapai Project No.: AKL2019-0040 Date: 18/03/2019 Borehole Location: Refer to site plan



1:25 Sheet 1 of 1 Logged by: JMJ Position: E.1745237.9m N.5926451.8m RI 23 50m Flevation: Hole Diameter: 50mm Survey Source: Checked by: TG Angle from horizontal: 90° Measured onsite Datum: N7TM Structure & Other Observations Consistency/ Relative Density Drilling Method/ Support Dynamic Cone Penetrometer Samples & Insitu Tests Material Description _og Moisture Condition Ē Recovery Soil: Soil symbol; soil type; colour; structure; bedding; plasticity; sensitivity; additional comments. (origin/geological unit) Rock: Colour; fabric; rock name; additional comments. (origin/geological unit) Ê (Blows/100mm) Discontinuities: Depth: Defect Graphic L Well Number; Defect Type; Dip; Defect Shape; Roughness; Aperture; Infill; Seepage; Spacing; Block Size; Block Shape; Remarks Ground Depth Ч 10 15 5 Depth Type & Results 23.5 OL: TOPSOIL 23.3 CL: CLAY : light orange. Low plasticity. D to н M (Puketoka Formation) 0.4 Peak = 204+kPa 23.0 CH: Silty CLAY: dark brownish grey. High plasticity. (Puketoka Formation) Peak = 117kPa Residual = 44kPa 0.8 М VSt Peak = 140kPa Residual = 82kPa 1.2 at 1.30m, becoming with black and orange staining. Minor organic smell. Peak = 140kPa 1.6 Residual = 73kPa 21.7 CH: Silty CLAY : black with brown streaks. High plasticity. Organic smell and minor fibrous rootlets and wood inclusions Peak = 67kPa 2.0 2 (Puketoka Formation) M to Residual = 32kPa w 21.2 CH: Silty CLAY: light brownish grey. High plasticity. 2.4 Peak = 70kPa (Puketoka Formation) Residual = 44kPa ΗА \mathbf{T} 2.8 Peak = 82kPa Residual = 47kPa 3 St 3.2 Peak = 88kPa Residual = 29kPa Peak = 93kPa Residual = 47kPa 3.6 w 19.7 CL: CLAY with some silt and trace fine sand: dark grey. Low plasticity. Sand is crushed completely weathered siltstone. 4.0 Peak = 90kPa Residual = 29kPa 4 (Waitemata Group) Peak = 160kPa Residual = 41kPa 4.4 VSt 4.8 Peak = UTP 5 Borehole terminated at 5.0 m Termination reason: Target Depth Reached Remarks: Groundwater encountered at 2.8m. This report is based on the attached field description for soil and rock, CMW Geosciences - Field Logging Guide, Revision 3 - April 2018.

BOREHOLE LOG - HA10-19



	sorer			eter to	SILE	e pian	6.6m N 5026206 7m	E 1			4.00			<u> </u>	.25	D	Sheet 1 of 1
	oggeo	d by: RL		Survey S	Sour	E. 174004		Elevation	n: N7	RL 2	1.00	Jm		ŀ	Hole Apal	Diar	meter: 50mm
	песк	30 DY. 1	G	Survey S			Neasured Offsite	Datum.				~		Jynan	Ang nic C		Structure & Other Observations
	ater	Samp	oles & Insitu Test	s 🕤		a B	Material Description	- plaeticity:	e e	ncy/ ensity	≥.	thod		Penet	trome	eter	Discontinuities: Depth: Defect
Well	Mpun					phic (sensitivity; additional comments. (origin/geologica	al unit)	oistu onditi	siste ve D	SCOVE	oddn	(BIOWS		1111)	Number; Defect Type; Dip; Defect
	Grot	Depth	Type & Resu	its		Gra De	ROCK: Colour; fabric; rock name; additional comments. (or unit)	rigin/geological	≤ŏ	Con	l R	Sillin		5 ⁻ 1	10	15 I	Snape; Roughness; Aperture; Infili; Seepage; Spacing; Block Size;
_				21.0	, –					Ľ.					-	+	Block Shape; Remarks
				20.7	,		ML: Clavey SILT with trace fine sand: light gray	and light	-								
		0.4	Peak = 108k	Pa		- X X 3	brown. Low plasticity.	and light									
			Residual = 28	kPa			(Puketoka Formation)										-
						1,XX											
		0.8	Peak = 110kF	Pa													
			Residual = 32	kPa		- <u>1×</u> ×3											
						1 <u> </u>				VSt						_	
		1.2	Peak = 121k	Pa													
			Residual = 41	kPa													
									м								-
		1.6	Peak = 109k	Pa													
			Residual = 46	kPa 19.3													
				1010			CL: Silty CLAY with trace fine sand: grey. Low p (Puketoka Formation)	lasticity.									
							(,										
		2.0	Peak = 81kP	a		,											
		2.0	Residual = 34	kPa	1	• <u> </u> x_*											
							at 2.10m, with some fine sand.			St							
										51							
		24	Peak - 155k	22		×											
		2.4	Residual = 49	kPa								ц.					_
						<u> </u>											
						××											
		20	Dook = 190k	20													
		2.0	Residual = 46	kPa													
				18.1		× ×	ML: Sandy SILT with minor clay: grey. Low plast	ticity. Sand									
						3	(Waitemata Group)										-
				-		$\times \times$											
		3.2	Peak = 217+k	Ра		- * * *											
																	-
		3.6	Peak = 201kP Residual = 46	a kPa						VSt to							
						$X \times X$				Н							
						- × × ×											
									w								
		4.0	Peak = 217+k	Pa	4	4 - × ×											
						-× × ×											
						$X \times X$											
		4.4	Peak = UTF	,		- (× × - × × >											
																	-
1						_îx^x											
		4.8	Peak = 217+k	Pa		-××>											
1						- XXX											
		L				5 - (× .×	Borehole terminated at 5.0 m			-	1						
Terr	ninati	on reas	on: Tar	aet Dent	 th R	Reached			1	1	L	1	1				_
				30. Dopi													
Rem	narks	Ground	dwater not er	ncounter	ed.												
			This report is	s based o	on t	he attach	ed field description for soil and rock, CMW	Geoscience	es - Fi	eld Lo	oggi	ng Gu	uide,	Rev	isio	n 3 -	April 2018.

BOREHOLE LOG - HA11-19

Client: Neil Group Limited Project: Trig & Brigham Creek Road Site Location: Whenuapai Project No.: AKL2019-0040 Date: 18/03/2019 Borehole Location: Refer to site plan



Sheet 1 of 1 Logged by: RD Position: E.1745465.3m N.5926340.9m RI 22 00m Flevation: Hole Diameter: 50mm Survey Source: Checked by: TG Angle from horizontal: 90° Measured onsite Datum: N7TM Structure & Other Observations Consistency/ Relative Density Drilling Method/ Support Dynamic Cone Penetrometer Samples & Insitu Tests Material Description _og Moisture Condition Ē Recovery Soil: Soil symbol; soil type; colour; structure; bedding; plasticity; sensitivity; additional comments. (origin/geological unit) Rock: Colour; fabric; rock name; additional comments. (origin/geological unit) Ê (Blows/100mm) Discontinuities: Depth: Defect Well Graphic I Number; Defect Type; Dip; Defect Shape; Roughness; Aperture; Infill; Seepage; Spacing; Block Size; Block Shape; Remarks Groundv Depth Ч 10 15 5 Depth Type & Results 22.0 OL: TOPSOIL 21.9 ML: SILT: orange. Low plasticity. Friable. (Puketoka Formation) × D 0.4 Peak = UTP 21.6 CH: CLAY with minor silt: orange brown. High plasticity. (Puketoka Formation) VSt to H 0.8 Peak = 217+kPa 21.1 CL: Silty CLAY with minor fine sand: light greyish orange. Low plasticity. (Puketoka Formation) 1 М Peak = 155kPa Residual = 65kPa 1.2 Peak = 116kPa 1.6 VSt Residual = 46kPa 20.3 ML: Clayey SILT with minor fine sand: light grey streaked orange. Low plasticity. (Puketoka Formation) Peak = 96kPa Residual = 34kPa 2.0 2 St 2.4 Peak = 118kPa Residual = 32kPa НА 2.8 Peak = 143kPa Residual = 32kPa M to W VSt 3 3.2 Peak = 167kPa Residual = 47kPa Peak = 217+kPa 3.6 4.0 Peak = 217+kPa н 4 $\overline{\times}$ 17.9 ML: Sandy SILT with minor clay: light grey streaked orange. Low plasticity. Sand in fine grained. × (Waitemata Group) Peak = 139kPa Residual = 44kPa 4.4 w VSt 4.8 Peak = 153kPa Residual = 29kPa 5 Borehole terminated at 5.0 m Termination reason: Target Depth Reached Remarks: Groundwater not encountered. This report is based on the attached field description for soil and rock, CMW Geosciences - Field Logging Guide, Revision 3 - April 2018.

F F	HAN Client: Project Site Lo Project	ND AUC Neil Group Li :: Trig & Brigh :: Trig : When :: No.: AKL201	mite am (uapa 9-00	R d Cree ai 40	BC	DREHOLE LOG - HA12-19	N	Geo	osci)) en	ces	
)ate: 2 Soreho	25/11/2019 ble Location: F	Refe	r to s	site p	an Logged by: JW Checked by: TG Scale: 1:25			Shee	o	of 1	
F	Positio	n: 1745342.0)mE;	59	2645	0.0mN Projection: NZTM				<u>,, ,</u>		
E	levati	on: 23.50m			_	Datum: AUCKHT 1946 Survey Source: Hand	d Hel	d Gł		/namie	Cone	,
Groundwate	Depth	ples & Insitu Tests Type & Results	RL (m)	Depth (m)	Graphic Lo	Material Description Soil: Soil symbol; soil type; colour; structure; bedding; plasticity; sensitivity; additional comments. (origin/geological unit) Rock: Colour; fabric; rock name; additional comments. (origin/geological unit)	Moisture Condition	Consistency telative Dens	(BI	enetro ows/1	00mm) 00mm))
-			23.5		-	ML: SILT with minor clay: brown. Low plasticity.		~				
			23.3		<u>I</u>	ML: SILT with some clav: orange brown. Low plasticity. Trace limonite streaks throughout.	-					
		Deels = 160kDe				(Puketoka Formation)		Vet				
	0.4	Residual = 58kPa		-				VSt				
					$X \times X$							
	0.8	Peak = 64kPa	22.8			CH: CLAY with minor silt: light brown streaked dark orange. High plasticity. (Puketoka Formation)						
		Residual = 26kPa			1							
				1 -		at 1.00m, becoming grey with trace organic staining and rootlets		St				
	1.2	Peak = 160kPa			1							
		Residual = 32kPa			1-							
			22.0	-		CH: Silty CLAV, gray brayer, High plasticity Trace organic staining	м					
	1.6	Peak = 128kPa Residual = 45kPa				(Puketoka Formation)		VSt				
			21.8			CH: Organic stained Silty CLAY: black. High plasticity. Rootlets. (Puketoka Formation)						
	2.0	Peak = 83kPa Residual = 58kPa	21.5	2 -	<u> </u>	CH: CLAY with minor silt: grey with black streaks. High plasticity.	-					
					<u>E</u>							
					<u> </u>							
	2.4	Peak = 99kPa Residual = 64kPa		-								
					1-			St				
	2.8	Peak = 86kPa	20.7									
	2.0	Residual = 32kPa	20.7			CH: Silty CLAY with minor fine to coarse sand: grey. High plasticity. Sand is sub angular to sub rounded. Trace organics. (Curketing Exemption)	w					
				3 -		at 3.00m, saturated						
	3.2	Peak = 128kPa				at 3.20m with some fine to coarse arained sand						
		Residual = 35kPa				at 5.20m, with some line to coarse grained send						
				-								
	3.6	Peak = 131kPa Residual = 32kPa	19.9			CH: Sandy CLAY with some silt: grey. Low plasticity. Trace organics.	-					
						(Puketoka Formation)						
					<u> </u>		s					
	4.0	Peak = 147kPa Residual = 38kPa		4 -						_		
								vst				
	4.4	Peak = 157kPa Residual = 58kPa		-								
	40	Deak - 17940-	10 7									
	4.0	Residual = 70kPa	10.1			CH: Silty CLAY: dark grey. High plasticity. Trace organic staining. (Puketoka Formation)	M to W					
				5 -		Borehole terminated at 5.0 m	† ·					
T	erminat	ion Reason: Tar	get D	epth	Reach	ed OD N		•				
	mear Va Remarks	ane No: 2081 s: Groundwater e	encou	ntere	D ed at 2.	он мо. 8m.						
		This report	is ba	sed o	on the a	attached field description for soil and rock, CMW Geosciences - Field Logging Guide, Revision 3 -	April	2018				

	1 ^ L		26	D								
	IAI	Neil Group Li	JC imite	N	DU	REHOLE LOG - HAIJ-19						
	Proiect	: Tria & Briah	am (u Cree	k Ro	ad						
5	Site Lo	cation: When	uapa	ai			_					
F	Project	No.: AKL201	9-00)40		C/M	N	Geo	osci	enc	es	
	Date: 2	5/11/2019	-									
	Boreho	le Location: I	Refe	r to s	site p	Ian Logged by: JW Checked by: IG Scale: 1:25			Shee	et 1 c	of 1	
	'OSIIIO Iovati	n: 1745363.(on: 23.00m	Jm⊨;	59	2644	9.0mN Projection: NZTM Datum: ALICKHT 1046 Survey Source: Hand	- H이	d CE	20			
		011. 20.00111			_			<u>,</u> ≩		/namic	Cone	
dwate	Sam	oles & Insitu Tests	Ē	Ű,	ic Log	Material Description	sture	stency Dens	P (B	enetror ows/10	neter 0mm)	
Broun	Depth	Type & Results	Ч	Dept	Graph	Rock: Colour; fabric; rock name; additional comments. (origin/geological unit)	Mois	Consis	5	10	15	
			23.0					۳, ۳				
			23.0			CL: TOFSOIL CL: Silty CLAY with trace gravel: orange, grey, brown and black. Low plasticity.	1					
					<u>}</u>							
					1000							
	0.4	Peak = 147kPa Residual = 64kPa	22.6 22.6		<u>k k k</u>	OL: Buried TOPSOIL		VSt				
				-		CH: Sinty CLAY with trace line to coaste sand: grey streaked orange and brown. High plasticity. (Puketoka Formation)						
	0.8	Peak = 83kPa			<u>*–</u>	at 0.90m 100mm seam of black amonic stained CLAV						
		Residual = 35kPa	22.1		<u>*</u>	CH: CI AY with minor silt and trace rootlets: grey mottled orange. High plasticity. Trace white pumiceous	-					
				1 -	<u>1-</u>	inclusions. (Pulstaka Eormation)		St			-	
					<u>t</u>							
	1.2	Peak = 128kPa Residual = 80kPa			1 <u>–</u> –							
					1							
				_	F		м					
	1.6	Peak = 115kPa			F			VSt				
		Residual = 58kPa			F							
					F	at 1.80m, with trace fine to medium grained sand						
					£							
	2.0	Peak = 99kPa Residual = 51kPa	21.0	2 -		CH: Silty CLAY with minor fine to coarse sand: grey. High plasticity. Trace white pumiceous mottles and	1					
						trace organics. (Puketoka Formation)		0.				
								51				
	2.4	Peak = 115kPa										
		Residual = 51kPa		-								
-	2.8	Peak = 134kPa Residual = 48kPa	20.2		- <u>X</u>	CH: Sandy CLAY with minor silt: dark grey. High plasticity. Sand is fine to coarse grained. Trace organics.	1					
				2 -								
				3								
	3.2	Peak = 144kPa				at 3 00m with some silf						
		Residual = 48kPa			<u> </u>							
					<u> </u>							
				-	F		M to					
	3.6	Peak = 147kPa Residual = 45kPa			<u> </u>		"	1/64				
					<u> </u>			voi				
					<u> </u>							
	4.0	Peak = 138kPa		4 -								
		Residual = 35kPa			<u> </u>							
			18.8		×	CH: Silty CLAY: dark grey. High plasticity.						
		D I. 4701-D.			<u>*–</u>	(Waitemata Group)						
	4.4	Residual = 74kPa		_	<u> ×_</u>							
					<u>*-</u> *		W to					
					<u>1×_</u>							
	4.8	Peak = 224+ kPa			<u>k_</u>							
					<u>*</u>							
				5 -		Borehole terminated at 5.0 m						_
Т	erminat	ion Reason: Tar	get D	epth I	Reach	ed						
S	shear Va	ane No: 2081			D	CP No:						
	emarks	: Groundwater e	encou	ntere	d at 2	9m.						
		This report	t is ba	sed c	on the	attached field description for soil and rock, CMW Geosciences - Field Logging Guide, Revision 3 \cdot	- April	2018.				

	IAN		GE	R	BC	OREHOLE LOG - HA14-19					
F	Project	: Trig & Brigh	am (c Cree	k Ro	ad					
F	Project	No.: AKL201	9-00)40		CM	N	Geo	oscie	nce	es
	Boreho	ble Location: F	Refe	r to s	site p	lan Logged by: JW Checked by: TG Scale: 1:25		ę	Sheet	1 of	1
F E	Positio Elevati	n: 1745395.0 on: 21.20m)mE;	59	2644	1.0mN Projection: NZTM Datum: AUCKHT 1946 Survey Source: Hand	d Hel	d GF	s		
vater	Sam	ples & Insitu Tests	(c	(L)	Log	Material Description	ion	ency/ bensity	Dyn Per (Bloy	amic Co etrome	one iter
Groundv	Depth	Type & Results	RL (n	Depth	Graphic	Soil: Soil symbol; soil type; colour; structure; bedding; plasticity; sensitivity; additional comments. (origin/geological unit) Rock: Colour; fabric; rock name; additional comments. (origin/geological unit)	Moistu Condit	Consiste Relative D	5	10	15
			21.2 21.2			OL: TOPSOIL CH: Silty CLAY with trace gravel: orange, brown, grey, black. High plasticity.	-				
	0.4	Peak = 166kPa Residual = 70kPa						VSt			
				-							
			20.4								
								F			
			20.2	1 -		CH: CLAY with minor silt and trace fine to coarse sand: brown streaked orange. High plasticity. Trace rootlets.	-				
	1.2	Peak = 90kPa Residual = 45kPa	19.9		 	(Puketoka Formation) at 1.20m, becoming grey streaked orange CIL Cit CI AV with the Factor account of the transformer because the planticity Transported	м				
					× ×_×	staining and trace rootlets. (Puketoka Formation)					
	1.6	Peak = 67kPa Residual = 19kPa						St			
			19.4			CH: Sandy CLAY with minor rootlate: dark arey. High plasticity. Trace organic staining. Alternating every					
	2.0	Peak - 173kPa		2		100-150mm with Clayey SILT, dark grey, low plasticity. (Puketoka Formation)					
	2.0	Residual = 45kPa		2 -							
-	2.4	Peak = 144kPa Residual = 80kPa									
	2.8	Peak = 115kPa									
		Residual = 48kPa	10.2	2 -							
			10.2	3 -		CH: Sandy CLAY: dark grey. High plasticity. Sand is fine to coarse grained. Inter-bedded with Clayey SILT, dark grey, low plasticity. (Waitemata Group)					
	3.2	Peak = 176kPa Residual = 45kPa									
								VSt			
	3.6	Peak = 192kPa Residual = 58kPa						VOL			
							W to S				
	4.0	Peak = 224+ kPa		4 -							
	4.4	Peak = UTP		_							
	4.8	Peak = UTP									
				5 -		Borehole terminated at 5.0 m					_
Т	erminat	ion Reason: Tar	1 get D	epth I	1 Reach	ed				-	
S	hear Va temarks	ane No: 2081 s: Groundwater e	encou	ntere	D d at 2	CP No: 5m.					
		This report	is ba	sed c	on the	attached field description for soil and rock, CMW Geosciences - Field Logging Guide, Revision 3 -	April	2018.			

ŀ	A		ЭE	R	BC	REHOLE LOG - HA15-19					
c	lient:	Neil Group Li	mite	d							
P	Project	: Trig & Brigh	am (Cree	k Ro	ad	_			V	
0 P	roject	No.: AKL201	9-00	ai 140		CM	N				_
	ate: 2	5/11/2019						Geo	scier	ice	S
B	oreho	le Location: F	Refer	r to s	site p	lan Logged by: TK Checked by: TG Scale: 1:25		S	Sheet 1	l of ′	1
P F	ositioi levatio	n: 1745378.0 on: 20.20m	mE;	592	2641	9.0mN Projection: NZTM Datum: AUCKHT 1946 Survey Source: Hand	l Hel	d GF	s		
ter	Sam	oles & Insitu Tests		_	b			y/ nsity	Dynar Pene	nic Cor	ne er
undwat			(m)	pth (m	phic Lo	Material Description Soil: Soil symbol; soil type; colour; structure; bedding; plasticity; sensitivity; additional comments. (origin/geological unit)	oisture	sistend ve Der	(Blows	/100mr	n)
Gro	Depth	Type & Results		De	Gra	Rock. Colour, labric, rock name, additional comments. (onginingeological unit)	≥ŭ	Con Relati	5 	10 1 	5
			20.2			OL: TOPSOIL					
							D				
	0.4	Peak = 178+ kPa	19.8			CI: Silty CLAY: Yellowish brown, mottled grey. Low-high plasticity. Trace fine sand. (Uncontrolled Fill)					
								VSt			
	0.8	Peak = 135kPa Residual = 61kPa					м				
				1 -							
	1.2	Peak = 61kPa Residual = 28kPa	18.9								
						OL: Buried TOPSOIL: Contains gravel.					
				-			W to S				
	1.6	Peak = 28kPa Residual = 18kPa	18.5					F to			
						CL: Silty CLAY with some sand: Brownish grey, mottled brown. Low plasticity, trace organic fragments and roots (<15mm)		St			
					<u></u>	(Puketoka Formation)	w				
	2.0	Peak = 74kPa Residual = 18kPa		2	<u>×_</u> ×						
▼			18.0			MH: Clavev SILT: Grev. Low plasticity.					
					$(\times \times)$	(Waitemata Group)					
	2.4	Peak = 178+ kPa			× × > (× ×						
			17.6		× × > • × ×	MH: Sandy SILT: Grey. Low plasticity. Fine to medium.					
						(Waitemata Group)					
	2.8	Реак = 1/8+ кРа			(
				3 -	(from 3.00m to 5.00m, Becoming moist, loosely packed					
	2.0	Deek = 170 J kDe			$(\times \times)$						
	3.2	Peak = 1/0+ kPa									
					× × > (× ×						
	26	Deak = 170 - 100			× × > (× ×			VSt to			
	3.0	i-eak = 170+ KPa						н			
	4.0	Book - LITR			(м				
	4.0	Teak - OTT		4	(IVI				
					$(\times \times)$						
		Deak - 178+ kDa									
	4.4	1 eak - 170' ki a			× × > < × ×						
					$(\times \times)$						
	4.8	Peak = 178+ kPa									
	5.0	Peak = 178+ kPa		5 —		Borehole terminated at 5.0 m	-				\vdash
Te	erminati	on Reason: Tar	get De	epth I	Reach	ed					
S	hear Va	ne No: 1620	ncou	ntere	D dat 2	CP No: 2m					
	5.10115						•	0010			
1		rnis report	is pa	5ea 0	in the	anaoneu nela description for son and rock, Civivi Geosciences - Field Logging Guide, Revision 3 -	April	∠uıŏ.			

HAND AUGER BOREHOLE LOG - HA16-19 Client: Neil Group Limited Project: Trig & Brigham Creek Road Site Lageting: Whenugeni												
Site Location: Whenuapai Project No.: AKL2019-0040												
Date: 25/11/2019 Borehole Location: Refer to site plan Logged by: LSW Checked by: TG Scale: 1:25									Sheet 1 of 1			
Position: 1745402.0mE; 5926415.0mN Projection: NZTM Elevation: 20.10m Datum: AUCKHT 1946 Survey Source: Hand Held CPS												
T T	Sam	Samples & Insitu Tests						cy/ nsity	Dynai Pene	Dynamic Cone Penetrometer		
Groundwa	Depth	Type & Results	RL (m	Depth (n	Graphic L	Material Description Soil: Soil symbol; soil type; colour; structure; bedding; plasticity: sensitivity; additional comments. (origin/geological unit) Rock: Colour; fabric; rock name; additional comments. (origin/geological unit)		Consisten Relative De	5 10 15			
			20.1			OL: TOPSOIL:	D					
			19.9			CL: Silty CLAY: Yellow, mottled brown. Low plasticity. (Uncontrolled Fill)						
	0.4	Peak = 123kPa Residual = 42kPa										
			19.5	-		MI: Clavay SILT Proven mattled vallage and gray. Law plasticity Erichla						
						(Uncontrolled Fill)						
	0.8	Peak = 120kPa Residual = 60kPa					м	vst				
				1 -						+		
	1.2	Peak = 114kPa Residual = 57kPa				from 1.20m to 1.60m, Becoming yellow, mottled brown, grey, some orange.						
				-								
	1.6	Peak = 81kPa Residual = 42kPa	18.5			CH: Silty CLAY: Yellow-orange. High plasticity. (Puketoka Formation)						
								St				
◄	2.0	Peak = 211+ kPa	18.1	2 -		CH: Silty CLAY: Dark grey, streaked orange. High plasticity	-					
						(Puketoka Formation)						
	2.4	Peak = 211+ kPa		-								
	2.8	Peak = 211+ kPa										
			17.1	2 -								
				5		CL: Clayey SILT with some sand: Dark grey, Low plasticity. Sand is fine to coarse grained. (Waitemata Group)						
	3.2	Peak = 211+ kPa					M to					
							vv	VSt to				
	3.6	Peak = 211+ kPa		-				Н				
	4.0	Peak = 211+ kPa		4 -								
	4.4	Peak = UTP										
				-								
	4.8	Peak = UTP										
	5.0	Peak = UTP		5 -	- 	Borehole terminated at 5.0 m	<u> </u>	-				
Termination Reason: Target Depth Reached												
Remarks: Groundwater encountered at 2.0m												
This report is based on the attached field description for soil and rock. CMW Geosciences - Field Logging Guide. Revision 3 - April 2018												


	HAND AUGER BOREHOLE LOG - HA18-19 Client: Neil Group Limited													
	Client: Project	Neil Group Li :: Trig & Brigh	mite am (d Cree	k Ro	ad								
(F	Site Lo Project	cation: When No.: AKL201	uapa 9-00	ai 140		CM	N	Geo			200			
[F	Date: 2 Boreho	25/11/2019 ble Location: F	Refe	r to s	site p	an Logged by: ISW Checked by: TG Scale: 1.25		Set	Shee	t 1 o	C 3			
F	Positio	n: 1745409.0)mE;	59	2637	5.0mN Projection: NZTM		<u>``</u>			<u></u>	_		
<u>ا</u>	Elevatio	on: 18.60m			5	Datum: AUCKHT 1946 Survey Source: Hand	d Hel	d GF	PS Dyi	namic	Cone			
Broundwate	Depth	Type & Results	RL (m)	Depth (m)	Braphic Lo	Material Description Soil: Soil symbol; soil type; colour; structure; bedding; plasticity; sensitivity; additional comments. (origin/geological unit) Rock: Colour; fabric; rock name; additional comments. (origin/geological unit)	Moisture Condition	consistency lative Dens	Pe (Blo	ws/10	Dmm)			
	bopui		18.6			OL: TOPSOIL:		0 a		+	_			
			18.4			MH: Clayey SILT: Grey, mottled brown and orange. Low plasticity, friable.								
	0.4	Peak = 172kPa				(Uncontrolled Fill)								
		Residual – Ookra		-										
	0.8	Peak = 135kPa Residual = 84kPa												
			17.6	1 -		MH: Clayey SILT: Grey, mottled brown and orange. High plasticity. (Uncontrolled Fill)	м	VSt			+			
	1.6													
			10.0			MH: Clayey SILT with minor sand: Grey, small orange and brown mottles. High plasticity. (Puketoka Formation)								
	2.0	Peak = 54kPa Residual = 27kPa		2 -										
			16.4			CH: Silty CLAY: Grey and dark brown. High plasticity. Poor recovery after 2.4m, shear strengths are not an accurate representation.		-						
	2.4	Peak = 69kPa Residual = 27kPa				(Puketoka Formation)								
				-	-x~									
	2.8	Peak = 57kPa			× ×									
		Residual = 30kPa												
				3 -				51						
	3.2	Peak = 66kPa Residual = 48kPa					s							
	3.6	Peak = 60kPa Residual = 45kPa			<u> </u>									
	4.0	Peak = 105kPa		4 -										
		Residual = 81kPa												
	4.4	Peak = 211+ kPa	14.2	-		ML: Clayey SILT with some sand: Grey. Low plasticity. (Waitemata Group)		VSt to						
							14/							
	4.8	Peak = 211+ kPa					**							
	5.0	Peak = UTP		5 -		Borehole terminated at 5.0 m	<u> </u>							
	Terminat	ion Reason: Tar	l get D	l epth l	∣ Reach	ed	1					_		
5 F	Shear Va Remarks	ane No: 2082 s: Groundwater e	encou	ntere	D d at 2.	CP No: 0m								
		This report	is ba	sed c	on the	attached field description for soil and rock, CMW Geosciences - Field Logging Guide, Revision 3 -	April	2018.						

	HAN Client:	ND AUC Neil Group Li	GE mite	R	BC	REHOLE LOG - HA19-19					
F S F	Project Site Lo Project	: Trig & Brigh cation: When No.: AKL201	am (uapa 9-00	Cree ai 40	ek Ro	ad	N	Geo			ç
C B)ate: 2 loreho	6/11/2019 le Location: F	Refei	to :	site p	lan Logged by: LSW Checked by: TG Scale: 1:25			Sheet	1 of	1
P	ositio	n: 1745295.0)mE;	59	2633	3.0mN Projection: NZTM			20		
5	sam				0	Datum: AUCKHT 1946 Survey Source: Hand			Dyna Dyna	mic Cor	ne
Groundwat	Depth	Type & Results	RL (m)	Depth (m	Graphic Lo	Material Description Soil: Soil symbol; soil type; colour; structure; bedding; plasticity; sensitivity; additional comments. (origin/geological unit) Rock: Colour; fabric; rock name; additional comments. (origin/geological unit)	Moisture Condition	Consistenc Relative Den	(Blow	s/100m 10 1	m) 15
			21.4			OL: TOPSOIL:					
	0.4	Peak = 124kPa Residual = 28kPa	21.0			CL: Silty CLAY: Yellow mottled grey and orange. Low plasticity (Uncontrolled Fill)	-				
			20.8			ML: Clayey SILT with minor sand: Dark brown. Low plasticity. Friable. Fine to medium sand. (Puketoka Formation)					
	0.8	Peak = 140kPa Residual = 48kPa	20.6	1 -		CL: Silty CLAY with minor sand: Grey mottled orange and brown. Low plasticity (Puketoka Formation)	M	VSt			
	1.2	Peak = 142kPa Residual = 79kPa									
	1.6										
◄	2.0	Peak = 36kPa Residual = 18kPa		2 -		from 2.00m to 2.20m, Becoming saturated, high plasticity		St			
	2.4	Peak = UTP	19.2			ML: Clayey SILT: Grey mottled orange. Low plasticity. (Puketoka Formation)		F			
	2.8	Peak = UTP		-		from 2.60m to 2.80m, Becoming brown	s				
	-			3 -		from 2.80m to 3.60m, Becoming grey mottled orange					
	3.2	Peak = 178+ kPa									
	3.6	Peak = UTP	17.8	-		ML: Clayey SILT with some sand: Dark grey. Low plasticity. (Waitemata Group)		VSt			
	4.0	Peak = UTP		4 -			w				
	4.4	Peak = UTP	16.9	-		MI - Clavey SII Twith come cand: Dark gray Low to bish placticity		-			
			16.7			(Waitemata Group) ML: Clayey SILT with some sand: Dark grey. Low to high plasticity.	s	-			
	4.8	Peak = UTP		5 -		(Waitemata Group)	w				
	erminat	ion Reason [.] Tan	det Di	epth	Reach	Borehole terminated at 5.0 m					1
S	hear Va	ane No: 1620	encou	ntere	D Ded at 2	CP No: 0m					
		This report	is ba	sed o	on the	attached field description for soil and rock, CMW Geosciences - Field Logging Guide, Revision 3	- April	2018.			



	HAND AUGER BOREHOLE LOG - HA21-19 Client: Neil Group Limited Project: Trig & Brigham Creek Road													
P	Project	: Trig & Brigh	am (Cree	ek Ro	ad	_							
P	Project	No.: AKL201	9-00	40		CM	N	Geo	oscie	nce	s			
	oate: 2 Ioreho	6/11/2019 le Location: F	Refei	r to :	site p	lan Logged by: LSW Checked by: TG Scale: 1:25		ę	Sheet	1 of	1			
P	Position	n: 1745120.0)mE;	59	2630	6.0mN Projection: NZTM	1 니시	4 66	200					
ם رو	Samr	DII. 20.0011			DD DD			sity	Dyna	amic Co	ne er			
oundwat			RL (m)	Depth (m	raphic Lo	Material Description Soil: Soil symbol; soil type; colour; structure; bedding; plasticity; sensitivity; additional comments. (origin/geological unit) Rock: Colour; fabric; rock name; additional comments. (origin/geological unit)	Moisture	ative Der	(Blov	/s/100m	im) 15			
ō	Depth	Type & Results	25.0		0	OL: TOPSOIL:		Rels	Ľ					
			24.8			CL Silly CLAX with trace cand; Gray stracked grappe/vellow. Small brown mottles. Low plasticity. Sand is								
	0.4	Book - 169kBo				fine to medium. (Puketoka Formation)								
	0.4	Residual = 56kPa												
	0.8	Peak = 114kPa Residual = 50kPa												
			24.0	1 -		ML: Clayey SILT with some sand: Light grey, almost white, mottled orange. Low plasticity. Friable. Sand is fine to medium								
	1.2 Peak = 132kPa Residual = 72kPa ine to medium. (Puketoka Formation)													
	Residual = 72kPa $\begin{array}{c} 1 \\ - \\ - \\ - \\ - \\ - \\ - \\ - \\ - \\ - \\$													
	1.6	Peak = 117kPa		-										
		Residual = 69kPa												
	2.0	Peak = 112kPa Residual = 63kPa		2 -										
	2.4	Peak = 147kPa Residual = 63kPa	22.6			CL: Silty CLAY: Grey mottled orange. Low to high plasticity.	-							
			22.4	-		(Puketoka Formation) MH: Clayey SILT: Light grey. High plasticity.		VSt						
▼	2.8	Peak = 150kPa				(Puketoka Formation)								
		Residual = 51kPa	22.0	3 -										
				0		ML: Clayey SILT with some sand: Dark grey. Low plasticity. (Waitemata Group)								
	3.2	Peak = 178+ kPa												
				-										
	3.6	Peak = UTP												
							W to S							
	4.0	Peak = UTP		4 -						_				
	4.4	Peak - LITP												
	4.4	reak - UTr												
	4.8	Peak = UTP												
	5.0	Peak = UTP	-	5 -		Borehole terminated at 5.0 m								
T	erminati	ion Reason: Tar	get De	epth	Reach	ed CP No:	•	•						
R	emarks	Groundwater e	encou	ntere	ed at 2.	8m								
		This report	is ba	sed o	on the	attached field description for soil and rock, CMW Geosciences - Field Logging Guide, Revision 3	April	2018.						

ŀ	1AH	ND AUC	ЭE	R	BC	REHOLE LOG - HA22-19							
C P	lient: Project	Neil Group Li : Trig & Brigh	mite am (d Cree	k Roa	ad							
S	ite Lo	cation: When	uapa	ai Mo			A			y			
	ate: 2	6/11/2019	9-00	40				Geo	oscie	nce	s		
B	oreho ositio	le Location: F n: 1745145.0	Refei)mE:	r to s 592	ite pl 26258	an Logged by: LSW Checked by: TG Scale: 1:25 3.0mN Projection: NZTM		ę	Sheet	1 of '	1		
E	levatio	on: 28.60m	, <u>-</u> ,			Datum: AUCKHT 1946 Survey Source: Hand	d Hel	d GF	s				
dwater	Samp	oles & Insitu Tests	(E	(m) r	ic Log	Material Description	sture dition	stency/ Density	Dyna Pen (Blow	etromete s/100mi	ne er m)		
Groun	Depth	Type & Results	RL	Dept	Graph	Rock: Colour; fabric; rock name; additional comments. (origin/geological unit)	Mois	Consis Relative	5	10 1	5		
			28.6			OL: TOPSOIL:							
	0.4	Peak = 160kPa	28.2			CL: Silty CLAY: Orange, mottled brown, grey, dark grey. Low plasticity	-						
				-	××	(Puketoka Formation)							
	0.8	Peak = 102kPa Residual = 63kPa			×								
				1 -				VSt					
1.2 Peak = 155kPa Residual = 69kPa													
Residual = 69kPa													
	м												
			26.8			CL: Silty CLAY: Orange, mottled grey. Low to high plasticity.							
	2.0	Peak = 56kPa Residual = 25kPa		2 -									
					×								
	2.4	Peak = 99kPa Residual = 63kPa		-									
					×								
	2.8	Peak = 59kPa Residual = 41kPa											
			25.6	3 -		MI · Clavey SILT: Grey, mottled grange, Low to high plasticity		St					
	2.2	Book - 61kBo				(Puketoka Formation)							
	3.2	Residual = 51kPa											
				· ·									
	3.6	Peak = 99kPa Residual = 61kPa											
			24.8			ML: Clayey SILT with some sand: Grey. Low plasticity.							
	4.0	Peak = 129kPa		4 -		(Waitemata Group)	W to						
		Residual = 58kPa					s						
	4.4	Peak = 150kPa Residual = 84kPa			$\left(\begin{array}{c} \times \times \\ \times \times \end{array} \right)$			VC					
						from 4.60m to 5.00m, ecoming interbedded with Silty CLAY		vət					
	4.8	Peak = 124kPa											
	FO	Residual = 58kPa											
	o.u erminati	Residual - 74kPa		enth F	Reach	Borehole terminated at 5.0 m							
s	hear Va	ane No: 1620			D								
R	emarks	Groundwater e	encou	ntere	d at 2.		۰	2042					
		i nis report	is pa	5eu 0	ii ine a	anaoneu neid description for son and fock, Givivy Geosciences - Fleid Logging Guide, Revision 3 -	Abu	201ŏ.					

	BOREHOLE LOG - MH01-19 Client: Neil Group Limited Project: Trig & Brigham Creek Road Site Location: Whenuapai																					
F	Proje	ct: Tri	g & Brigham (u Creel	k Ro	bad																
	Site L Proje	.ocatio ct No.	on: Whenuapa : AKL2019-00	ai 140																N		
	Date:	26/11	/2019	r to o	ito r	lan	Loggod by: Th	,	Cho		od	bu	» та	2	50			1.5	0			
	Positi	on: 1	745319.0mE;	592	2597	70.0m	N Projection: NZTM	`	Che	Cr	eu	by	. 10	2	An	gle.	fro	n ł	nor	izoı	ntal:	90°
E	Eleva	ition: 1	5.80m				Datum: AUCKHT 1946		. ≥	1					Su	rve	y S	oui	rce Def	e: H	and	Held GPS Structure & Other Observations
Vell	ndwater	Sam	ples & Insitu Tests	L (m)	oth (m)	hic Log	Soil: Soil symbol; soil type; colour; structure; bedding; plasticity; sensitivity; additional comments. (origin/geological unit)	oisture ndition	sistency/	N	/eath	ering	covery	gD	S	Streng	ith		Spa (m	cing m)	g Metho	Discontinuities: Depth; Defect Number; Defect Type; Dip; Defect
	Grou	Depth	Type & Results	R	Del	Grap	Rock: Colour; fabric; rock name; additional comments. (origin/geological unit)	δğ	Cons Relativ	RS	8 A	NW SW	uw Re		N N	MS	s s c	20 50 50	20-60 60-200	200-600 600-2000	Drilling	Shape; Roughness; Aperture; Infill; Seepage; Spacing; Block Size; Block Shape; Remarks
				15.8 15.7			TOPSOIL: brown. CH: Silty CLAY: with trace fine to medium sand: brown mottled light	D to					60									-
		0.5	Peak = 74kPa Residual = 36kPa		-		grey. High plasticity. (Uncontrolled Fill)	м	St												33	
													100								OB / P	
		1.0	Residual = 53kPa	14.6	1-		CH: Silty CLAY: with trace fine to		VSt				100									
		1.5 1.5	Peak = 63kPa Residual = 20kPa		-		medium sand; light brownish grey mottled orange. High plasticity. (Puketoka Formation)															
			SPT = (4,4,10) N* = 14										89								SPT	
					2 -	1×	at 2.20m, trace organic															_
	Image: Second																					
$\begin{array}{ c c c c c c c c c c c c c c c c c c c$																						
	$\begin{array}{c c c c c c c c c c c c c c c c c c c $																					
$\begin{array}{c c c c c c c c c c c c c c c c c c c $																						
							at 3.70m, becoming bluish grey						10								PQ3	
					4 -		at 4.00m, becoming brownish grey, minor fine to medium sand						55								OB /	
		4.5	SPT = (3,3,3) N* =		-		at 4.50m, becoming grey		51													
		5055	Buch Tubo 11162				mottled orange.						100								SPT	
		5.0-5.5	Fush Tube 1 003		5 -								91								J63	
					-																3	
													100								OB / PQ	
		6.0	SPT = (3,3,3) N* = 6		6 -								0								μ	
					-																0	
																					g	
					7 -		at 7.10m, becoming brownish	w					86								OB / F	
		7.5	SPT = (5,7,10) N* =	8.3	-		grey motiled dark grey, minor medium to coarse sand. ML: Sandy SILT: with minor clay:															
			17				bluish grey. Low plasticity. Medium to coarse sand.						100								SPT	-
					8 -		(waitemata Group)															-
					-	{							100								3 / PQ3	-
									VSt												Ö	-
		9.0	SPT = (7,13,17) N* = 30		9 -								0									-
					_	(X X X X) (X X							10								SF	
													100								3 / PQ3	-
				-	10 -																ő	
	Fermi Shea	natior r Vane	Reason: Tai No: 1620	rget	Dep	th Re	eached CP No:					_						_				
	Rema	arks:																				
			This report is ba	sed o	n the	attach	ned field description for soil and roc	k, CM	IW Ge	eos	cier	nces	s - Fi	eld I	Logo	ging	Gui	de,	Re	visio	n 3 - A	April 2018.

E	BOREHOLE LOG - MH01-19 Client: Neil Group Limited Project: Trig & Brigham Creek Road Site Legation: Whonuspai																				
C	roje	ct: Tri	g & Brigham C	a Cree	k Ro	ad															
S F	ite L roje	ocatio ct No.	on: Whenuapa : AKL2019-00	ai 140															M		
)ate:	26/11	/2019	r to c	sito r	lan	Loggod by: T		Cho	oko	dh	т	C	c				0	-	Sh	
F	Positi	on: 1	745319.0mE;	592	2597	70.0m	N Projection: NZTM	\	Cile	CRE	u b	<u>y. i</u>	0	A	ngle	fror	n ł	nor	izor	ntal: 9	90°
E	leva	tion: 1	5.80m			1	Datum: AUCKHT 1946		2					S	urvey	/ So	our	Ce Def	e: H	and I	Held GPS Structure & Other Observations
Vell	ndwater	Sam	ples & Insitu Tests	(m) -	oth (m)	hic Log	Soil: Soil symbol; soil type; colour; structure; bedding; plasticity; sensitivity; additional	isture	istency/ e Densi	Wea	atherir	ng	sovery		Strengt	ea th		Spa (m	cing m)	Methoopport	Discontinuities: Depth; Defect Number; Defect Type; Dip; Defect
	Grou	Depth	Type & Results	R	Dep	Grap	Rock: Colour; fabric; rock name; additional comments. (origin/geological unit)	O M	Cons Relativ	RS CV	A M A	N A	х Г	EW	N N N N	o 8 8	<20 <20	60-200	200-600 600-2000	Drilling	Shape; Roughness; Aperture; Infill; Seepage; Spacing; Block Size; Block Shape; Remarks
				5.5			ML: Sandy SILT: bluish grey. Low														
		10.5	SPT = (12,22,30) N* = 52		-		plasticity. Medium to coarse sand. (Waitemata Group)					2	3							La la	-
					11 -	-							-							ە ا	- - -
																				03	
					-				н			100	100							OB / P	-
		12.0	SPT =		12 -																
			(17,28,32/70mm) N* = 50+									100	100							SPT	-
3.1 3.1 3.1 3.1 3.1 3.1 3.1 3.1 3.1 3.1																					
3.1 ···· Grey, SANDSTONE. Weathered to 13 ···· coarse. (Waitemata Group) ···																					
13 - · · · coarse. (Waitemata Group)																					
13.5 $\begin{array}{c} \text{SPT} = \\ (29,50/56mm) \text{Nc} = \\ 50^+ \end{array}$ 2.3 $\begin{array}{c} \cdot \cdot \cdot \\ \cdot \cdot \cdot \\ a \text{ sandy SILT grey mottled dark} \end{array}$																					
					14 -		grey, low plasticity. (Waitemata Group)														-
																					-
					-							007	100							-/HQ3	
					15 -																-
		15.5	SPT = (50/90mm) Nc = 50+	0.3	-		Grey, SANDSTONE. Weathered to					_	0							o∟⊢	
					16 -		coarse. (Waitemata Group)														
												5	56							/ HQ3	
					-															F	-
		17.0	SPT = (50/115mm)		17 -																
			Nc = 50+										0							NTH	-
					-															33	-
					18 -							5	61							TT / HG	
																					-
		18.5	SPT = (50/90mm) Nc = 50+		-							_	5							ωч⊢	-
					40																-
					19 -							2	00							НQ3	
					-															È	- - -
					20																-
				-	20 -	-	Borehole terminated at 20.00 m														
T S	ermi Sheai	natior r Vane	Reason: Tai No: 1620	rget	Dep	th Re DC	eached CP No:														
F	Rema	arks:																			
			This report is ba	sed o	on the	attach	ed field description for soil and roo	ck, CN	1W Ge	eosci	ence	es - I	Field	Lo	gging	Guio	de,	Re	visio	13-A	pril 2018.

Position: 1745319.0 E, 5925970.0 N

Client: Neil Group Ltd

Project: Trig & Brigham Creek Road Location: Whenuapai

Project No: AKL2019-0040

Date: 26/11/19

Logged by: TK Checked by: TG

Elevation: RL 15.8m Angle fr

Angle from Horizontal: 90°

Hole Diameter: 100mm

Plant: Tractor Rig Contractor: Prodrill



MH01-19: 0m to 3.0m



MH01-19: 3.0m to 6.0m



Client: Neil Group Ltd

Project: Trig & Brigham Creek Road Location: Whenuapai

Project No: AKL2019-0040

Date: 26/11/19

Logged by: TK Checked by: TG Position: 1745319.0 E, 5925970.0 N Elevation: RL 15.8m Hole Diameter: 100mm Angle from Horizontal: 90° Plant: Tractor Rig Contractor: Prodrill



MH01-19: 6.0m to 8.85m



MH01-19: 8.85m to 11.65m



Client: Neil Group Ltd

Project: Trig & Brigham Creek Road Location: Whenuapai

Project No: AKL2019-0040

Date: 26/11/19

Logged by: TK Checked by: TG Position: 1745319.0 E, 5925970.0 N Hole Diameter: 100mm Elevation: RL 15.8m

Angle from Horizontal: 90°

Plant: Tractor Rig Contractor: Prodrill



MH01-19: 11.65m to 15.0m



MH01-19: 15.0m to 18.9m



Client: Neil Group Ltd

Project: Trig & Brigham Creek Road Location: Whenuapai

Project No: AKL2019-0040

Date: 26/11/19

Logged by: TK Checked by: TG Position: 1745319.0 E, 5925970.0 N Elevation: RL 15.8m Hole Diameter: 100mm Angle from Horizontal: 90° Plant: Tractor Rig Contractor: Prodrill



MH01-19: 18.9m to 20.0m



E	BOREHOLE LOG - MH02-19 Client: Neil Group Limited Project: Trig & Brigham Creek Road Site Location: Whenuapai																					
P	roje	ct: Trig	g & Brigham (u Creel	k Ro	bad																
S P	ite L roje	.ocatic ct No.:	on: Whenuapa : AKL2019-00	ai 140																N		Consciences
	ate:	27/11	/2019	r to o	ito r	alan	Loggod by: Th	,	Cho	ok	od	by	·тс	2	e.		. .	1.5	50	-	••	• Geosciences
B	ositi	on: 1	745259.0mE;	592	2613	30.0m	N Projection: NZTM	\	Cile	UN	eu	Dy.	. 10	2	A	ngle	;. e fro	om	hc	orizo	ontal:	90°
E	leva	tion: 2	27.00m				Datum: AUCKHT 1946		. ≯	Ι				Γ	S	urve	ey S	Sou 	D	e: H	land	Held GPS Structure & Other Observations
Nell	ndwater	Sam	oles & Insitu Tests	L (m)	oth (m)	hic Log	Soil: Soil symbol; soil type; colour; structure; bedding; plasticity; sensitivity; additional comments. (origin/deological unit)	oisture ndition	sistency/	W	eathe	ering	covery	gD		Strer	ngth		Sp (r	acing mm)	j Methor Ipport	Discontinuities: Depth; Defect Number; Defect Type; Dip; Defect
	Grou	Depth	Type & Results	ĸ	Del	Grap	Rock: Colour; fabric; rock name; additional comments. (origin/geological unit)	ĕ₿	Cons Relativ	RS	S A S	SW	Re		Ē	Š∧ ¥	ss	S 20	20-60	80-200 800-200	>2000 Drilling St	Shape; Roughness; Aperture; Infill; Seepage; Spacing; Block Size; Block Shape; Remarks
				27.0 26.8			TOPSOIL: brown.	D to					80									-
		0.5	Peak = 178+ kPa		.		medium sand; orange mottled grey. High plasticity.	м													33	-
							(Puketoka Formation) at 0.50m, becoming grey mottled orange.						100								OB / PC	-
		1.0	Peak = 152kPa Residual = 58kPa		1 -		, i i i i i i i i i i i i i i i i i i i						8									-
		1.5	Peak = 120kPa Residual = 86kPa		-								-									
		1.5	SPT = (2,6,14) N* = 20										100								SPT	
					2 -				VSt													-
	3.0 Peak = 142kPa 3 X-																					
$\begin{array}{c c c c c c c c c c c c c c c c c c c $																						
$ \begin{array}{c ccccccccccccccccccccccccccccccccccc$															St							
													91								U63	-
				23.0	4 -	<u>-×</u>	CL: Silty CLAY: with minor fine to medium sand: grey Low plasticity	-													P Q3	-
		4.5	Peak = 38kPa	22.5	.	<u></u>	(Puketoka Formation)						100								0B / I	-
		4.5	Residual = 13kPa SPT = (4,4,7) N* = 11			-× × > - × × - × ×	ML: Clayey SILI: with minor fine to medium sand; grey. Low plasticity. (Puketoka Formation)						100								SPT	-
					5 -																	-
					_								37								/PQ3	-
						_X X X _ X X _X X X	at 5.50m, becoming grey mottled dark grey, some medium to coarse sand.														OB	
		6.0 6.0	Peak = 28kPa Residual = 10kPa		6 -																	
			SPT = (3,3,3) N* = 6										100								SP'	-
				20.0	7 -		Sandy SILT: with minor clay; grey.	_	F				86								DB / PQ	
							Low plasticity, medium to coarse. (Puketoka Formation)															-
		7.5 7.5	Peak = 36kPa Residual = 10kPa SPT = (1,3,3) N* =		-	(W					100								SPT	
			6		8 -																	-
						-××> <××× -××>															PQ3	
					-																OB /	
		9.0	Peak = 25kPa		9 -																	
		9.0	SPT = (2,4,4) N* = 8										100								SPT	-
					-								0		1						PQ3	-
					10 -		from 9.80m to 9.85m, with trace organic fragments.						10								OB/I	-
Т	ermi	nation	Reason: Re	fusa	l I me	et		1				11		I				1				1
S	hea	r Vane	No: 1620			DC	CP No:															
	GILIS	411\3.	This report is ba	sed o	n the	attach	ned field description for soil and roc	k, CN	IW Ge	eos	cien	ices	s - Fi	eld l	Log	gging	g Gu	ide,	Re	evisio	on 3 - A	April 2018.

	client roje ite L roje ate: oreh	: Neil ocatio ocatio ct No. 27/11 ole L on: 1	Group Limite 3 & Brigham C 3 N: Whenuapa : AKL2019-00 /2019 Docation: Refer 745259.0mE:	d Creel 140 <u>r to s</u> 592	k Ro	ad Jan 0.0m	Logged by: Th	ζ	Che	cked	ł by	/: TC	6	<u>Sca</u>	le:	1:5 0m	50 ho	N rizor	Sh	Geosciences
Kell	Groundwater Groundwater	Sam	27.00m	RL (m)	Depth (m)	Graphic Log	Datum: AUCKHT 1946 Material Description Soli: Soli symbol; soli type; colour; structure; bedding; plasticity; sensitivity; additional comments. (origin/geological unit) Rock: Colour; fabric; rock name; additional comments. (origin/geological unit)	Moisture Condition	Consistency/ Relative Density	Weat	herin	Jw Becovery	RQD	Sur Est Sti	vey ؟ imated rength	Sou	De Spa (m 09-00	e: H	Drilling Method/ Support	Held GPS Structure & Other Observations Discontinuities: Depth; Defect Number; Defect Type; Dip; Defect Shape; Roughness; Aperture; Infill; Seepage; Spacing; Block Size; Block Shape; Remarks
		10.5 10.5	Peak = 58kPa Residual = 15kPa SPT = (4,6,9) N* = 15	16.7			ML: Sandy SILT: dark grey interbedded with clay layers. Low plasticity. (Waitemata Group)		St to VSt			100							SPT	-
		12.0 12.0	SPT = (14,30,20/75mm) N* = 50+	15.5			Grey mottled dark grey, SANDSTONE. Weathered to Silty SAND fine to medium sand. (Waitemata Group)					100 100							SPT OB / PQ3	
		13.2	Peak = UTP SPT = (32,50/95mm) Nc =	14.5 14.2	- - - - - - - - - - - - - - - - - - -		Grey SILTSTONE. Weathered to a Sandy SILT, grey, medium to coarse. (Waitemata Group) Grey mottled dark grey, SANDSTONE. Weathered to Silty SAND fine to medium sand.					0 100							SPT OB / PQ3	
			50+	13.2	14 -		(Waitemata Group) Grey, SANDSTONE. (Waitemata Group) from 14.00m to 14.30m, Core loss due to core bound.					32							т / наз	13.8-14.0m:Dl,
		15.5	SPT = (50/115mm) Nc = 50+	11.9 11.7		×××: ×××:	Grey, SILTSTONE. (Waitemata Group) Grey, SANDSTONE. (Waitemata Group) Borehole terminated at 15.50 m					0	2						S Р TT/HQ3 Т	14.7-14.9m:5,DI,5°,UN,R,CL, CN, 15.0m:1,B,ST,R,GA,IF,(Z), 15.0m:1,B,5°,PL,S,CL, 15.2-15.4m:4,B,5°,UN,R,CL,C N, 15.4m:1,CN,5°,PL,S,CL, 15.4m:1,DI,
					16 -	-														-
					17 -	· • • • • •														-
					18	-														
					20 -	- - - - - - -														
T S F	ermi heai lema	nation Vane arks:	Reason: Re No: 1620	fusa	l me	t DC	CP No:	<u> </u>				s - Fi	eld			iide	Re		h 3 - A	.pril 2018

Client: Neil Group Ltd

Project: Trig & Brigham Creek Road Location: Whenuapai

Project No: AKL2019-0040

Date: 27/11/19

Logged by: TK Checked by: TG Position: 1745259.0 E, 5926130.0 N Elevation: RL 27.0m Hole Diameter: 100mm Angle from Horizontal: 90° Plant: Tractor Rig Contractor: Prodrill



MH02-19: 0m to 2.86m



MH02-19: 2.86m to 7.2m



Client: Neil Group Ltd

Project: Trig & Brigham Creek Road

Location: Whenuapai

Project No: AKL2019-0040

Date: 27/11/19

Logged by: TK Checked by: TG Position: 1745259.0 E, 5926130.0 N Elevation: RL 27.0m Hole Diameter: 100mm Angle from Horizontal: 90° Plant: Tractor Rig Contractor: Prodrill



MH02-19: 7.2m to 10.32m



MH02-19: 10.32m to 13.2m



Client: Neil Group Ltd

Project: Trig & Brigham Creek Road Location: Whenuapai

Project No: AKL2019-0040

Date: 27/11/19

Logged by: TK Checked by: TG Position: 1745259.0 E, 5926130.0 N Elevation: RL 27.0m Hole Diameter: 100mm Angle from Horizontal: 90° Plant: Tractor Rig Contractor: Prodrill



MH02-19: 13.2m to 15.5m



C F S	TEST PIT LOG - TP01-19 Client: Neil Group Limited Project: Trig & Brigham Creek Road Site Location: Whenuapai Project No.: AKL2019-0040 Date: 26/11/2019 Test Pit Location: Refer to site plan Logged by: JW Checked by: TG Scale: 1:25 Sheet 1 of 1													
L T)ate: 2 est Pi	26/11/2019 t Location: Re	efer t	o sit	te pla	n Logged by: JW Checked by: TG	Sc	ale:	1:2	25	Sheet 1 of 1			
F	Positio	n: 1745206.0)mE;	59	2597	4.0mN Projection: NZTM	Pit [Dime	nsions: 3	3.0m b	y 2.0m			
E	levati	on:Elevation:	27.0	0m		Datum: AUCKHT 1946	Sur	vey S	Dvnamic	Hand I	Held GPS Structure & Other Observations			
dwater	Sam	ples & Insitu Tests	(E	Ű.	ic Log	Material Description Soil: Soil symbol; soil type; colour; structure; bedding; plasticity; sensitivity; additional	sture	stency/ Densit	Penetron (Blows/10	neter 0mm)	Discontinuities: Depth; Defect			
Groun	Depth	Type & Results	R	Dept	Graph	comments. (origin/geological unit) Rock: Colour; fabric; rock name; additional comments. (origin/geological unit)	Mois	Consis telative	5 10 1	5 20	Shape; Roughness; Aperture; Infill; Seepage; Spacing; Block Size;			
			27.0		-	OL: TOPSOIL		L L			Block Shape; Remarks			
	0.5	Peak = UTP	26.8	-		ML: Clayey SILT: brown, orange, grey and black. Low plasticity. Trace gravel, concrete and old drain pipe. (Uncontrolled Fill)								
	1.0	Peak = >200kPa Residual = 48kPa	26.0	1 -		CH: CLAY with some silt: light grey streaked orange. High plasticity. (Puketoka Formation)	-							
	1.5	Peak = 224+ kPa		-			м	VSt to H						
	2.0	Peak = 192kPa Residual = 112kPa		2 -										
	2.5	Peak = 163kPa Residual = 74kPa	24.4	-		MH: Clayey SILT: light grey mottled orange. High plasticity. (Puketoka Formation)	_							
	3.0	Peak = 144kPa Residual = 51kPa		3 -		Test pit terminated at 3.00 m								
				-										
				4 -										
				-										
			4	5 -										
F	ermin Shear Io: Remar	ation Reason Vane 2081 ks: Groundw This report	: Tai rater	not o	dept E enco	h reached DCP No: untered. attached field description for soil and rock, CMW Geosciences - Field	Loggi	ng Gu	ide, Revisi	on 3 - A	, pril 2018.			

TEST PIT PHOTOGRAPHS: TP01-19

Client: Neil Group Limited Project: Trig & Brigham Creek Road Location: Whenuapai Project No: AKL2019-0040

Date: 26/11/2019

Logged by: JW Checked by: TG Position: E: 1745206 N: 5925974 Elevation: 27.0m

Dimensions: 3.0m x 2.0m Termination Depth: 3.0m Plant: 20T Excavator Contractor: Abernethy Contractors

ences

Sheet No. 1 of 1



TP01-19 – TEST PIT EXCAVATION

	TES		LO	G	- T	P02-19									
C	Project	:: Trig & Brigh	imite iam (a Cree	ek Ro	ad									
	Site Lo	cation: When	uapa o_oc	ai MO					ſ						
	Date: 2	26/11/2019	10-00	,40									Geosciences		
	Test Pi	t Location: Re	efer t	o sit	te pla	n Logged by: JW Checked by: TC	Sc Pit I	ale: Dime	nsio	1 ns [.]	:25	n h	Sheet 1 of 1		
E	Elevati	on:Elevation:	25.5	50m	2000	Datum: AUCKHT 1946	Sur	vey S	Sour	ce:	Han	nd F	Held GPS		
/ater	Sam	ples & Insitu Tests	Ê	Ê	Log	Material Description	e e	ncy/ ensity	Dy P	nam eneti	nic Cone rometer		Structure & Other Observations		
groundw	Denth	Type & Results	RL (m	Depth (Braphic	Soil: Soil symbol; soil type; colour; structure; bedding; plasticity; sensitivity; additional comments. (origin/geological unit) Rock: Colour; fabric; rock name; additional comments. (origin/geological unit)	Moistu Conditi	onsiste lative D	(0)	40] 45. 0	, ,	Number; Defect Type; Dip; Defect Shape; Roughness; Aperture; Infill; Scorege: Species; Plock Size;		
0	Depin	Type & Results	25.5					G IS	5	10	15 2	0	Seepage; Spacing; Block Size; Block Shape; Remarks		
													-		
			25.3			CH: Silty CLAY with minor topsoil: brown streaked orange and grey. Rootlets. Trace organics. Very loosely compacted.							-		
						(Uncontrolled Fill)							-		
	0.5	Peak = 48kPa Residual = 13kPa		-			М	F					-		
													-		
													-		
◄	1.0	Peak = 77kPa		1 -	1000	at 1.00m, perched aroundwater and trace organics							-		
	Residual = 29kPa														
													-		
	1.5	Peak = 51kPa Residual = 19kPa	24.0	-		CH: Organic stained Silty CLAY with some organics: dark grey streaked black Hinhly plasticity	W to	St					-		
					<u></u>	(Puketoka Formation)							-		
					<u> </u>								-		
	2.0	Peak = 83kPa		2 -	-x^	Toot nit termineted at 2.00 m							2.0m: yellow nova coil at the —		
		Residual = 29kPa			-	lest pit terminated at 2.00 m							base of test pit		
													-		
					-										
				-	-								-		
					-								-		
													-		
				3 -	-								-		
					-								-		
					-								-		
													-		
				-	-								-		
													-		
													-		
					-								-		
				4 -	-										
					-								-		
					1										
				-											
					-								-		
					-								-		
				_	-								-		
	<u> </u>	ation D	<u> </u>	5 -	-								-		
	ermin Shear	ation Reason Vane 2081	i: le	rmin	nated Г	eariy due to nova coil encountered.)CP No:									
1 F	vo: Remar	ks: Perched	grou	ndw	ater	at 1.0m.									
		This report	t is ba	sed o	on the	attached field description for soil and rock, CMW Geosciences - Field	d Loggi	ng Gι	uide, F	Revi	ision 3	- A	pril 2018.		

TEST PIT PHOTOGRAPHS: TP02-19

Client: Neil Group Limited Project: Trig & Brigham Creek Road Location: Whenuapai Project No: AKL2019-0040

Date: 26/11/2019

Logged by: JW Checked by: TG Position: E: 1745227 N: 5926000 Elevation: 25.50m Dimensions: 3.0m x 2.5m Termination Depth: 2.0m Plant: 20T Excavator Contractor: Abernethy Contractors



TP02-19 – TEST PIT EXCAVATION





	ΓES	T PIT I	_0	G	- T	P03-19						
	lient: Proiect	Neil Group Li	imite am (d Cree	k Ro	ad						
s	Site Lo	cation: When	uapa	ai	K I KO							
P r	vroject	No.: AKL201 6/11/2019	9-00	140						Λ	Λ	Geosciences
Т	est Pi	t Location: Re	əfer t	o sit	e pla	n Logged by: JW Checked by: TG	Sca	ale:		1::	25	Sheet 1 of 1
P	ositio levati	n: 1745219.(on:Elevation:)mE; 25.4	592 10m	2603	6.0mN Projection: NZTM Datum: AUCKHT 1946	Pit E Surv	Dime	nsio Sour	ns: (3.0m l Hand	by 2.0m Held GPS
<u>ت</u>	Sam	nles & Insitu Tests	20.4		DD DD			isity		ynamic	Cone	Structure & Other Observations
undwat			RL (m)	apth (m	aphic Lo	Naterial Description Soil: Soil symbol; soil type; colour; structure; bedding; plasticity; sensitivity; additional comments. (origin/geological unit)	loisture	nsistend ive Der	(B	lows/10	00mm)	Discontinuities: Depth; Defect Number; Defect Type; Dip; Defect Shape: Roughness: Aperture: Infill:
Gro	Depth	Type & Results		ă	0 22	Rock: Colour; fabric; rock name; additional comments. (origin/geological unit)	≥0	Cor Relat	5	10	15 20	Seepage; Spacing; Block Size; Block Shape; Remarks
			25.4			OL: TOPSOIL						
			20.2			CH: Silty CLAY with trace organics: orange, brown, grey and black. High plasticity. Trace pipe, trace concrete. Loosely compacted.						
						at 0.30m, large block of concrete, 0.4m x 0.4m						-
	0.5	Peak = 72kPa Residual = 29kPa		-								-
								St				
	1.0	Peak = 80kPa		1 -			м					
		Residual = 32kPa										
			-									
					<u>†-</u>	(Puketoka Formation)						
	1.5	Peak = 128kPa Residual = 61kPa		-	<u>E-</u>							-
					<u> -</u> _							
					<u>+</u>			VSt				
	2.0	Peak = 131kPa		2-	E-:	at 1.90m, moist to wet	M					
	2.0	Residual = 64kPa		2		Test pit terminated at 2.00 m						-
					-							
												-
				-								-
				3 -								
												-
				-								-
												-
				4 -								
					-							
												-
				-								
												-
		<u> </u>	<u> </u>	5 -	1							
J	ermina hear	ation Reason ^{Vane} 2∩81	: Tai	rget	dept г	h reached DCP No:						
	lo: Remar	ks: No aroun	idwa	ter e	ncou	intered.						
		This report	t is ba	sed c	n the	attached field description for soil and rock, CMW Geosciences - Field	Loggii	ng Gu	iide, F	Revis	on 3 - /	April 2018.

TEST PIT PHOTOGRAPHS: TP03-19

Client: Neil Group Limited Project: Trig & Brigham Creek Road Location: Whenuapai Project No: AKL2019-0040

Date: 26/11/2019

Logged by: JW Checked by: TG Position: E: 1745219 N: 5926036 Elevation: 25.40m Dimensions: 3.0m x 2.0m Termination Depth: 2.0m Plant: 20T Excavator Contractor: Abernethy Contractors

Geosciences

Sheet No. 1 of 1



TP03-19 – TEST PIT EXCAVATION

TEST PIT LOG - TP04-19 Client: Neil Group Limited Project: Trig & Brigham Creek Road															
F	Project Site Lo	: Trig & Brigh cation: When	iam (iuapa	Cree ai	ek Ro	ad						• -			
F	Project	No.: AKL201 6/11/2019	9-00)40							Λ		Geosciences		
	est Pit	Location: Re	efer t	o si	te pla	n Logged by: JW Checked by: TO	Sca	ale:		1:	25		Sheet 1 of 1		
F E	ositioi Elevatio	n: 1745272.0 on:Elevation:)mE; 23.0	59 00m	2603	2.0mN Projection: NZTM Datum: AUCKHT 1946	Pit L Surv	Jime vey S	nsic Sour	ns: ce:	3.0r Har	n b nd F	y 2.0m Held GPS		
vater	Samp	oles & Insitu Tests	Ê	(L)	Log	Material Description	ion	incy/ ensity	D F (B	ynamic enetro	Cone meter)	Structure & Other Observations		
Groundv	Depth	Type & Results	RL (n	Depth	Graphic	Soil: Soil symbol; soil type; colour; structure; bedding; plasticity; sensitivity; additional comments. (origin/geological unit) Rock: Colour; fabric; rock name; additional comments. (origin/geological unit)	Moistu Condit	Consiste elative D	5	10	15 2	20	Number; Defect Type; Dip; Defect Shape; Roughness; Aperture; Infill; Seepage; Spacing; Block Size;		
			23.0		-	OL: TOPSOIL		° Å	Ĭ			Ľ	Block Shape; Remarks		
			22.8		1	MI - Clavey SILT with organics: dark brown I ow plasticity	_						-		
			22.7			(Puketoka Formation) CH: Silty CLAY: grey mottled orange. High plasticity. Organic staining.	1						-		
	0.5	Peak = 147kPa Residual = 35kPa			<u>×</u> _×	(Puketoka Formation)							-		
							W	VSt					-		
													-		
	1.0	Peak = 160kPa		1 -						_			-		
T	12	Residual = 83KPa													
	1.2 Peak = 176kPa Residual = 80kPa Test pit terminated at 1.20 m														
				2 -									-		
					-								-		
					-								-		
					-								-		
					-								-		
													-		
					-								-		
				3 -									_		
													-		
					-								-		
													-		
					-								-		
													-		
				4 -					\vdash	+					
					-								-		
													-		
					-								-		
					-										
					-								- - -		
				5 -							<u> </u>				
3	ermin Shear	ation Reason Vane 2081	: Ta	rget	dept г	n reached CP No:									
N F	lo: Remarl	ks: Groundw	ater	see	ے page	observed at 1.2m.									
		This report	t is ba	sed o	on the	attached field description for soil and rock, CMW Geosciences - Field	Loggi	ng Gu	ide, I	Revis	ion 3	3 - A	pril 2018.		

TEST PIT PHOTOGRAPHS: TP04-19

Client: Neil Group Limited Project: Trig & Brigham Creek Road Location: Whenuapai Project No: AKL2019-0040

Date: 26/11/2019

Logged by: JW Checked by: TG Position: E: 1745272 N: 5926032 Elevation: 23.0m Dimensions: 3.0m x 2.0m Termination Depth: 1.2m Plant: 20T Excavator Contractor: Abernethy Contractors

Geosciences

Sheet No. 1 of 1

CMW



TP04-19 – TEST PIT EXCAVATION

TEST PIT LOG - TP05-19																	
Client: Neil Group Limited																	
	Site Location: Whenuapai																
F	Project No.: AKL2019-0040																
Test Pit Location: Refer to site plan Locaced by: JW Checked by: TG Scale: 1.25 Sheet 1 of 1																	
Position: 1745271.0mE; 5925996.0mN Projection: NZTM Pit Dimensions: 3.5m by 2.0m																	
E	levati	on:Elevation:	21.4	0m		Datum: AUCKHT 1946	Sur	vey \$ ≥	Sou	rce: Dynam	Ha ic Cor	and I	Held GPS Structure & Other Observations				
Samples & Insitu Tests						Material Description Soil: Soil symbol; soil type; colour; structure; bedding; plasticity; sensitivity; additional	sture dition	stency/ Densi	Penetrometer (Blows/100mm)			er m)	Discontinuities: Depth; Defect				
Grour	Depth	Type & Results	R	Dep	Grapt	comments. (origin/geological unit) Rock: Colour; fabric; rock name; additional comments. (origin/geological unit)	Moi Con	Consi Relative	5	5 10] 15	20	Shape; Roughness; Aperture; Infill; Seepage; Spacing; Block Size;				
			21.4			OL: TOPSOIL					T		- Block Shape, Remarks				
			21.2			CH: Silty CLAY: orange, brown, grey and black. High plasticity. Trace pipe,	-						-				
						concrete, gravel, cobbles, cloth and plastic. (Uncontrolled Fill)							-				
	0.5	Peak = 147kPa											-				
	0.0	Residual = 35kPa											-				
							м						-				
													-				
	1.0	Peak = >200kPa Residual = 51kPa		1 -		at 1.00m, well compacted						-					
													-				
		Peak = 157kPa Residual = 45kPa				at 1.20m, trace concrete		VSt					-				
													-				
	1.5			-		at 1.50m, moist to wet with trace organics							-				
		Peak = 125kPa Residual = 51kPa											-				
	2.0		19.6			CH: CLAY with some silt: grey, black, orange and brown. High plasticity.	-						-				
				2 -		(uncontrolled Fill)							-				
													-				
						OL: Buried TOPSOIL CH: Silty CLAY with organics: grey mottled orange. High plasticity. Organic	M to W						-				
		Peak = 64kPa Residual = 42kPa											-				
-	2.5		40.0	-									-				
			18.7					St to VSt					-				
				-		staining throughout. (Puketoka Formation)											
	3.0	Peak = 131kPa		3 -		- · · · · · · · · · · · · · · · · · · ·											
		Residual = 48kPa				Test pit terminated at 3.00 m							-				
													-				
													-				
											-						
													-				
													-				
				4 -													
													-				
													-				
				. 													
													-				
													-				
<u> </u>			<u> </u>	5 -													
	Shear Vane 2081 DCP No:																
N F	No:Remarks: Groundwater seepage observed at 2.6m in the topsoil.																
		This report	is ba	sed o	n the a	attached field description for soil and rock, CMW Geosciences - Field	Loggi	ng Gι	uide,	Revi	sion	3 - A	pril 2018.				

TEST PIT PHOTOGRAPHS: TP05-19

Client: Neil Group Limited Project: Trig & Brigham Creek Road Location: Whenuapai Project No: AKL2019-0040

Date: 26/11/2019

Logged by: JW Checked by: TG Position: E: 1745271 N: 5925996 Elevation: 21.40m Dimensions: 3.5m x 2.0m Termination Depth: 3.0m Plant: 20T Excavator Contractor: Abernethy Contractors

CMW Geosciences

Sheet No. 1 of 1



TP05-19 – TEST PIT EXCAVATION

TEST PIT LOG - TP06-19														
Client: Neil Group Limited Project: Trig & Brigham Creek Road														
Site Location: Whenuapai														
Date: 26/11/2019														
	Iest Pit Location: Refer to site plan Logged by: JW Checked by: TG Scale: 1:25 Sheet 1 of 1 Position: 1745331.0mE; 5926017.0mN Projection: NZTM Pit Dimensions: 3.0m by 2.0m													
E	Elevati	on:Elevation:	20.0	0m		Datum: Al	JCKHT 1946	S	Surv	vey S	Sourc	e: F	land	Held GPS
vater	Sam	ples & Insitu Tests	Ê	(L	c Log	Soil: Soil symbol: soil type: /	Material Description pe; colour; structure; bedding; plasticity; sensitivity; additional comments. (origin/geological unit) ; rock name; additional comments. (origin/geological unit)	ditional	tion	ency/ Density	Dynamic Cone Penetrometer (Blows/100mm)		Cone eter)mm)	Structure & Other Observations Discontinuities: Depth; Defect Number; Defect Type; Dip; Defect Shape; Roughness; Aperture; Infili; Seepage; Spacing; Block Size;
Ground	Depth	Type & Results	RL (Depth	Graphic	Rock: Colour; fabric; ro		nit)	Condi	Consist elative I	5	5 10 15 20		
			20.0		-	OL: TOPSOIL				- œ .				Block Shape; Remarks
			19.8			ML: Clayey SILT: brown (Puketoka Formation)	. Low plasticity. With large roots.							
		5 1	19.6			CH: Silty CLAY: grey mo	ottled orange. High plasticity.							-
	0.5	Peak = >200kPa Residual = 51kPa		-		(Fukeloka Formation)								
									м	VSt to St				
	1.0	Peak = 147kPa Residual = 48kPa	19.0	1 -		CH: CLAY with minor sil (Puketoka Formation)	t: grey mottled orange. High plasticity.							
					<u> </u>									
	1.5	Peak = 83kPa Residual = 32kPa		-		Т	est pit terminated at 1.50 m							-
					-									
					-									
				2 -						-				
					-									-
					-									
				-	-									-
					-									
				3 -	-									
					-									-
					-									-
					-									-
					-									
					-									
					-									
				4 -	-									
					-									-
				-										
														-
				5 -										
Į	ermin Shear	ation Reason Vane	: Ta	rget	depth	n reached				1				
N F	lo: Remar	ks: Groundw	ater	not	ם encou	untered.								
		This report	is ba	sed c	on the a	attached field descriptio	on for soil and rock, CMW Geosciences	s - Field Lo	oggir	ng Gui	ide, R	evisio	on 3	April 2018.

TEST PIT PHOTOGRAPHS: TP06-19

Client: Neil Group Limited Project: Trig & Brigham Creek Road Location: Whenuapai Project No: AKL2019-0040

Date: 26/11/2019

Logged by: JW Checked by: TG Position: E: 1745331 N: 5926017 Elevation: 20.0m Dimensions: 3.0m x 2.0m Termination Depth: 1.5m Plant: 20T Excavator Contractor: Abernethy Contractors

CMW Geosciences

Sheet No. 1 of 1



TP06-19 – TEST PIT EXCAVATION

TEST PIT LOG - TP07-19													
Client: Neil Group Limited Project: Trig & Brigham Creek Road													
Site Location: Whenuapai													
Project No.: AKL2019-0040 Date: 26/11/2019													
Test Pit Location: Refer to site plan Logged by: JW Checked by: TG Scale: 1:25 Sheet 1 of 1													
	Elevation: Elevation: 18.50m Datum: AUCKHT 1946 Survey Source: Hand Held GPS												
ater	Sam	ples & Insitu Tests		(L	60-	Material Description Soil: Soil symbol; soil type; colour; structure; bedding; plasticity; sensitivity; additional comments. (origin/geological unit) Rock: Colour: fabric: rock name: additional comments. (origin/geological unit)	e E	ncy/ ensity	1	Dynamic Cone Penetrometer			Structure & Other Observations
roundw:	Durth		RL (m	Jepth (r	araphic I		Moistur Conditic	onsister ative De	(Blows	s/100	mm)	Number; Defect Type; Dip; Defect Shape; Roughness; Aperture; Infil;
Ū	Depth	Type & Results	18.5		0			с В В С	5	5 10	0 15	5 20	Seepage; Spacing; Block Size; Block Shape; Remarks
			18.4	-		CH: Silty CLAY: orange, brown, grey and black. High plasticity. Trace	_						
				-		rootlets, trace gravel, trace concrete and loosely compacted. (Uncontrolled Fill)							
	0.5	Book = 141kBo											-
	0.5	Residual = 19kPa											
							м	VSt					
				-									-
	1.0	Peak = 192kPa Residual = 96kPa	17.4	1 -								+	
			17.3	-		OL: Buried TOPSOIL CH: CLAY with some silt: grey streaked orange. High plasticity. Trace	_						-
					E-1	rootlets, trace limonite staining. Trace organic staining. (Puketoka Formation)							
	1.5	Peak = 147kPa Residual = 64kPa		-		Test pit terminated at 1.50 m							-
				-									-
													-
				2 -								_	
				-									-
				-									
													-
				-	-								-
				-									-
				-	-								-
				3 -									
				-									-
				-	-								-
				-									
				-									-
				-									
				4 -							_	_	
				-	-								-
				-									-
				- -									-
				-	-								-
				-									-
				-	-								-
	<u> </u>		<u> </u>	5 -	1								
	Shear Vane 2081 DCP No:												
	Remar	ks: Groundw	ater	no e	ncou	intered.							
1		This report	is ba	sed o	on the	attached field description for soil and rock, CMW Geosciences - Field	l Loggi	ng Gu	iide,	Rev	visio	n 3 - A	April 2018.

TEST PIT PHOTOGRAPHS: TP07-19

Client: Neil Group Limited Project: Trig & Brigham Creek Road Location: Whenuapai Project No: AKL2019-0040

Date: 26/11/2019

Logged by: JW Checked by: TG Position: E: 1745289 N: 5925956 Elevation: 18.50m Dimensions: 3.0m x 2.0m Termination Depth: 1.5m Plant: 20T Excavator Contractor: Abernethy Contractors

Geosciences

Sheet No. 1 of 1

CMW



TP07-19 – TEST PIT EXCAVATION














ŀ	HAND AUGER BOREHOLE LOG - HA01-20										
C P	lient: roject:	Neil Construc 71 Trig Roa	ction d	Limi	ited						
S P	Site Location: Whenuapai Project No.: AKL2020-0231										
	ate: 1	6/09/2020						Geo	scier		5
P	oreno ositior	ie Location: 8	bee s)mE;	592	2620	Logged by: FS Checked by: JW Scale: 1:25 3.0mN Projection: NZTM			Sheet 1	of 1	
E	levatio	on: 33.00m				Datum: AUCKHT1946 Survey Source: AC C	Geom	aps	Dynon	in Con	
dwater	Samp	les & Insitu Tests	Ē	(m) H	nic Log	Material Description Soil: Soil symbol: soil type: colour: structure terding: plasticity: sensitivity: additional comments. (origin/geological unit)	sture dition	stency/ Density	Penet (Blows	romete 100mn	r n)
Groun	Depth	Type & Results	RL	Dept	Grapt	Rock: Colour; fabric; rock name; additional comments. (origin/geological unit)	Con	Consi Relative	5	0 1	5
			33.0			OL: TOPSOIL: dark brown.	M to				
			20.7				w				
	0.4	Peak = 155kPa	32.7			ML: Clayey SILT: brown mottled dark brown and orange. Very stiff, low plasticity, moderately sensitive. (Puketoka Formation)					
		Residual - 40kPa		-							
						at 0.60m, becoming greyish brown mottled orange.					
	0.8	Peak = 134kPa Residual = 37kPa									
				1 -		at 1.00m, becoming light grey mottled orange.					
	1.2	Peak = 142kPa									
		Residual = 40kPa					м				
				-							
	1.6	Peak = 174kPa Residual = 67kPa									
	2.0	Deak - 136kDa		2							
	2.0	Residual = 67kPa		-				VSt			
			30.7								
	2.4	Peak = 110kPa Residual = 64kPa				CH: CLAY with minor silt: light grey. Still to very still, high plasticity, insensitive to moderately sensitive. (Puketoka Formation)					
				-	<u> </u>						
		D									
	2.8	Residual = 64kPa			Ē						
				3 -	<u> </u>	at 3.00m, becoming light grey mottled orange.	M to W				
	3.2	Peak = 110kPa Residual = 70kPa				at 3.20m, becoming dark grey with minor black mottling.					
					<u>E-</u>						
				-							
	3.6	Peak = 123kPa Residual = 60kPa			E						
09-202 0					<u> </u>	at 3.80m, silt becoming absent.					
4 ^{16−}	4.0	Peak = 104kPa		4 -	<u> </u>		vv				
		Residual – Orkra									
					=	at 4.20m, becoming grey.					
	4.4	Peak = 78kPa Residual = 60kPa		_	<u>E-</u>		s	St			
					ŧ	at 4.60m, becoming dark grey.					
	4.8	Peak = 88kPa			 						
		rkesioual = 67kPa		E -	E						
Т	erminati	on Reason: Tar	det de	enth r	eache	Borehole terminated at 5.0 m					
s	hear Va	ne No: 1620	901 UC	-Puil	E	ICP No:					
R	emarks	: Groundwater e	encou	ntere	d at 4	.0m.					
		This report	is ba	sed o	n the	attached field description for soil and rock, CMW Geosciences - Field Logging Guide, Revision 3 -	April	2018.			



F S	HAN Client: Project	ND AUG Neil Construc : 71 Trig Road cation: When	SE ction d uapa	R Limi	BC ited	REHOLE LOG - HA03-20					
P C	Project No.: AKL2020-0231 Date: 16/09/2020										
B P	oreho ositio	le Location: S 1: 1744834.0	See s)mE;	site 59:	olan 2606	Logged by: FS Checked by: JW Scale: 1:25 1.0mN Projection: NZTM		5	Sheet '	l of	1
E	levatio	on: 40.00m				Datum: AUCKHT1946 Survey Source: AC C	Geom	aps	Dyna	nic Co	ne
Groundwater	Samples & Insitu Tests E E B 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0							Consistency/ telative Densit	Blows (Blows	tromete s/100m	er m) 15
	0.4	Peak - 01kPa	40.0			OL: TOPSOIL: dark brown.		Ľ			
	0.4	Residual = 13kPa	39.0	-		ML: Clayey SILT: greyish brown mottled orange. Stiff to very stiff, low plasticity, insensitive to sensitive. (Puketoka Formation)					
	0.8	Peak = 185kPa Residual = 63kPa		1 -		at 0.80m, becoming light brownish grey mottled orange.					
	1.2	Peak = UTP		-		at 1.20m, becoming light grey mottled orange.	м				
	1.6	Peak = 160kPa Residual = 88kPa									
	2.0	Peak = 150kPa Residual = 96kPa		2 -							
	2.4	Peak = 174kPa Residual = 110kPa		-		at 2.60m, becoming light grey mottled orange and red.		St to VSt			
	2.8	Peak = 147kPa Residual = 90kPa		3 -		at 3 10m becoming grange motfled grav					
	3.2	Peak = 120kPa Residual = 64kPa		_							
	3.6	Peak = 131kPa Residual = 70kPa					W				
09-2020	4.0	Peak = 118kPa Residual = 67kPa		4 -		at 4.20m, becoming light brownish grey.	W to S				
, e	4.4	Peak = 96kPa Residual = 64kPa	35.5	-		CL: CLAY with minor silt: dark grey. Very stiff, low plasticity, insensitive. (Puketoka Formation)					
	4.8	Peak = 160kPa Residual = 90kPa		5 -		Borehole terminated at 5.0 m		VSt			
Т	Termination Reason: Target depth reached										
S R	hear Va emarks	ne No: 1620 : Groundwater e	encou	ntere	D d at 4.	CP No: 4m.					
		This report	is ba	sed o	on the	attached field description for soil and rock, CMW Geosciences - Field Logging Guide, Revision 3 -	April	2018.			

C P S	HAND AUGER BOREHOLE LOG - HA04-20 Client: Neil Construction Limited Project: 71 Trig Road Site Location: Whenuapai									
P D	Project No.: AKL2020-0231 Date: 16/09/2020									
B	Borehole Location: See site plan Logged by: FS Checked by: JW Scale: 1:25 Sheet 1 of 1 Desition: 1744002 0mE; 5006108 0mN Desition: NZTM									
	levatio	n: 1744922.0 on: 32.75m	me;	594	26198	Datum: AUCKHT1946 Survey Source: AC C	Geor	aps		
Broundwater	Samp	oles & Insitu Tests	RL (m)	Depth (m)	Braphic Log	Material Description Soil: Soil symbol; soil type; colour; structure; bedding; plasticity; sensitivity; additional comments. (origin/geological unit) Rock: Colour; fabric; rock name; additional comments. (origin/geological unit)	Moisture Condition	onsistency/ lative Density	Dynami Penetro (Blows/1	c Cone ometer 00mm) 0 15
0	Doput		32.8			OL: TOPSOIL: dark brown.	м	Rec		
	0.4	Peak = 94kPa Residual = 27kPa	32.4			ML: Clayey SILT: orangeish brown. Stiff to very stiff, low plasticity, insensitive to moderately sensitive. (Puketoka Formation)				
	0.8	Peak = 134kPa Residual = 59kPa		1 -	XXXXXXXX XXXXXX XXXXXXXXXXXXXXXXXXXXXX	at 0.80m, becoming grey mottled orange.				
	1.2	Peak = 136kPa Residual = 53kPa								
	1.6	Peak = 127kPa Residual = 67kPa		-		at 1.50m, becoming light grey.	M to W			
	2.0	Peak = 147kPa Residual = 78kPa		2 -		at 1.90m, becoming grey and dark grey.		St to		
	2.4	Peak = 131kPa Residual = 67kPa			× × × × × × × × × ×	at 2.20m, becoming light grey motiled brange.		VSt		
-09-2020	2.8	Peak = 126kPa Residual = 62kPa		3 -	× ×× ×× ×× × × ×× ×× × × ×× ×× ×× ×					
A ¹⁶	3.2	Peak = 107kPa Residual = 59kPa								
	3.6	Peak = 88kPa Residual = 43kPa				at 3.50m, becoming with some fine grained sand, clay becoming absent.				
	4.0	Peak = 91kPa Residual = 43kPa	28.6	4		M. Condu CII Tuliakt kommink annu mettled annang. Van etiff lauralesticitu inconsitius to mederatelu	s			
	4.4	Peak = 110kPa Residual = 56kPa				sensitive. Sand is fine grained, poorly graded. (Puketoka Formation)		VSt		
	4.8	Peak = 115kPa Residual = 53kPa		5 -		Borehole terminated at 5.0 m				
Te	Termination Reason: Target depth reached									
S R	hear Va emarks	ne No: : Groundwater e	encou	ntere	D d at 3.	CP No: 2m.				
		This report	is ba	sed o	n the a	attached field description for soil and rock, CMW Geosciences - Field Logging Guide, Revision 3 -	April	2018.		









ł	HAND AUGER BOREHOLE LOG - HA09-20											
	Client: Project	Neil Construc	ction d	Lin	nited							
s	Site Location: Whenuapai											
F	Project No.: AKL2020-0231 Date: 16/09/2020 CMW Geosciences											
E	Boreho	ble Location: S	See s	site	plan	Logged by: CK Checked by: JW Scale: 1:25		5	Shee	et 1	of 1	
F	Positio	n: 1744999.2 on: 35 90m	2mE;	59	2603	4.5mN Projection: NZTM Datum: AUCKHT1946 Survey Source: AC (eom	ans				
	Sam	ples & Insitu Tests		-	bo			/sity	D	ynamie	c Con	e r
oundwat			RL (m)	epth (m	aphic Lo	Material Description Soil: Soil symbol; soil type; colour; structure; bedding; plasticity; sensitivity; additional comments. (origin/geological unit) Rock: Colour; fabric; rock name; additional comments. (origin/geological unit)	Aoisture	nsistend tive Der	(B	lows/1	00mr	n)
ğ	Depth	Type & Results	05.0		5		20	Rela		, 10	J 1	5
			35.9			IOPSOIL:						
			35.7			CH: CLAY with minor silt: Orange brown mottled grey and dark brown. High plasticity. (Puketoka Formation)						
	0.4	Peak = UTP	ak = UTP									
		5 1 100 5			1							
	0.8	Residual = 74kPa										
				1 ·	1-							
	1.2	Peak = UTP										
						from 1.30m to 2.30m, becoming whitish grey streaked orange						
					<u> </u>							
	1.6	Peak = >193										
	2.0	Peak = UTP		2 -			D					
					1	from 2 30m to 2 70m becoming streaked ninkish red		VSt				
	2.4	Peak = UTP										
					1-1							
	2.8	Peak = UTP			 	from 2.70m to 2.90m, becoming dark brown streaked black with trace fine grained sand						
						from 2.90m to 3.30m, becoming light grey streaked dark brown						
				3 ·	<u>+</u>							
	3.2	Peak = 149kPa Residual = 110kPa			1 							
						from 3.30m to 5.00m, becoming whitish grey streaked orange and yellow						
	3.6	Peak = 152kPa			1-							
	0.0	Residual = 124kPa										
					£							
	4.0	Peak = 108kPa Residual = 80kPa		4 ·	<u>+</u>					_		
							м					
	4.4	Peak = 77kPa Residual = 55kPa										
							w					
∎	4.8	Peak = 83kPa						st				
		rtesiduai = 52KPa		5								
		ion Reason: Tor		anth	reacho	Borehole terminated at 5.0 m						
s	hear Va	ane No: 2904	gorut	Put	D	CP No:						
R	lemarks	: Groundwater e	encou	nter	ed at 4.	8m.						
		This report	is ba	sed	on the	attached field description for soil and rock, CMW Geosciences - Field Logging Guide, Revision 3	April	2018.				



Appendix D: Laboratory Test Results



DETERMINATION OF THE WATER CONTENT, LIQUID LIMIT, PLASTIC LIMIT, PLASTICITY INDEX & LINEAR SHRINKAGE TEST METHOD NZS 4402 : 1986 TEST 2.1, 2.2, 2.3, 2.4 & 2.6

Project Name :	Trig & Brigham Creek		
		Project No :	19 0382 00
Client :	CMW Geosciences	Page :	1 of 1
Address :	PO Box 300206	Date of Order :	28.11.19
	Albany, Auckland 0754		
		Sample Method :	Hand Auger
Attention :	Tessa	Sample Date :	26.11.19
		Sampled By :	CMW Geosciences Ltd

Test Details :

Test performed on : History : Whole Sample Natural

Sample	Location	Denth	Liquid Limit	Plastic	Plasticity	Linear Shrinkage	Natural Water Content
No.	Location	(m)	(LL)	(PL)	(PI)	(LS)	(%)
366J	MH01-19	2.5 to 3.0	95	28	67	-	51.8

Comments :

Tested By:	СК	Date :	29.11.19 to 06.12.19
Calculated By :	СК	Date :	09.12.19
Checked By :	ZH	Date :	09.12.19



Please reply to: W.E. Campton

CMW Geosciences Ltd. PO Box 300 206 Albany Auckland 0752

Babbage Geotechnical Laboratory Level 4 68 Beach Road Auckland 1010 Telephone E-mail

P O Box 2027 New Zealand 64-9-367 4954 wec@babbage.co.nz

Page 1 of 4

Job Number: 63186#L **BGL Registration Number: 2752** Checked by: JF

12th December 2019

Attention: **TESSA GALBRAITH**

ONE DIMENSIONAL CONSOLIDATION TESTING

Dear Tessa,

TRIG & BRIGHAM CREEK ROAD (your reference AKL2019-0040) Re: Report Number: 63186#L/Consol MH01-19 5.00 - 5.50m

Borehole No: MH01-19 Sample No: TUBE **Depth: 5.00 – 5.50m**

The following report presents the results of one dimensional consolidation testing at BGL of a 60mm diameter undisturbed push-tube soil sample delivered to this laboratory on the 3rd of December 2019. Our instructions were to carry out a one dimensional consolidation test using cycle times that would give both the $\sqrt{T_{90}}$ and T_{50} values, and using a standard pressure sequence.

The push-tube sample was tested in accordance with the following standards:

Water Content:	NZS4402:1986:Test 2.1
One Dimensional Consolidation:	NZS4402:1986:Test 7.1

Please note that consolidation cycles were of a variable time duration, and hence is a departure from the test standard which states that the cycle time period for the consolidation loads after the initial cycle should be of approximately the same length. The time for each consolidation cycle was determined by observing consolidation data until the secondary consolidation could be assessed. Subsequent load cycles were taken to at least the time of the previous cycle.

The sample was extruded from the tube in small increments & trimmed into the consolidation ring, until the sample protruded from both sides of the ring. A wire was then used to cut the sample from the soil remaining in the tube, and a scalpel and straight edge was used to trim the sample flat in the ring.

These test results only relate to the sample tested. The values of my shown on the table have been calculated for each pressure increment, using void ratio difference for that increment. Note that a solid density value of 2.65t/m³ was assumed for this test, and is not part of the IANZ endorsement for this report. This test was carried out in a laboratory in which the temperature is kept at $20^{\circ}C \pm 3^{\circ}C$.





Job Number: 63186#L 12th December 2019 Page 2 of 4

As per the reporting requirements of NZS4402: 1986: Test 2.1: water content is reported to two significant figures for values below 10%, and to three significant figures for values of 10% or greater. As per the reporting requirements of NZS4402: 1986: Test 7.1: one dimensional consolidation, the coefficients of consolidation (c_v 's), and coefficients of volume compressibility (m_v 's) are reported to two significant figures.

Note that the Coefficient of Secondary Compression (C_{sec}) and the Coefficient of Permeability (k) values reported on page 4 have been calculated based on the methods described in "Manual of Soil Laboratory Testing Volume 2: Permeability, Shear Strength & Compressibility Tests" by K.H. Head & R.J. Epps, 3rd Edition, 2011. The Coefficient of Permeability values were calculated using the $c_v(log)$ values determined in the test. The reporting of these figures is not part of NZS4402:1986:Test 7.1, therefore these figures are not part of the IANZ endorsement for this report.

Sample Description (not part of BGL IANZ Accreditation)

MH01-19 / TUBE / 5.00 – 5.50m: CLAY, minor fine sand, stiff, moderately to highly plastic, light grey with white speckles, slightly moist, occasional black organics.

Each test result is data obtained at a specific test location. The nature and continuity of subsoil conditions away from the test area could vary from the data recovered during this testing, therefore the test results relate only to the sample as-received, and relate only to the sample under test.

Thank you for the opportunity to carry out this testing. If you have any queries regarding the content of this report please contact the person authorising this report below at your convenience.

Yours faithfully,

Wayne Campton Signatory (Laboratory Manager) Babbage Geotechnical Laboratory



All tests reported herein have been performed in accordance with the laboratory's scope of accreditation. This report may not be reproduced except in full & with written approval from BGL.



SPECIMEN HISTORY

undisturbed / disturbed / remoulded / compacted / other: Specimen from 60mm diameter push-tube Compacted with NZ Standard Compaction effort / other compaction:

SPECIMEN PREPARATION

Extruded from 60mm diameter tube straight into consol ring in small increments & trimmed into consol ring. Both sides of ring then trimmed flat with a scalpel & straight edge.

TEST DETAILS

Consol machine number:	1		Surface area of top of sample:	1960	mm ²
Consol ring number: Sample diameter:	1A 49.95	mm	Solid density of soil particles (assumed / measured):	2.65	t/m ³

DCI	Job No:	Reg. No:	Sheet	of	Version No:	8
BCIL	63186#L	2752	4	4	Issue Date:	October 2017
	PROJECT:				Auth. By:	WEC
Babbage Geotechnical Laboratory	TRIG 8	& BRIC	SHAM	CRE	EK RC	DAD
ONE DIMENSIONA	L CONSOLIDAT	ION		Tested By:	ТН	December 2019
Test Method: NZS4402:1986:T		Compiled By:	TH	11-Dec-19		
Test Method: NZS4402:1986:T		Checked By:	JF	12-Dec-19		

Borehole No: MH01-19 Sample No: TUBE Depth: 5.00 - 5.50m

Applied Pressure	Incremental Deflection	Specimen Thickness	Compression Ratio	Height of Voids	Void Ratio	Coefficient of Volume Compressibility	Coeffi Consolid	cient of dation - c _v	
						m _v	(log time)	(sqrt time)	
kPa	mm	mm		mm	е	m²/MN	m ² /year	m²/year	
4.2	0.000	21.150	1.000	9.899	0.880				
16.3	-0.030	21.180	1.001	9.929	0.883	sample swelled			
32.0	-0.005	21.185	1.002	9.934	0.883	sample swelled			
63.2	0.007	21.178	1.001	9.927	0.882	0.011	13	21	
125.8	0.088	21.090	0.997	9.840	0.875	0.066	6.9	12	
250.9	0.297	20.794	0.983	9.543	0.848	0.11	6.1	7.9	
501.1	0.602	20.191	0.955	8.941	0.795	0.12	4.3	5.9	
1001.6	1.029	19.163	0.906	7.912	0.703	0.10	3.2	3.7	
250.9	-0.278	19.441	0.919	8.190	0.728		BACKLOAD	1	
32.0	-0.718	20.159	0.953	8.908	0.792	BACKLOAD 2			

Coefficient of Secondary Compression - C _{sec}								
Applied Pressure	C _{sec}							
sample	swelled							
sample swelled								
63.2	0.001							
125.8	0.001							
250.9	0.002							
501.1	0.005							
1001.6	0.008							

Coefficient of Permeability - k			
Applied Pressure	k (m/s)		
63.2	4.3E-11		
125.8	1.4E-10		
250.9	2.1E-10		
501.1	1.6E-10		
1001.6	1.0E-10		

INITIAL	FINAL
58.42	58.42
21 150	19.163 (after consolidation)
21.150	20.159 (after rebound)
33.2	31.2
1.41	1.56
11.251	11.251
0.880	0.703 (after consolidation)
0.880	0.792 (after rebound)
100.0	-
	58.42 21.150 33.2 1.41 11.251 0.880 100.0



Please reply to: W.E. Campton

CMW Geosciences Ltd. PO Box 300 206 Albany Auckland 0752 Babbage Geotechnical Laboratory Level 4 68 Beach Road P C Auckland 1010 Ne Telephone 64-E-mail we

P O Box 2027 New Zealand 64-9-367 4954 wec@babbage.co.nz

Page 1 of 4

Job Number: 63186#L BGL Registration Number: 2752 Checked by: JF

12th December 2019

Attention: **TESSA GALBRAITH**

ONE DIMENSIONAL CONSOLIDATION TESTING

Dear Tessa,

Re: TRIG & BRIGHAM CREEK ROAD (your reference AKL2019-0040) Report Number: 63186#L/Consol MH02-19 3.45 – 3.95m

Borehole No: MH02-19 Sample No: TUBE Depth: 3.45 – 3.95m

The following report presents the results of one dimensional consolidation testing at BGL of a 60mm diameter undisturbed push-tube soil sample delivered to this laboratory on the 3rd of December 2019. Our instructions were to carry out a one dimensional consolidation test using cycle times that would give both the $\sqrt{T_{90}}$ and T_{50} values, and using a standard pressure sequence.

The push-tube sample was tested in accordance with the following standards:

Water Content:	NZS4402:1986:Test 2.1
One Dimensional Consolidation:	NZS4402:1986:Test 7.1

Please note that consolidation cycles were of a variable time duration, and hence is a departure from the test standard which states that the cycle time period for the consolidation loads after the initial cycle should be of approximately the same length. The time for each consolidation cycle was determined by observing consolidation data until the secondary consolidation could be assessed. Subsequent load cycles were taken to at least the time of the previous cycle.

The sample was extruded from the tube in small increments & trimmed into the consolidation ring, until the sample protruded from both sides of the ring. A wire was then used to cut the sample from the soil remaining in the tube, and a scalpel and straight edge was used to trim the sample flat in the ring.

These test results only relate to the sample tested. The values of m_v shown on the table have been calculated for each pressure increment, using void ratio difference for that increment. Note that a solid density value of 2.65t/m³ was assumed for this test, and is not part of the IANZ endorsement for this report. This test was carried out in a laboratory in which the temperature is kept at 20°C ± 3°C.



Job Number: 63186#L 12th December 2019 Page 2 of 4

As per the reporting requirements of NZS4402: 1986: Test 2.1: water content is reported to two significant figures for values below 10%, and to three significant figures for values of 10% or greater. As per the reporting requirements of NZS4402: 1986: Test 7.1: one dimensional consolidation, the coefficients of consolidation (c_v 's), and coefficients of volume compressibility (m_v 's) are reported to two significant figures.

Note that the Coefficient of Secondary Compression (C_{sec}) and the Coefficient of Permeability (k) values reported on page 4 have been calculated based on the methods described in "Manual of Soil Laboratory Testing Volume 2: Permeability, Shear Strength & Compressibility Tests" by K.H. Head & R.J. Epps, 3rd Edition, 2011. The Coefficient of Permeability values were calculated using the $c_v(log)$ values determined in the test. The reporting of these figures is not part of NZS4402:1986:Test 7.1, therefore these figures are not part of the IANZ endorsement for this report.

Sample Description (not part of BGL IANZ Accreditation)

MH02-19 / TUBE / 3.45 – 3.95m: SILT, firm, slightly to moderately plastic, grey, moist.

Each test result is data obtained at a specific test location. The nature and continuity of subsoil conditions away from the test area could vary from the data recovered during this testing, therefore the test results relate only to the sample as-received, and relate only to the sample under test.

Thank you for the opportunity to carry out this testing. If you have any queries regarding the content of this report please contact the person authorising this report below at your convenience.

Yours faithfully,

Wayne Campton Signatory (Laboratory Manager) Babbage Geotechnical Laboratory



All tests reported herein have been performed in accordance with the laboratory's scope of accreditation. This report may not be reproduced except in full & with written approval from BGL.



Specimen from 60mm diameter push-tube

Compacted with NZ Standard Compaction effort / other compaction:

SPECIMEN PREPARATION

Extruded from 60mm diameter tube in small increments & trimmed into consol ring. Both sides of ring then trimmed flat with a scalpel & straight edge.

TEST DETAILS

Consol ring number: 2B So Sample diameter: 50.58 mm	lid density of soil particles (assumed / measured):	2.65	t/m ³

DCI	Job No:	Reg. No:	Sheet	of	Version No:	8
	63186#L	2752	4	4	Issue Date:	October 2017
	PROJECT:				Auth. By:	WEC
Babbage Geotechnical Laboratory	TRIG 8		SHAM		EK RO	DAD
ONE DIMENSIONAL CONSOLIDATION			Tested By:	TH	Dec 2019	
Test Method: NZS4402:1986:Test 2.1 - Water Content				Compiled By:	TH	9-Dec-19
Test Method: NZS4402:1986:Test 7.1 - Consolidation				Checked By:	JF	12-Dec-19

Borehole No: MH02-19 Sample No: TUBE

Depth: **3.45 - 3.95m**

Applied Pressure	Incremental Deflection	Specimen Thickness	Compression Ratio	Height of Voids	Void Ratio	Coefficient of Volume Compressibilit	Coeffi Consolid	cient of dation - c _v
riccouro	Demotion	Therates		10100		m _v	(log time)	(sqrt time)
kPa	mm	mm		mm	e	m²/MN	m²/year	m²/year
4.8	0.000	19.890	1.000	11.252	1.303			
16.6	0.166	19.724	0.992	11.086	1.283		seating cycle	9
31.9	0.086	19.638	0.987	11.000	1.273	0.28	24	22
62.4	0.165	19.473	0.979	10.835	1.254	0.28	25	30
123.4	0.267	19.206	0.966	10.568	1.223	0.22	29	29
245.4	0.590	18.616	0.936	9.978	1.155	0.25	26	28
489.5	1.061	17.555	0.883	8.917	1.032	0.23	24	27
977.5	1.388	16.167	0.813	7.529	0.872	0.16	16	24
245.4	-0.249	16.416	0.825	7.777	0.900		BACKLOAD	1
31.9	-0.487	16.903	0.850	8.265	0.957		BACKLOAD	2

Coefficient of Secondary Compression - C _{sec}			
Applied Pressure	C _{sec}		
The logarithm of time graphs of the Coefficient of Secor values for th	s did not allow determination ndary Compression (Csec) nese cycles.		
123.4	0.001		
245.4	0.002		
489.5	0.004		
977.5	0.003		

Coefficient of Permeability - k			
Applied Pressure	k (m/s)		
31.9	2.1E-09		
62.4	2.2E-09		
123.4	2.0E-09		
245.4	2.0E-09		
489.5	1.7E-09		
977.5	8.1E-10		

	INITIAL	FINAL		
Mass of dry specimen (g)	46.00	46.00		
Thickness of specimen (mm)	19 890	16.167 (after consolidation)		
mickness of specificity (mill)		16.903 (after rebound)		
Water Content (%)	45.1	37.6		
Dry Density (t/m ³)	1.15	1.42		
Height of soil particles (mm)	8.638	8.638		
Void Ratio	1.303	0.872 (after consolidation)		
		0.957 (after rebound)		
Degree of saturation (%)	91.7	-		

Appendix E: Natural Hazards Risk Assessment



NATURAL HAZARDS RISK ASSESSMENT FOR LAND SUBDIVISION AT TRIG & BRIGHAM CREEK ROAD

A. CONTEXT

Section 106 of the Resource Management Act (RMA) requires an assessment of the risk from natural hazards to be carried out when considering the granting of a subdivision consent. S106 RMA specifically states that the assessment must consider the combined effect of the natural hazard likelihood and material damage to land, other land or structures (consequence).

Section 2 of the RMA defines natural hazards as any atmospheric or earth or water related occurrence (including earthquake, tsunami, erosion, volcanic and geothermal activity, landslip, subsidence, sedimentation, wind, drought, fire or flooding) the action of which adversely affects or may adversely affect human life, property, or other aspects of the environment.

This appendix to CMW report reference AKL2019-0040AM Rev.0 sets out the criteria for and presents the results of an assessment of the geotechnical-related natural hazards associated with this proposed subdivision development. The remaining hazards, i.e. tsunami, wind, drought, fire and flooding hazards are not covered by this assessment.

B. BASIS OF ASSESSMENT

B1. Risk Classification

The occurrence of natural hazards and their potential impacts on the proposed subdivision development is assessed in terms of risk significance, which is based on likelihood and consequence factors. A risk table is used to help assess the likelihood and consequence factors, the form of which used by CMW for this project is presented in Table B1.

	Table B1: Natural Hazard Risk Classification					
				Consequence		
		Insignificant 1	Minor 2	Moderate 3	Major 4	Catastrophic 5
	Almost Certain	Medium	High	Very high	Extreme	Extreme
	5	5	10	15	20	25
po	Likely	Low	Medium	High	Very high	Extreme
	4	4	8	12	16	20
kelihoo	Moderate	Low	Medium	Medium	High	Very high
	3	3	6	9	12	15
Ē	Unlikely	Very low	Low	Medium	Medium	High
	2	2	4	6	8	10
	Rare	Very low	Very low	Low	Low	Medium
	1	1	2	3	4	5

B2. Likelihood

With respect to assessing the likelihood or chance of the risk occurring, the qualitative definitions used by CMW for this project are provided in Table B2 for each likelihood classification.

	Table B2: Qualitative Natural Hazard Likelihood Definitions			
1	Rare	The natural hazard is not expected to occur during the design life of the project		
2	Unlikely	The natural hazard is unlikely, but may occur during the design life		
3	Moderate	The natural hazard will probably occur at some time during the life of the project		
4	Likely	The natural hazard is expected to occur during the design life of the project		
5	Almost Certain	The natural hazard will almost definitely occur during the design life of the project		

B3. Consequence

In terms of determining the consequence or severity of the natural hazard occurring, the qualitative definitions used by CMW for this project are provided in Table B3 for each consequence classification.

	Table B3: Qualitative Natural Hazard Consequence Definitions				
1	Insignificant	Very minor to no damage, not requiring any repair, no people at risk, no economic effect to landowners.			
2	Minor	Minor damage to land only, any repairs can be considered normal property maintenance no people at risk, very minor economic effect.			
3	Moderate	Some damage to land requiring repair to reinstate within few months, minor cosmetic damage to buildings being within relevant code tolerances, does not require immediate repair, no people at risk, minor economic effect.			
4	Major	Significant damage to land requiring immediate repair, damage to buildings beyond serviceable limits requiring repair, no collapse of structures, perceptible effect to people, no risk to life, considerable economic effect.			
5	Catastrophic	Major damage to land and buildings, possible structure collapse requiring replacement, risk to life, major economic effect or possible site abandonment.			

B4. Risk Acceptance

It is recognised that the natural hazard risk assessment provided herein is qualitative and, due to the wide range of possible geohazards that could occur, is somewhat subjective. Other methods are available to quantitatively assess an acceptable level of geotechnical related natural hazard risk, such as defining an acceptable factor of safety with respect to slope stability or acceptable differential ground settlements with respect to recommended building code limits.

Therefore, to give this qualitative natural hazard risk assessment some relevance to more commonly adopted numerical or quantitative geotechnical assessment techniques, a residual risk rating of very low to medium (risk value = 1 to 9 inclusive) is considered an acceptable result for the proposed subdivision development.

A risk rating of high to extreme (risk value \geq 10) is considered an unacceptable result for the proposed subdivision development.

C. RISK ASSESSMENT

The natural hazards relevant to this proposed subdivision development and adjacent, potentially affected land have been assessed with respect to the criteria outlined above.

Assessment is based on proposed post development ground conditions with and without any geotechnical controls. The latent risk was first assessed with the site in its proposed developed state to consider the risks to the development and surrounding land, including assessment of land modifications from the pre-existing natural state, without any implemented geotechnical controls. The specific geotechnical mitigation measures and engineering design solutions outlined in the table below and CMW report, where relevant, were then considered to determine the natural hazard residual risk remaining after the proposed controls have been implemented.

Table C1: Natural Hazard Risk Assessment Results									
RMA S2 Hazard	Description	Proposed Site Latent Risk of Damage to Land / Structures		ed Site Risk of o Land / ures	Comments and Geotechnical Control	Proposed Site Residual Risk of Damage to Land / Structures OR Acceleration/ Worsening of Hazard with Geotechnical Controls Implemented			
	Likelihood Consequence Risk Rating			Likelihood	Consequence	Risk Rating			
Earthquake	Fault Rupture	1	4	Low 4	Low proximity to active faults	1	4	Low 4	
	Liquefaction Induced Flooding and/ or Subsidence	2	4	Medium 8	Depth of cover / mainly clay soils based on existing information	2	4	Medium 8	
	Lateral Spread	2	4	Medium 8	Depth of cover / mainly clay soils based on existing information	2	4	Medium 8	

Results of this assessment are presented in Table C1 below.

Volcanic Activity	Ash & Pyroclastic Falls	1	5	Medium 5	Low proximity to active volcanoes	1	5	Medium 5
	Lava flows & Lahars	1	5	Medium 5	Low proximity to active volcanoes	1	5	Medium 5
Geothermal Activity	Formation of geysers, hot springs, fumaroles, mud pools	1	5	Medium 5	Low proximity to active geothermal areas	1	5	Medium 5
Erosion	Cut Batters	4	3	High 12	Max 1:3 gradient / surface water control / benches	2	3	Medium 6
	Fill Batters	4	3	High 12	Max 1:3 gradient / surface water control / benches	2	3	Medium 6
Landslip	Global Slope Instability	4	4	Very High 16	Slope gradient / drainage / retaining walls	2	4	Medium 8
	Soil Creep	3	4	High 12	Foundation design / footing depth / slope regrading	2	4	Medium 8
	Bearing Capacity Failure	2	4	Medium 8	Undercut and replace / fill embankment gradient	2	4	Medium 8
	Cut & Fill Batter Instability	2	4	Medium 8	Surface water controls, regrading	1	4	Low 4
Subsidence	Expansive soils	5	4	Extreme 20	Foundation design for highly expansive soils	5	1	Medium 5
	Sinkholes	1	4	Low 4	Unlikely in existing geology	1	4	Low 4
	Soft Soils	2	4	Medium 8	Undercut and remove / pre-load / ground improvement / pile	1	4	Low 4
Sedimentation	Rockfall, debris inundation	2	4	Medium 8	Regrade slope / earthworks	1	4	Low 4

Notes:

- Assessments include the impact of the proposed subdivision works on adjacent properties.
- The following reference(s) contain information on the hazards contained in this assessment and the non-geotechnical hazards that have not been included:
 - $\circ \quad \text{Auckland} \quad$
 - https://aucklandcouncil.maps.arcgis.com/apps/MapSeries/index.html?appid=81aa3de1 3b114be9b529018ee3c649c8

Appendix F: Stability Analyses Results

Project Job No.	Trig & Brigham Creek Road AKL2019-0040			
Date	6/12/2019	* seismic peak ground ac	celeration at 0.115g	
ву	16			
Section	Case	Failure Mode	Min. FS	Acceptance Comments
Α	Existing Contour - Normal ground water table	Circular	2.6	У
	Existing Contour - Highly saturated (GW @ 0.5m)	Circular	1.5	У
	Existing Contour - Seismic, Normal GWT	Circular	1.7	У
	Proposed Contour - Normal ground water table	Circular	2.8	у
	Proposed Contour - Highly saturated	Circular	2.4	ý
	Proposed Contour - Highly saturated (Drainage Failure)	Circular	2.1	y
	Proposed Contour - Seismic, Normal GWT	Circular	1.7	У
В	Existing Contour - Normal ground water table	Circular	5.0	У
	Existing Contour - Highly saturated (GW @ 0.5m)	Circular	3.0	У
	Existing Contour - Seismic, Normal GWT	Circular	2.4	У
	Proposed Contour - Normal ground water table	Circular	2.3	У
	Proposed Contour - Highly saturated	Circular	1.6	У
	Proposed Contour - Highly saturated (Drainage Failure)	Circular	1.4	У
	Proposed Contour - Seismic, Normal GWT	Circular	1.7	У
с	Existing Contour - Normal ground water table	Circular	4.8	У
	Existing Contour - Highly saturated (GW @ 0.5m)	Circular	3.1	У
	Existing Contour - Seismic, Normal GWT	Circular	2.3	У
	Proposed Contour - Normal ground water table	Circular	2.3	У
	Proposed Contour - Highly saturated	Circular	1.7	У
	Proposed Contour - Highly saturated (Drainage Failure)	Circular	1.5	У
	Proposed Contour - Seismic, Normal GWT	Circular	1.6	У
D	Existing Contour - Normal ground water table	Circular	3.1	У
	Existing Contour - Highly saturated (GW @ 0.5m)	Circular	1.9	У
	Existing Contour - Seismic, Normal GWT	Circular	2.0	У
	Proposed Contour - Normal ground water table	Circular	1.8	У
	Proposed Contour - Highly saturated	Circular	1.4	У
	Proposed Contour - Highly saturated (Drainage Failure)	Circular	1.3	У
	Proposed Contour - Seismic, Normal GWT	Circular	1.4	У

Material Name	Color	Unit Weight (kN/m3) Strength Type (Cohesion (kPa)	Phi (deg)	Water Surface	Ни Туре	Hu
Engineered Fill		18	Mohr-Coulomb 5 3		30	Water Surface	Custom	1
Uncertified Fill		17	Mohr-Coulomb	2	27	Water Surface	Custom	1
Puketoka Formation Alluvium		17	Mohr-Coulomb	2	27	Water Surface	Custom	1
Residual Waitemata Group Soils		18	Mohr-Coulomb	3	30	Water Surface	Custom	1
Waitemata Group Transition Zone		18	Mohr-Coulomb	10	30	Water Surface	Custom	1
Waitemata Group Bedrock		18	Mohr-Coulomb	10	40	Water Surface	Custom	1



	Material Name Color Unit Weig (kN/m3)	ht Strength Type Cohesion Phi (kPa) Wa	Water Surface Hu Type Hu	
	Engineered Fill 18	Mohr-Coulomb 5 30 Wa	Water Surface Custom 1	
-	Uncertified Fill 17	Mohr-Coulomb 2 27 Wa	Water Surface Custom 1	
	Puketoka Formation Alluvium	Mohr-Coulomb 2 27 Wa	Water Surface Custom 1	
	Residual Waitemata Group Soils 18	Mohr-Coulomb 3 30 Wa	Water Surface Custom 1	
	Waitemata Group Transition Zone 18	Mohr-Coulomb 10 30 Wa	Water Surface Custom 1	
	Waitemata Group Bedrock 18	Mohr-Coulomb 10 40 Wa	Water Surface Custom 1	
	Proposed Profile	20.00 kN/m2 61-10 100000000	2.4 (I) (I) (I) (I) (I) (I) (I) (I) (I) (I)	
0 20	<u>40 60</u>	80	100 120 140	160
Project		Trig & E	Brigham Creek Road	
Analysis Descript	tion	Section A - Proposed	d Profile, Circular, High Groundwater	
	Date: 6/12/2019	Scale 1:750	Company Neil Construciton Ltd	
SLIDE WALLET 8.029 Geosciences Figure No	- Job No	AKL2019-0040	File Name AKL2019-0040_AA'_PR_CA_HGW_061219	

-

	Material Name Color Unit Weight (kN/m3) Strength Type Cohesion (kPa) Phi (deg (deg (deg 2) Engineered Fill Image: Strength Type Xmm	Water SurfaceHu TypeHuWater SurfaceCustom1Water SurfaceCustom1Water SurfaceCustom1Water SurfaceCustom1Water SurfaceCustom1Water SurfaceCustom1Water SurfaceCustom1
20.00 kN/m2 Existing Profile	ELECTRON CONTRACTOR CO	C.1 GE-LOHM W W Sie Boundary
	0 60 80	100 120 140 160
Project	Trig 8	Brigham Creek Road
Analysis Descript	section A - Proposed Profile,	Circular, High Groundwater (Drainage Failure)
	Date: 6/12/2019 Scale 1:750	Company Neil Construciton Ltd
SLIDENWERKET 8.029 Geosciences	- ^{Job No} AKL2019-0040	File Name AKL2019-0040_AA'_PR_CA_HGW_061219 (Drainage Failure)





-											
		Material Name	Color	Unit Weight (kN/m3)	Strength Type	Cohesion (kPa)	Phi (deg)	Water Surface	Hu Type	Hu	
		Engineered Fill		18	Mohr-Coulomb	5	30	Water Surface	Custom	1	
0	-	Puketoka Formation Alluvium		17	Mohr-Coulomb	2	27	Water Surface	Custom	1	
<u>ں</u>		Residual Waitemata Group Soils		18	Mohr-Coulomb	3	30	Water Surface	Custom	1	
		Waitemata Group Transition Zone		18	Mohr-Coulomb	10	30	Water Surface	Custom	1	
-		Waitemata Group Bedrock		18	Mohr-Coulomb	10	40	Water Surface	Custom	1	
40	existing Profile	20.00 kN/n	n2		HA22-19	HA06-19	CP105-19	20.0) kN/m2		Proposed Profile Farthworks Extent Site Boundary
-								•			
					l	l					=
20											
-											
0-											
	0 20	40		60			80			1	100 120 140
	Project Trig & Brigham Creek Road										
		Analysis Description		Se	ction B - Pr	oposec	l Pro	file, Circul	ar, High	Gr	roundwater (Drainage Failure)
		Drawn By G Date:	6	5/12/201	9	^{Scale} 1	:600) Comp	any		Neil Construciton Ltd
CLUD	Geoscience	Figure No -			Job No AKL	2019-(0040) File N	ame AKL2	201	19-0040_BB'_PR_CA_HGW_061219 (Drainage Failure)








Appendix G: Groundwater Impacts Assessment

AKL2020-0231 - Rev 1

Project name:

71 Trig Road, Whenuapai

Assessment of geotechnical aspects of proposed development with respect to the Auckland Unitary Plan Operative in Part (Updated 12 June 2020)

Chapter E: Auckland-wide rules, Natural resources»E7 Taking, using, damming and diversion of water and drilling»E7.6. Standards Permitted activities»E7.6.1. Permitted activities

»E7.6.1.6. Dewatering or groundwater level control associated with a groundwater diversion permitted under Standard E7.6.1.10

Condition		Geotechnical Interpretation of Compliance
	Non- Compliant	
1. The water take must not be geothermal water	Compliant	1. Groundwater is not geothermal.
2. The water take must not be for a period of more than 10 days where it occurs in peat soils, or 30 days in other types of soil or rock	Non - Compliant	2. There are no peat soils identified on this site. Groundwater diversion likely to be required for more than 30 days due to the
		proposed development levels.
3. The water take must only occur during construction	Non - Compliant	3. Groundwater diversion likely to extend beyond construction period.

Chapter E: Auckland-wide rules, Natural resources»E7 Taking, using, damming and diversion of water and drilling»E7.6. Standards Permitted activities»E7.6.1. Permitted activities

»E7.6.1.10. Diversion of groundwater caused by any excavation, (including trench) or tunnel

Condition		Geotechnical Interpretation of Compliance
1.All of the following activities are exempt from the Standards E7.6.1.10(2) – (6)	Non - Compliant	
a. pipes cables or tunnels including associated structures which are drilled or thrust and are less than 1.2m in external diameter	Compliant	a. No pipes greather than 1.2m are proposed.
b. pipes including associated structures up to 1.5m in external diameter where a closed faced or earth pressure balanced machine is used	Compliant	b. Not proposed for this site.
c. piles up to 1.5m in external diameter are exempt from these standards	Compliant	c. Not proposed for this site.
d. diversions for no longer than 10 days; or	Non - Compliant	d. Groundwater likely to be encountered therefore diversions may be required.
e. diversions for network utilities and road network linear trenching activities that are progressively opened, closed and stabilised where	Compliant	e. Service trench excavations are not part of this application.
the part of the trench that is open at any given time is no longer than 10 days		
2.Any excavation that extends below natural groundwater level, must not exceed:	Compliant	
a. 1ha in total area; and		a. Although excavations are likely to extend below the natural groundwater level, the affected area will be less than 1ha.
b. 6m depth below the natural ground level		b. Not applicable for this site as cut levels are only proposed to be a maximum of 3.0m below natural ground level.
3. The natural groundwater level must not be reduced by more than 2m on the boundary of any adjoining site.	Compliant	3. No groundwater drawdown anticipated at any site boundary as the proposed cuts grade awy from the boundary, with the maximum cut depth located approximately 10m away from the boundary.
4.any structure, excluding sheet piling that remains in place for no more than 30 days, that physically impedes the flow of groundwater through the site	Compliant	
must not:		
a. impede the flow of groundwater over a length of more than 20m; and		a. No potentially groundwater impeding structures of this nature are proposed for this site.
b.extend more than 2m below the natural groundwater level.		b. No potentially groundwater impeding structures of this nature are porposed for this site.
5. The distance to any existing building or structure (excluding timber fences and small structures on the boundary) on an adjoining site from the edge of any:	Compliant	
a.trench or open excavation that extends below natural groundwater level must be at least equal to the depth of the excavation		a. Trenches/excavations are not proposed to extend below the natural groundwater level.
b.tunnel or pipe with an external diameter of 0.2 - 1.5m that extends below natural groundwater level must be 2m or greater; or		b. Tunnels/pipes are not proposed to extend below the natural groundwater level.
c.a tunnel or pipe with an external diameter of up to 0.2m that extends below natural groundwater level has no separation requirement.		c. Noted.
6.The distance from the edge of any excavation that extends below natural groundwater level, must not be less than:	Compliant	
a.50m from the Wetland Management Areas Overlay		a. Greater than 50m from any Wetland Management Overlay
b.10m from a scheduled Historic Heritage Overlay; or		b. Greater than 10m from any Historic Heritage Overlay
c.10m from a lawful groundwater take.		c. Greater than 10m from any lawful groundwater take.



creating great places PLANNERS | SURVEYORS | ENGINEERS ARCHITECTS | ENVIRONMENTAL

This drawing and design remains the property of, and may not be reproduced or amended without the written permission of Cato Bolam Consultants Ltd. No liability shall be accepted for unauthorised use of this drawing and design.

Brigham Creek and Trig Road Whenuapai

71 Trig Road Bulk Earthworks Cut fill Contours

FOR RESOURCE CONSENT

Area Cut (m ²) Fill (m ²) Balance(m ²) Area Cut (m ²) Fill (m ²) Balance(m ²) Fordstm ² 2610 24510 2300(Cut) Notes: •••••••••••••••••••••••••••••••••••	Existing Stripped Surface to Finished Subgrade Surface Area Cut (m) Fill (m) Balance(m) Stores: Cot fill contours shown are derived from the finished surface ninus 300(m) thick of topsoil; finished subgrade surface assumes Existing stripped surface assumes the existing surface minus 300(m) thick of topsoil; finished subgrade surface assumes Submet thick of topsoil; finished subgrade surface assumes finished surface minus 200(m) thick of topsoil; finished subgrade surface Submet thick of topsoil; finished subgrade Cut to Fill Legend	20/01/2021 29/01/2021 14/04/2021 14/04/2021	DRAWN DATE 20/0	1/2021	ORIGINAL SCA 1:1	MLE ORI 500	SC 2 GINAL S	0/01/2021 IZE A3
Area Cut (m) Fill (m) Balance(m) Area Cut (m) Fill (m) Balance(m) Area Cut (m) Fill (m) Balance(m) 67031m² 28510 24510 2300(Cut) Notes: Image: Cut (m) Fill (m) Balance(m) • Cut fill contours shown are derived from the finished surface to existing surface. Existing stripped surface assumes the existing surface assumes finished surface assumes finished surface minus 200mm thick of topsoil; finished subgrade surface assumes finished surface minus 200mm thick of topsoil and 200mm deep trimming for the road at bulk earthworks stage. Out Cut to Fill Legend	Existing Stripped Surface to Finished Subgrade Surface Area Cut (m) Balance(m) 67031m ² 26810 24510 2300(Cut) Notes: Cut fill contours shown are derived from the finished surface ninus 300mm thick of topsoil; finished subgrade surface assumes finished surface minus 200mm thick of topsoil and 200mm deep trimming for the road at bulk earthworks stage. Submet thick of objecti; finished subgrade surface assumes finished surface minus 200mm thick of topsoil; finished surface assumes the existing Contours due to the context stage. Cut to Fill Legend 35 Existing Contours & Area Extent of Earthworks Fill Contours & Area Extent of Earthworks 200/17021 DBARM DREVEND MAME 1/4/4/201 DATE DRIGINAL SCALE ORIGINAL SCALE	20/01/2021 29/01/2021 14/04/2021 14/04/2021	DRAWN	1/000-	ORIGINAL SCA	LE ORI	SC 2 GINAL S	120/01/2021 IZE
Area Cut (m ²) Fill (m ²) Balance(m ²) Area Cut (m ²) Fill (m ²) Balance(m ²) Area Cut (m ²) Fill (m ²) Balance(m ²) Area Cut (m ²) Fill (m ²) Balance(m ²) Otom Area Cut (m ²) Fill (m ²) Balance(m ²) Notes: Cut (m ²) Fill (m ²) Balance(m ²) • Outsing stripped surface assumes the existing surface anius 300mm deep trimming for the road at bulk earthworks stage. Existing Contours and thick of topsoil and 200mm deep trimming for the road at bulk earthworks stage. • Out contours & fill Contours & Area Cut contours & Area • Out contours & Area Extent of Earthworks • Out contours & Area Fill Contours & Area • Out contours & Area Fill Contours & Area • Out contours & Area Fill Contours & Area • Out contours & Area Fill Contours & Area • Out contours & Area Fill Contours & Area • Out contours & Area State of Earthworks • Out contour contout contour contout contour contout contout c	Existing Stripped Surface to Finished Subgrade Subgrade Surface Image: Cut (m) Fill (m) Balance(m) Note: Cot fill contours shown are derived from the finished surface to existing surface. 2: String stripped surface assumes the existing surface minus 300mm thick of topsoil information subsections in the original surface assumes the existing Contours and Subgrade Surface assumes finished surface to the original surface assumes the existing Contours for the road at bulk earthworks stage. Image: Cut (m) Surface in the original subgrade assumes to the existing Contours for the road at bulk earthworks stage. Image: Cut (m) Surface in the original subgrade assumes to the existing Contours for the road at bulk earthworks stage. Image: Cut (m) Surface in the original subgrade assumes the existing Contours for the road at bulk earthworks stage. Image: Cut (m) Surface in the original subgrade assumes the existing Contours for the road at bulk earthworks stage. Image: Cut (m) Surface in the original subgrade assumes the existing Contours for the road at bulk earthworks. Image: Cut (m) Surface in the original subgrade assumes the existing Contours for the road at bulk earthworks. Image: Cut (m) Surface in the original subgrade assumes the existing Contours for the road at bulk earthworks. Image: Cut (m) Surface in the original subgrade assumes the existing contours for the road at bulk earthworks. Image: Cut (m) Surface assumes the existing contours for the original subgrade assumes the existing contours for the road subgrade assumes the existing contours for the origin subgrade assumes the existi	20/01/2021 29/01/2021 14/04/2021	DRAWN			Μ	SC 2	0/01/202
Area Cut (m ²) Fill (m ²) Balance(m ²) Area Cut (m ²) Fill (m ²) Balance(m ²) Area Cut (m ²) Fill (m ²) Balance(m ²) Area Cut (m ²) Fill (m ²) Balance(m ²) Otosting 26810 24510 2300(Cut) Notes: •••••••••••••••••••••••••••••••••••	Existing Stripped Surface to Finished Surface Surface Area Cut (m ²) Fill (m ²) Balance(m ²) Notes: • <td< th=""><th>20/01/2021</th><th>DEJURNED</th><th></th><th></th><th>1 14</th><th> 14</th><th></th></td<>	20/01/2021	DEJURNED			1 14	14	
Area Cut (m) Fill (m) Balance(m') 67031m ² 26810 24510 2300(Cut) Listing Stripped Surface to Finished Subgrade Surface Area Cut (m) Fill (m) Balance(m') 67031m ² 26810 24510 2300(Cut) Votes: Colspan="2">Cut (m) Fill (m) Balance(m') String Stripped Surface assumes the existing surface minus 300mm thick of topsoil and sourface assumes finished surface assumes finished surface assumes finished surface minus 200mm thick of topsoil and sourface minus 200mm thick of topsoil and source minus 200mm thick of topsoil and the antiworks stage. Image: Cut to Fill Legend Image: Cut contours & Area Image: Cut contours & Area Image: Cut to Fill Contours & Area Image: Cut contours & Area Image: Cut contours & Area Image: Cut to Fill Contours & Area Image: Cut contours & Area Image: Cut contours & Area Image: Cut to Fill Contours & Area Image: Cut contours & Area <	Existing Stripped Surface to Finished Subgrade Surface Area Cut (m ²) Fill (m ²) Balance(m ²) Solution 28810 24510 2300(Cut) Nets: Cut fill contours shown are derived from the finished surface to existing surface minus 300rm thick of topsoil and 200rm deep timming for the road at bulk earthworks stage: Image: Cut (m ²) Cut to Fill Legend					M	SC 7	0/01/202
Area Cut (m) Fill (m) Balance(m) <u>Area</u> Cut (m) Fill (m) Balance(m) <u>Bristing Stripped Surface to Finished Subgrade Surface</u> Area Cut (m) Fill (m) Balance(m) G7031m ² 26810 24510 2300(Cut) String Stripped Surface to Finished Subgrade Surface and Surface to existing surface minus Solution Shown are derived from the finished surface to existing surface minus Solution Surface assumes the existing surface minus Solution The road at bulk earthworks stage. Cut to Fill Legend	Existing Stripped Surface to Finished Subgrade Surface Area Cut (m ²) Fill (m ²) Balance(m ²) Notes: • Cut fill contours shown are derived from the finished surface to existing surface. • Disting stripped surface assumes the existing surface minus 300mm thick of topsoil, finished subgrade surface assumes finished surface assumes the existing surface minus 100mm thick of topsoil and 200mm deep trimming for the road at bulk earthworks stage. • Out fill Contours shown are derived from the finished surface to existing stripped surface assumes the existing surface minus 200mm thick of topsoil and 200mm deep trimming for the road at bulk earthworks stage. • Out fill Legend 0 - 35 - Existing Contours 0 - 2ero Contour 0 - 2ero Contour 0 - 2ero Contours 0 - 2ero Contour 0 - 2ero Contour 0 - 2ero Contours 0 - 2ero Contours 0 - 2ero Contour 0 - 2ero Contour 0 - 2ero Contour 0 - 2ero Contours 0 - 2ero Contour 0 - 2ero Cont					N/	ME	DATE
Area Cut (m) Fill (m) Balance(m) <u>Area</u> Cut (m) Fill (m) Balance(m) <u>Brising Stripped Surface to Finished Subgrade Surface</u> Area Cut (m) Fill (m) <u>Balance(m)</u> <u>Cut (m)</u> <u>Ellisting Stripped Surface</u> assumes <u>Balance(m)</u> <u>Balance(m)</u> <u>Existing Stripped Surface</u> <u>Balance(m)</u> <u>Balance(m)</u> <u>Balance(m)</u> <u>Stripped Surface</u> <u>Existing Stripped Surface</u> <u>Balance(m)</u> <u>Balance(m)</u> <u>Stripped Surface</u> <u>Balance(m)</u> <u>Cut Contours Surface</u> <u>Balance(m)</u> <u>Stripped Surface</u> <u>Balance(m)</u> <u>Cut Contours & Area</u> <u>Balance(m)</u> <u>Balance(m)</u> <u>Stripped Surface</u> <u>Balance(m)</u> <u>Cut Contours & Area</u> <u>Balance(m)</u> <u>Balance(m)</u> <u>Striped Surface</u> <td< th=""><th>Existing Stripped Surface to Finished Surface Surface Area Cut (m) Fill (m) Balance(m) Notes: • Cut fill contours shown are derived from the finished surface to existing surface. • Disting stripped surface assumes the existing surface minus 300mm thick of topsoil, finished subgrade surface assumes finished surface assumes the existing surface minus 100mm thick of topsoil and 200mm deep times of the road at bulk earthworks stage. • Out fill contours shown are derived from the finished surface to existing stripped surface assumes the existing surface minus 200mm thick of topsoil and 200mm deep times of the road at bulk earthworks stage. • Out fill Legend 35 - Existing Contours - 0 - Zero Contour - 0 - Zero Contour - 1 - Cut Contours & Area - Extent of Earthworks • Out Contours & Area - Extent of Earthworks • Out Contours & Area - Extent of Earthworks</th><th></th><th></th><th></th><th></th><th></th><th></th><th></th></td<>	Existing Stripped Surface to Finished Surface Surface Area Cut (m) Fill (m) Balance(m) Notes: • Cut fill contours shown are derived from the finished surface to existing surface. • Disting stripped surface assumes the existing surface minus 300mm thick of topsoil, finished subgrade surface assumes finished surface assumes the existing surface minus 100mm thick of topsoil and 200mm deep times of the road at bulk earthworks stage. • Out fill contours shown are derived from the finished surface to existing stripped surface assumes the existing surface minus 200mm thick of topsoil and 200mm deep times of the road at bulk earthworks stage. • Out fill Legend 35 - Existing Contours - 0 - Zero Contour - 0 - Zero Contour - 1 - Cut Contours & Area - Extent of Earthworks • Out Contours & Area - Extent of Earthworks • Out Contours & Area - Extent of Earthworks							
Area Cut (m ³) Fill (m ³) Balance(m ³) <u>Area</u> Cut (m ³) Fill (m ³) Balance(m ³) <u>Area</u> Cut (m ³) Fill (m ³) Balance(m ³) <u>Area</u> Cut (m ³) Fill (m ³) Balance(m ³) <u>Area</u> Cut (m ³) Fill (m ³) Balance(m ³) <u>Area</u> Cut (m ³) Fill (m ³) Balance(m ³) <u>Area</u> Cut (m ³) Fill (m ³) Balance(m ³) <u>Area</u> Cut (m ³) Fill (m ³) Balance(m ³) <u>Area</u> Cut (m ³) Fill (m ³) Balance(m ³) <u>Area</u> Cut (m ³) Existing Surface aninus <u>Soloment thick of topsoil</u> finished surface assumes finished surface minus <u>Area</u> Cut for Fill Legend <u>– Existing Contours</u> <u> Existing Contours</u> <u>– Existing Contours</u> Fill Contours & Area <u> Existing Contours</u> Fill Contours & Area Fill Contours & Area <u> Existing Contours</u> Fill Contours & Area Fill Contours & Area	Existing Stripped Surface to Finished Subgrade Surface Area Cut (m ²) Fill (m ³) Balance(m ³) Notes: • Control on the substrate of the substrate of existing surface minus 300mm thick of topsoil and 200mm deep trimming for the road at bulk earthworks stage: • Cut to Fill Legend • Out Contours & Area • Out C		_					
Area Cut (m) Fill (m) Balance(m) <u>Area</u> Cut (m) Cut (m) Cut (m) <u>Area</u> Cut (notours shown are derived from the finished surface minus 200mm thick of topsoil and 200mm deep timing for the road at bulk earthworks stage. <u>Area</u> <u>Cut to Fill Legend</u> <u>-</u> <u>-</u> Existing Contours <u>Area</u> <u>Cut Contours & Area</u> Fill Contours & Area Fill Contours & Area <u>Area</u> <u>Fill</u> <u>Cut Contours & Area</u> Fill Contours & Area <u>Area</u> <u>Area</u> <u>Extent of Earthworks</u> <u>Area</u> <u>Area</u> <	Area Cut (m) Fill (m) Balance(m) You Fill (m) Balance(m) Status Status Status • Cut (m) Fill (m) Balance(m) • Cut (m) Fill (m) Balance(m) • Cut (m) Status Status • Cut (m) Status Status • Cut (m) Status Status • Status Status Status							
Area Cut (m ³) Fill (m ³) Balance(m ³) <u>Existing Stripped Surface to Finished Subgrade Surface</u> Area Cut (m ³) Fill (m ³) Balance(m ³) 67031m ² 26810 24510 2300(Cut) Notes: • Cut fill contours shown are derived from the finished surface to existing surface. • Stifting stripped surface assumes the existing surface minus 200mm thick of topsoil and 200mm deep trimming for the read at bulk earthworks stage. • Out fill contours shown are derived from the finished surface minus 200mm thick of topsoil and 200mm deep trimming for the read at bulk earthworks stage. • Out fill Contours & fill (m ³) Cut to Fill Legend • Out Contours & Area • Out Contour </td <td><u>A solution of the construction of the constr</u></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td>	<u>A solution of the construction of the constr</u>							
Area Cut (m ³) Fill (m ³) Balance(m ³) <u>Area</u> Cut (m ³) Fill (m ³) Balance(m ³) <u>Area</u> Cut (m ³) Fill (m ³) Balance(m ³) <u>Area</u> Cut (m ³) Fill (m ³) Balance(m ³) <u>Area</u> Cut (m ³) Fill (m ³) Balance(m ³) <u>Area</u> Cut (m ³) Fill (m ³) Balance(m ³) <u>Area</u> Cut (m ³) Fill (m ³) Balance(m ³) <u>Area</u> Cut (m ³) Fill (m ³) Balance(m ³) <u>Area</u> Cut (m ³) Fill (m ³) Balance(m ³) <u>Area</u> Cut (m ³) Cut (m ³) Fill (m ³) <u>Stitus</u> Stitus stripped surface assumes the existing surface minus Stitus <u>Stitus</u> Stitus Stitus Stitus Cut contour deep trimming for the read at bulk earthworks stage. <u>Area</u> <u>Cut (m³) Cut Contours & Area <u>Cut Contours & Area</u> <u>Fill Contours & Area</u> <u>Area</u> <u>Area</u> <u>Fill Contours & Area</u> <u>Fill Contours & Area</u> <u>Area</u> <u>Area</u> <u>Area</u> <u>Area</u> <u>Area</u> <u>Area</u> </u>	<u>A solution of the read at bulk and the finite of the read at bulk and the finite of the read at bu</u>	7E						
Area Cut (m') Fill (m) Balance(m) 67031m ² 2050 21250 9000(Cut) Listing Stripped Surface to Finished Subgrade Surface Area Cut (m') Fill (m') Balance(m') 67031m ² 26810 24510 2300(Cut) View Out fill contours shown are derived from the finished surface to existing surface minus 200mm thick of topsoil and 200mm deep timming for the road at bulk earthworks stage. 5000000000000000000000000000000000000	Existing Stripped Surface to Finished Subgrade Surface Area Cut (m ²) Fill (m ²) Balance(m ²) Notes: • Cut fill contours shown are derived from the finished surface to existing surface. • Sixiting stripped Curface assumes the existing surface minus 300mm thick of topsoil; finished subgrade surface assumes finished surface minus 200mm thick of topsoil and 200mm deep trimming for the road at bulk earthworks stage. • O Cut to Fill Legend - 35 - Existing Contours - 0 Zero Contour • O Zero Contour • Fill Contours & Area Fill Contours & Area • O Existing Contours & Area • O <t< td=""><td>- -</td><td></td><td></td><td></td><td></td><td></td><td></td></t<>	- -						
Area Cut (m') Fill (m) Balance(m) 67031m ² 26810 24510 2300(Cut) Listing Stripped Surface to Finished Subgrade Surface Area Cut (m') Fill (m) Balance(m) 67031m ² 26810 24510 2300(Cut) Votes: Cut full contours shown are derived from the finished surface to existing surface minus 200mm thick of topsoil and 200mm deep trimming for the road at bulk earthworks stage: Cut full Contours shown are derived from the finished surface assumes finished subgrade surface assumes finished subgrade surface minus 200mm thick of topsoil and 200mm theep trimming for the road at bulk earthworks stage: Out file to fill Legend -35 Existing Contours -0 Zero Contour -10 Cut Contours & Area -10 Cut Contours & Area -10 Extent of Earthworks	Existing Stripped Surface to Finished Subgrade Surface Area Cut (m ²) Fill (m ²) Balance(m ²) Notes: • Cut fill contours shown are derived from the finished surface to existing surface assumes the existing surface minus 300mm thick of topsoil; finished subgrade surface assumes finished surface minus 200mm thick of topsoil and 200mm deep training for the road at bulk earthworks stage. Image: Cut Contour Surface assumes the existing surface minus 200mm thick of topsoil and 200mm deep training for the road at bulk earthworks stage. Image: Cut Contour Surface assumes the existing Contours Surface field to the contour Surface minus 200mm thick of topsoil and 200mm deep training for the road at bulk earthworks stage. Image: Cut Contour Surface assumes the existing Contours Surface field to the contour	-						
Area Cut (m²) Fill (m²) Balance(m²) 67031m² 30250 T1250 9000(Cut) Existing Stripped Surface to Finished Subgrade Surface Area Cut (m²) Fill (m²) Balance(m²) 67031m² 26810 24510 2300(Cut) Xex Xex Votes: Cut fill contours shown are derived from the finished surface to existing surface assumes the existing surface assumes finished surface minus 200mm thick of topsoil and 200mm deep trimming for the road at bulk earthworks stage. Image: triangle for the road at bulk earthworks stage. Cut to Fill Legend 0 260 Cut Contours & Area 0 Cut Contours & Area Cut Contours & Area 0 Cut Contours & Area Cut Contours & Area 0 260 Extent of Earthworks	Existing Stripped Surface to Finished Subgrade Surface Area Cut (m ³) Fill (m ³) Balance(m ³) Notes: • Cut fill contours shown are derived from the finished surface to existing surface. Existing stripped surface assumes the existing surface assumes finished subgrade surface assumes finished subgrade surface assumes finished surface assumes the existing surface. • Existing stripped surface assumes the existing surface minus 300mm thick of topsoil, finished subgrade surface assumes finished surface minus 200mm thick of topsoil and 200mm deep trimming for the road at bulk earthworks stage. • Out to Fill Legend • 35 Existing Contours • 0 - Zero Contour • 1 - Cut contours & Area • 1 - Cut contours & Area • 1 - Existing Contours & Area	₽ 7E						
Area Cut (m) Fill (m) Balance(m) <u>Area</u> Cut (m) Fill (m) Balance(m) <u>67031m²</u> 26810 24510 2300(Cut) Vetes: • • • • • • • • • • • • • • • • • • • • • • • <	Existing Stripped Surface to Finished Subgrade Surface Area Cut (m ³) Fill (m ³) Balance(m ³) Notes: • Cut fill contours shown are derived from the finished surface to existing surface. Existing stripped surface assumes the existing surface minus 300mm thick of topsoil, finished subgrade surface assumes finished subfrace minus 200mm thick of topsoil and 200mm theep trimming for the road at bulk earthworks stage. Image: Cut to Fill Legend of the road at bulk earthworks stage. Image: Cut Contours & Area Image: Cut to fill Contours & Area Image: Cut Contours & Area Image: Cut to fill Contours & Area Image: Cut Contours & Area Image: Cut to fill Contours & Area Image: Cut Contours & Area Image: Cut to fill Contours & Area Image: Cut Contours & Area Image: Cut to fill Contours & Area Image: Cut Contours & Area Image: Cut to fill Contours & Area Image: Cut Contours & Area Image: Cut to fill Contours & Area Image: Cut Contours & Area Image: Cut to fill Cut to f	#						
Area Cut (corr Fill (corr Balance(m ²) Existing Stripped Surface to Finished Subgrade Surface Area Cut (m ²) Balance(m ²) Area Cut (m ²) Fill (m ²) Balance(m ²) Subgrade Surface to Finished Subgrade Surface Area Cut (m ²) Fill (m ²) Balance(m ²) Subgrade Surface to Finished Subgrade Surface to Existing surface minus 300mt thick of topsoil; finished subgrade surface assumes finished surface minus 200mm thick of topsoil and 200mm deep timining for the road at bulk earthworks stage. Cut to Fill Legend	Existing Stripped Surface to Finished Subgrade Surface Area Cut (m ³) Fill (m ³) Balance(m ³) Strong 26810 24510 2300(Cut) Notes: • • • • • Cut fill contours shown are derived from the finished surface to existing surface. • • • Existing stripped surface assumes the existing surface minus 300mm thick of topsoil, finished subgrade surface assumes finished surface to existing contours the road at bulk earthworks stage. • • Cut to Fill Legend • • • • Cut contours & Area • • • • Cut contours & Area • • • • • Cut contours & Area • • • • • • Cut to Fill Legend • • • • • • • • • • • </td <td>×2 ~</td> <td></td> <td></td> <td></td> <td></td> <td></td> <td></td>	×2 ~						
Area Cut (m ²) Fill (m ²) Balance(m ²) Existing Stripped Surface to Finished Subgrade Surface Area Cut (m ²) Fill (m ²) Balance(m ²) Area Cut (m ²) Fill (m ²) Balance(m ²) Surface to existing surface to existing surface to existing surface. Cut fill contours shown are derived from the finished surface to existing surface. Existing stripped surface assumes the existing surface assumes finished surface minus 300mm thick of topsoil and 200mm deep trimming for the road at bulk earthworks stage. Votes: Cut to Fill Legend -35 Existing Contours -0 Zero Contour -35 Existing Contours & Area -0 Zero Contour -11 - Cut Contours & Area -0 Zero Contour -11 - Cut Contours & Area -0 Zero Contour -11 - Cut Contours & Area -0 Zero Contour -11 - Cut Contours & Area -0 Extent of Earthworks -11 - Cut Contours & Area -0 Extent of Earthworks -11 - Cut Contours & Area -0 Extent of Earthworks -11 - Cut Contours & Area -0 Extent of Earthworks -11 - Cut Contours & Area -0 Extent of Earthworks -11 - Cut Contours & Area	Existing Stripped Surface to Finished Subgrade Surface Area Cut (m ³) Fill (m ³) Balance(m ³) 67031m ² 26810 24510 2300(Cut) Notes: • • • • • Cut fill contours shown are derived from the finished surface to existing surface. • • • Existing stripped surface assumes the existing surface minus 300mm thick of topsoil, finished subgrade surface assumes finished surface minus 200mm thick of topsoil and 200mm deep trimming for the road at bulk earthworks stage. • Cut to Fill Legend • • • • Cut contours & Area • • • • • • • • • • • • • • • • • • • • • • • • • • • • • • • • • • • • • • • •							
Area Cut (m ²) Fill (m ²) Balance(m ²) Area Cut (m ²) Fill (m ²) Balance(m ²) Area Cut (m ²) Fill (m ²) Balance(m ²) 67031m ² 26810 24510 2300(Cut) Notes: Cut fill contours shown are derived from the finished surface to existing surface. Existing stripped surface assumes the existing surface minus 300mm thick of topsoil; finished subgrade surface assumes finished surface minus 200mm thick of topsoil and 200mm deep trimming for the road at bulk earthworks stage. View Cut to Fill Legend	Existing Stripped Surface to Finished Subgrade Surface Area Cut (m ³) Fill (m ³) Balance(m ³) 67031m ² 26810 24510 2300(Cut) Notes: • Cut fill contours shown are derived from the finished surface to existing surface. • Existing stripped surface assumes the existing surface minus 300mm thick of topsoil; finished subgrade surface assumes finished surface minus 200mm thick of topsoil and 200mm deep trimming for the road at bulk earthworks stage. • Out to Fill Legend 35 Existing Contours • Out contours & Area 35							
Area Cut (m ³) Fill (m ³) Balance(m ³) <u>Area</u> Cut (m ³) Fill (m ³) Balance(m ³) <u>Area</u> Cut (m ³) Fill (m ³) Balance(m ³) 67031m ² 26810 24510 2300(Cut) Notes: Cut (m ³) Fill (m ³) Balance(m ³) Cut (m ³) Fill (m ³) Balance(m ³) Solution: Area Cut (m ³) Fill (m ³) Balance(m ³) 67031m ² 26810 24510 2300(Cut) Notes: Cut (m ³) Fill (m ³) Balance(m ³) Cut (m ³) Fill (m ³) Balance(m ³) Solution: Solution: Cut (m ³) Fill (m ³) Balance(m ³) Cut (m ³) Fill (m ³) Balance(m ³) Solution: Cut (fill Legend Fill Contours & Area Fill Contours & Area Cut (fill Contours & Area Cut	Existing Stripped Surface to Finished Subgrade Surface Area Cut (m ³) Fill (m ³) Balance(m ³) 67031m ² 26810 24510 2300(Cut) Notes: • Cut fill contours shown are derived from the finished surface to existing surface assumes the existing surface minus 300mm thick of topsoil; finished subgrade surface assumes finished surface minus 200mm thick of topsoil and 200mm deep trimming for the road at bulk earthworks stage. Image: Cut Contour for the road at bulk earthworks stage. Image: Cut Contour for Cut to Fill Legend for Cut Contours & Area for Cut	4						
Area Cut (m ³) Fill (m ³) Balance(m ³) Existing Stripped Surface to Finished Subgrade Surface Area Cut (m ³) Fill (m ³) Balance(m ³) 67031m ² 26810 24510 2300(Cut) Notes: Cut fill contours shown are derived from the finished surface to existing surface. Existing stripped surface assumes the existing surface minus 300mm thick of topsoil; finished subgrade surface assumes finished surface minus 200mm thick of topsoil and 200mm deep trimming for the road at bulk earthworks stage. Image: Cut contains a stripped of the contains and the finished surface to existing Contours and the cut contours & Area Cut Contours & Area Image: Cut contains & Area Image: Cut contains & Area Image: Cut contains & Area Image: Cut contains & Area Image: Cut contains & Area Image: Cut contains & Area Image: Cut contains & Area Image: Cut contains & Area Image: Cut contains & Area Image: Cut contains & Area Image: Cut contains & Area Image: Cut contains & Area Image: Cut contains & Area Image: Cut contains & Area Image: Cut contains & Area Image: Cut contains & Area Image: Cut contains & Area Image: Cut contains & Area Image: Cut contains & Area Image: Cut cont	Existing Stripped Surface to Finished Subgrade Surface Area Cut (m ³) Fill (m ³) Balance(m ³) 67031m ² 26810 24510 2300(Cut) Notes: Cut fill contours shown are derived from the finished surface to existing surface. Existing stripped surface assumes the existing surface minus 300mm thick of topsoil; finished subgrade surface assumes finished surface minus 200mm thick of topsoil and 200mm deep trimming for the road at bulk earthworks stage. Image: Cut to Fill Legend (Cut to Fill Legend (Cut contours & Area) Cut Contours & Area Image: Cut contour for the fill (Cut contours & Area) Fill Contours & Area Image: Cut contour for the contour for the fill contour for the contour for fill contour for	f y						
Area Cut (m²) Fill (m²) Balance(m²) <u>Existing Stripped Surface to Finished Subgrade Surface</u> <u>Area</u> Cut (m²) Fill (m²) Balance(m²) <u>67031m²</u> 26810 24510 2300(Cut) <u>Votes:</u> • Cut fill contours shown are derived from the finished surface to existing surface. • Existing stripped surface assumes the existing surface minus 300mm thick of topsoil; finished subgrade surface assumes finished surface minus 200mm thick of topsoil and 200mm deep trimming for the road at bulk earthworks stage. Out to Fill Legend	Existing Stripped Surface to Finished Subgrade Surface Area Cut (m³) Fill (m³) Balance(m³) 67031m² 26810 24510 2300(Cut) Notes: Cut fill contours shown are derived from the finished surface to existing surface. Existing stripped surface assumes the existing surface minus 300mm thick of topsoil and 200mm deep trimming for the road at bulk earthworks stage. Image: Cut to Fill Legend Image: Cut Contours & Area Image: Cut Contours & Area Image: Cut Contours & Area Image: Cut Cut Contours & Area Image: Cut Cut Contours & Area Image: Cut	/ (
Area Cut (m ³) Fill (m ³) Balance(m ³) Existing Stripped Surface to Finished Subgrade Surface Area Cut (m ³) Fill (m ³) Balance(m ³) §7031m ² 26810 24510 2300(Cut) Notes: Cut fill contours shown are derived from the finished surface to existing surface. Existing stripped surface assumes the existing surface minus 300mm thick of topsoil; finished subgrade surface assumes finished surface incurs 200mm thick of topsoil and 200mm deep trimming for the road at bulk earthworks stage. Votes: Cut to Fill Legend ————————————————————————————————————	Existing Stripped Surface to Finished Subgrade Surface Area Cut (m³) Fill (m³) Balance(m³) 67031m² 26810 24510 2300(Cut) Notes: Cut fill contours shown are derived from the finished surface to existing surface. Existing stripped surface assumes the existing surface minus 300mm thick of topsoil, finished subgrade surface assumes finished surface minus 200mm thick of topsoil and 200mm deep trimming for the road at bulk earthworks stage. Image: Cut to Fill Legend (main the finished surface to existing Contours (main the finished surface for the road at bulk earthworks stage) Image: Cut contour the finished surface to the road at bulk earthworks stage. Image: Cut contour the finished surface for the road at bulk earthworks stage. Image: Cut contour the finished surface for the road at bulk earthworks stage. Image: Cut contour the finished surface for the road at bulk earthworks stage. Image: Cut contour the finished surface for the road at bulk earthworks stage. Image: Cut contour the finished surface for the road at bulk earthworks stage. Image: Cut contour the finished surface for the road at bulk earthworks stage. Image: Cut contour the finished surface for the road at bulk earthworks Image: Cut contour the finished surface for the road at bulk earthworks Image: Cut contour the finished surface for the road at bulk earthworks <tr< td=""><td></td><td></td><td></td><td></td><td></td><td></td><td></td></tr<>							
Area Cut (m³) Fill (m³) Balance(m³) 67031m² 30250 21250 9000(Cut) Existing Stripped Surface to Finished Subgrade Surface Area Cut (m³) Fill (m³) Balance(m³) 67031m² 26810 24510 2300(Cut) Notes: Cut fill contours shown are derived from the finished surface to existing surface. Existing stripped surface assumes the existing surface minus 300mm thick of topsoil; finished subgrade surface assumes finished surface minus 200mm thick of topsoil and 200mm deep trimming for the road at bulk earthworks stage. Votes: Cut to Fill Legend 35 Existing Contours 0 Zero Contour 35 Fill Contours & Area 35 Fill Contours & Area	Existing Stripped Surface to Finished Subgrade Surface Area Cut (m³) Fill (m³) Balance(m³) 67031m² 26810 24510 2300(Cut) Notes: • Cut fill contours shown are derived from the finished surface to existing surface. • Existing stripped surface assumes the existing surface minus 300mm thick of topsoil; finished subgrade surface assumes finished surface minus 200mm thick of topsoil and 200mm deep trimming for the road at bulk earthworks stage. • Out to Fill Legend	/						
Area Cut (m³) Fill (m³) Balance(m³) Existing Stripped Surface to Finished Subgrade Surface Area Cut (m³) Fill (m³) Balance(m³) 67031m² 26810 24510 2300(Cut) Notes: Cut fill contours shown are derived from the finished surface to existing surface. Existing stripped surface assumes the existing surface minus 300mm thick of topsoil; finished subgrade surface assumes finished surface minus 200mm thick of topsoil and 200mm deep trimming for the road at bulk earthworks stage. Image: Cut to Fill Legend 35 Existing Contours Image: Cut contour Image: Cut contours & Area Fill Contours & Area Image: Cut contours & Area Existing Contours & Area Image: Cut contours & Area Existent of Earthworks	Existing Stripped Surface to Finished Subgrade Surface Area Cut (m³) Fill (m³) Balance(m³) 67031m² 26810 24510 2300(Cut) Notes: • Cut fill contours shown are derived from the finished surface to existing surface. • Existing stripped surface assumes the existing surface minus 300mm thick of topsoil; finished subgrade surface assumes finished surface minus 200mm thick of topsoil and 200mm deep trimming for the road at bulk earthworks stage. • O Cut to Fill Legend • O Zero Contour • O Zero Contour • O Zero Contours & Area • O Cut Contours & Area • O Existing Contours & Area • O Cut Contours & Area • O Existing Contours & Area • O Existing Contours & Area • O Existent of Earthworks							
Area Cut (m³) Fill (m³) Balance(m³) 67031m² 30250 21250 9000(Cut) Existing Stripped Surface to Finished Subgrade Surface Area Cut (m³) Fill (m³) Balance(m³) 67031m² 26810 24510 2300(Cut) Notes: Cut fill contours shown are derived from the finished surface to existing surface. Existing stripped surface assumes the existing surface minus 300mm thick of topsoil; finished subgrade surface assumes finished surface minus 200mm thick of topsoil and 200mm deep trimming for the road at bulk earthworks stage. Image: Cut to Fill Legend 35 Existing Contours Image: Cut contours Image: Cut contours & Area Image: Cut contours & Area Image: Cut contours Fill Contours & Area Image: Cut contours & Area	Existing Stripped Surface to Finished Subgrade Surface Area Cut (m³) Fill (m³) Balance(m³) 67031m² 26810 24510 2300(Cut) Notes: • Cut fill contours shown are derived from the finished surface to existing surface. • Existing stripped surface assumes the existing surface minus 300mm thick of topsoil; finished subgrade surface assumes finished surface minus 200mm thick of topsoil; and 200mm deep trimming for the road at bulk earthworks stage. • O Cut to Fill Legend • O Zero Contour • O Zero Contour • O Zero Contour • O Zero Contour • O Cut Contours & Area • O Existing Contours & Area • O Existing Contours & Area • O Existent of Earthworks	*	'E					
Area Cut (m ³) Fill (m ³) Balance(m ³) 67031m ² 30250 21250 9000(Cut) Existing Stripped Surface to Finished Subgrade Surface Area Cut (m ³) Fill (m ³) Balance(m ³) 67031m ² 26810 24510 2300(Cut) Notes: Cut fill contours shown are derived from the finished surface to existing surface. Existing stripped surface assumes the existing surface minus 300mm thick of topsoil; finished subgrade surface assumes finished surface minus 200mm thick of topsoil and 200mm deep trimming for the road at bulk earthworks stage. O Zero Contour 0 Existing Contours & Area 0 Zero Contour 0 Existing Contours & Area	Existing Stripped Surface to Finished Subgrade Surface Area Cut (m³) Fill (m³) Balance(m³) 67031m² 26810 24510 2300(Cut) Notes: Cut fill contours shown are derived from the finished surface to existing surface. Existing stripped surface assumes the existing surface minus 300mm thick of topsoil; finished subgrade surface assumes finished surface minus 200mm thick of topsoil and 200mm deep trimming for the road at bulk earthworks stage. Image: Cut to Fill Legend	∯ کـر						
Area Cut (m³) Fill (m³) Balance(m³) 67031m² 30250 21250 9000(Cut) Existing Stripped Surface to Finished Subgrade Surface Area Cut (m³) Fill (m³) Balance(m³) 67031m² 26810 24510 2300(Cut) Notes: Cut fill contours shown are derived from the finished surface to existing surface. Existing stripped surface assumes the existing surface minus 300mm thick of topsoil; finished subgrade surface assumes finished surface minus 200mm thick of topsoil and 200mm deep trimming for the road at bulk earthworks stage. Cut to Fill Legend 35 Existing Contours 0 Zero Contour 35 Existing Contours & Area 0 Zero Contour Existing Contours & Area	Existing Stripped Surface to Finished Subgrade Surface Area Cut (m³) Fill (m³) Balance(m³) 67031m² 26810 24510 2300(Cut) Notes: Cut fill contours shown are derived from the finished surface to existing surface. Existing stripped surface assumes the existing surface minus 300mm thick of topsoil; finished subgrade surface assumes finished surface minus 200mm thick of topsoil and 200mm deep trimming for the road at bulk earthworks stage. Image: Cut to Fill Legend of the road at bulk earthworks stage. Image: Cut Contours & Area of the road of the road at provide the road of the road of the road at provide t		r					
Area Cut (m ³) Fill (m ³) Balance(m ³) 67031m ² 30250 21250 9000(Cut) Existing Stripped Surface to Finished Subgrade Surface Area Cut (m ³) Fill (m ³) Balance(m ³) 67031m ² 26810 24510 2300(Cut) Notes: Cut fill contours shown are derived from the finished surface to existing surface. Existing stripped surface assumes the existing surface minus 300mm thick of topsoil; finished subgrade surface assumes finished surface minus 200mm thick of topsoil and 200mm deep trimming for the road at bulk earthworks stage. $\begin{pmatrix} Cut to Fill Legend \\35 Existing Contours \\35 Existing$	Existing Stripped Surface to Finished Subgrade Surface Area Cut (m³) Fill (m³) Balance(m³) 67031m² 26810 24510 2300(Cut) Notes: Cut fill contours shown are derived from the finished surface to existing surface. Existing stripped surface assumes the existing surface minus 300mm thick of topsoil; finished subgrade surface assumes finished surface minus 200mm thick of topsoil and 200mm deep trimming for the road at bulk earthworks stage. Image: Cut to Fill Legend 0. 0. Zero Contour Image: Cut Contours & Area 0. Sero Contour & Area					Extent of	∟arthw	/orks
AreaCut (m³)Fill (m³)Balance(m³)67031m²30250212509000(Cut)Existing Stripped Surface to Finished Subgrade Surface AreaAreaCut (m³)Fill (m³)Balance(m³)67031m²26810245102300(Cut)Notes:Cut fill contours shown are derived from the finished surface to existing surface.Existing stripped surface assumes the existing surface minus 300mm thick of topsoil; finished subgrade surface assumes finished surface minus 200mm thick of topsoil and 200mm deep trimming for the road at bulk earthworks stage.OCut to Fill Legend 35Existing ContoursOZero ContourImage: Cut Contours & AreaFill Contours & Area	Existing Stripped Surface to Finished Subgrade Surface Area Cut (m³) Fill (m³) Balance(m³) 67031m² 26810 24510 2300(Cut) Notes: Cut fill contours shown are derived from the finished surface to existing surface. Existing stripped surface assumes the existing surface minus 300mm thick of topsoil; finished subgrade surface assumes finished surface minus 200mm thick of topsoil and 200mm deep trimming for the road at bulk earthworks stage. Image: Cut to Fill Legend35 Existing Contours Image: Cut Contours & Area Image: Cut Contours & Area	×08		· · · · · · · · ·	J			
Area Cut (m³) Fill (m³) Balance(m³) 67031m² 30250 21250 9000(Cut) Existing Stripped Surface to Finished Subgrade Surface Area Cut (m³) Fill (m³) Balance(m³) 67031m² 26810 24510 2300(Cut) Notes: Cut fill contours shown are derived from the finished surface to existing surface. Existing stripped surface assumes the existing surface minus 300mm thick of topsoil; finished subgrade surface assumes finished surface minus 200mm thick of topsoil and 200mm deep trimming for the road at bulk earthworks stage. Cut to Fill Legend 35 Existing Contours 0 Zero Contour 1 Cut Contours & Area	Existing Stripped Surface to Finished Subgrade Surface Area Cut (m³) Fill (m³) Balance(m³) 67031m² 26810 24510 2300(Cut) Notes: Cut fill contours shown are derived from the finished surface to existing surface. Existing stripped surface assumes the existing surface minus 300mm thick of topsoil; finished subgrade surface assumes finished surface minus 200mm thick of topsoil and 200mm deep trimming for the road at bulk earthworks stage. <i>O O Cut to Fill Legend O Cut Contours & Area D Cut Contours & Area D Cut Contours & Area Cut Contours & C</i>		30		1	Fill Conto	urs & A	Area
Area Cut (m³) Fill (m³) Balance(m³) 67031m² 30250 21250 9000(Cut) Existing Stripped Surface to Finished Subgrade Surface Area Cut (m³) Fill (m³) Balance(m³) 67031m² 26810 24510 2300(Cut) Notes: Cut fill contours shown are derived from the finished surface to existing surface. Existing stripped surface assumes the existing surface minus 300mm thick of topsoil; finished subgrade surface assumes finished surface minus 200mm thick of topsoil and 200mm deep trimming for the road at bulk earthworks stage. Cut to Fill Legend 35 Existing Contours 0 Zero Contour 0 Zero Contour	Existing Stripped Surface to Finished Subgrade Surface Area Cut (m³) Fill (m³) Balance(m³) 67031m² 26810 24510 2300(Cut) Notes: Cut fill contours shown are derived from the finished surface to existing surface. Existing stripped surface assumes the existing surface minus 300mm thick of topsoil; finished subgrade surface assumes finished surface minus 200mm thick of topsoil and 200mm deep trimming for the road at bulk earthworks stage. Cut to Fill Legend 35 Existing Contours 0 Zero Contour 1 Cut Contours & Area		-1.₩/ 1.₩					
Area Cut (m³) Fill (m³) Balance(m³) 67031m² 30250 21250 9000(Cut) Existing Stripped Surface to Finished Subgrade Surface Area Cut (m³) Fill (m³) Balance(m³) 67031m² 26810 24510 2300(Cut) Notes: Cut fill contours shown are derived from the finished surface to existing surface. Existing stripped surface assumes the existing surface minus 300mm thick of topsoil; finished subgrade surface assumes finished surface minus 200mm thick of topsoil and 200mm deep trimming for the road at bulk earthworks stage. Cut to Fill Legend 35 Existing Contours 0 Zero Contour	Existing Stripped Surface to Finished Subgrade Surface Area Cut (m³) Fill (m³) Balance(m³) 67031m² 26810 24510 2300(Cut) Notes: Cut fill contours shown are derived from the finished surface to existing surface. Existing stripped surface assumes the existing surface minus 300mm thick of topsoil; finished subgrade surface assumes finished surface minus 200mm thick of topsoil and 200mm deep trimming for the road at bulk earthworks stage. Image: Cut to Fill Legend				-1	Cut Cont	ours &	Area
Area Cut (m³) Fill (m³) Balance(m³) 67031m² 30250 21250 9000(Cut) Existing Stripped Surface to Finished Subgrade Surface Area Cut (m³) Fill (m³) Balance(m³) 67031m² 26810 24510 2300(Cut) Notes: Cut fill contours shown are derived from the finished surface to existing surface. Existing stripped surface assumes the existing surface minus 300mm thick of topsoil; finished subgrade surface assumes finished surface minus 200mm thick of topsoil and 200mm deep trimming for the road at bulk earthworks stage. X Cut to Fill Legend 35 Existing Contours	Existing Stripped Surface to Finished Subgrade Surface Area Cut (m³) Fill (m³) Balance(m³) 67031m² 26810 24510 2300(Cut) Notes: Cut fill contours shown are derived from the finished surface to existing surface. Existing stripped surface assumes the existing surface minus 300mm thick of topsoil; finished subgrade surface assumes finished surface minus 200mm thick of topsoil and 200mm deep trimming for the road at bulk earthworks stage. Cut to Fill Legend 35 Existing Contours		6/1		U ———	Zero Con	tour	
Area Cut (m³) Fill (m³) Balance(m³) 67031m² 30250 21250 9000(Cut) Existing Stripped Surface to Finished Subgrade Surface Area Cut (m³) Fill (m³) Balance(m³) 67031m² 26810 24510 2300(Cut) Notes: Cut fill contours shown are derived from the finished surface to existing surface. Existing stripped surface assumes the existing surface minus 300mm thick of topsoil; finished subgrade surface assumes finished surface minus 200mm thick of topsoil and 200mm deep trimming for the road at bulk earthworks stage. Xi Cut to Fill Legend	Existing Stripped Surface to Finished Subgrade Surface Area Cut (m³) Fill (m³) Balance(m³) 67031m² 26810 24510 2300(Cut) Notes: Cut fill contours shown are derived from the finished surface to existing surface. Existing stripped surface assumes the existing surface minus 300mm thick of topsoil; finished subgrade surface assumes finished surface minus 200mm thick of topsoil and 200mm deep trimming for the road at bulk earthworks stage. Cut to Fill Legend Cut to Fill Legend	10.18	<u>}</u> }∦/	3	55 — — —	Existing (contou	rs
Area Cut (m³) Fill (m³) Balance(m³) 67031m² 30250 21250 9000(Cut) Existing Stripped Surface to Finished Subgrade Surface Area Cut (m³) Fill (m³) Balance(m³) 67031m² 26810 24510 2300(Cut) N Notes: Cut fill contours shown are derived from the finished surface to existing surface. Existing stripped surface assumes the existing surface minus 300mm thick of topsoil; finished subgrade surface assumes finished surface minus 200mm thick of topsoil and 200mm deep trimming for the road at bulk earthworks stage.	Existing Stripped Surface to Finished Subgrade Surface Area Cut (m³) Fill (m³) Balance(m³) 67031m² 26810 24510 2300(Cut) Notes: . Cut fill contours shown are derived from the finished surface to existing surface. . Existing stripped surface assumes the existing surface minus 300mm thick of topsoil; finished subgrade surface assumes finished surface minus 200mm thick of topsoil and 200mm deep trimming for the road at bulk earthworks stage.		the second			III Legen	<u>u</u>	
Area Cut (m³) Fill (m³) Balance(m³) 67031m² 30250 21250 9000(Cut) Existing Stripped Surface to Finished Subgrade Surface Area Cut (m³) Fill (m³) Balance(m³) 67031m² 26810 24510 2300(Cut) Notes: Cut fill contours shown are derived from the finished surface to existing surface. Existing stripped surface assumes the existing surface minus 300mm thick of topsoil; finished subgrade surface assumes finished surface minus 200mm thick of topsoil and 200mm deep trimming for the road at bulk earthworks stage. & X	Existing Stripped Surface to Finished Subgrade Surface Area Cut (m³) Fill (m³) Balance(m³) 67031m² 26810 24510 2300(Cut) Notes: Cut fill contours shown are derived from the finished surface to existing surface. Existing stripped surface assumes the existing surface minus 300mm thick of topsoil; finished subgrade surface assumes finished surface minus 200mm thick of topsoil and 200mm deep trimming for the road at bulk earthworks stage. & & & &	and a second	~				4	
Area Cut (m³) Fill (m³) Balance(m³) 67031m² 30250 21250 9000(Cut) Existing Stripped Surface to Finished Subgrade Surface Area Cut (m³) Fill (m³) Balance(m³) 67031m² 26810 24510 2300(Cut) Notes: • Cut fill contours shown are derived from the finished surface to existing surface. Existing stripped surface assumes the existing surface minus 300mm thick of topsoil; finished subgrade surface assumes finished surface minus 200mm thick of topsoil and 200mm deep trimming for the road at bulk earthworks stage.	Existing Stripped Surface to Finished Subgrade Surface Area Cut (m³) Fill (m³) Balance(m³) 67031m² 26810 24510 2300(Cut) Notes: Cut fill contours shown are derived from the finished surface to existing surface. Existing stripped surface assumes the existing surface minus 300mm thick of topsoil; finished subgrade surface assumes finished surface minus 200mm thick of topsoil and 200mm deep trimming for the road at bulk earthworks stage.	$\tilde{(}$	29 -					
Area Cut (m³) Fill (m³) Balance(m³) 67031m² 30250 21250 9000(Cut) Existing Stripped Surface to Finished Subgrade Surface Area Cut (m³) Fill (m³) Balance(m³) 67031m² 26810 24510 2300(Cut) Note: Cut fill contours shown are derived from the finished surface to existing surface. Cut fill contours shown are derived from the finished surface to existing surface. Existing stripped surface assumes the existing surface minus 300mm thick of topsoil; finished subgrade surface assumes finished surface minus 200mm thick of topsoil and 200mm deep trimming for the road at bulk earthworks stage.	Existing Stripped Surface to Finished Subgrade Surface Area Cut (m³) Fill (m³) Balance(m³) 67031m² 26810 24510 2300(Cut) Notes: . Cut fill contours shown are derived from the finished surface to existing surface. . Existing stripped surface assumes the existing surface minus 300mm thick of topsoil; finished subgrade surface assumes finished surface minus 200mm thick of topsoil and 200mm deep trimming for the road at bulk earthworks stage.	N			- J			
Area Cut (m³) Fill (m³) Balance(m³) 67031m² 30250 21250 9000(Cut) Existing Stripped Surface to Finished Subgrade Surface Area Cut (m³) Fill (m³) Balance(m³) 67031m² 26810 24510 2300(Cut) Notes: Cut fill contours shown are derived from the finished surface to existing surface. Existing stripped surface assumes the existing surface minus 300mm thick of topsoil; finished subgrade surface assumes	Existing Stripped Surface to Finished Subgrade Surface Area Cut (m³) Fill (m³) Balance(m³) 67031m² 26810 24510 2300(Cut) Notes: . . Cut fill contours shown are derived from the finished surface to existing surface. . Existing stripped surface assumes the existing surface minus 300mm thick of topsoil; finished subgrade surface assumes	tinished surfa trimmina for	ace minus 20 the road at bi	umm thick o ulk earthwoi	or topsoil and ks stage.	200mm dee	эp	
Area Cut (m³) Fill (m³) Balance(m³) 67031m² 30250 21250 9000(Cut) Existing Stripped Surface to Finished Subgrade Surface Area Cut (m³) Fill (m³) 67031m² 26810 24510 2300(Cut) Votes: Cut fill contours shown are derived from the finished surface to existing surface. Existing stripped surface assumes the existing surface minus	Existing Stripped Surface to Finished Subgrade Surface Area Cut (m³) Fill (m³) Balance(m³) 67031m² 26810 24510 2300(Cut) Notes: Cut fill contours shown are derived from the finished surface to existing surface. Existing stripped surface assumes the existing surface minus	300mm thick	of topsoil; fi	nished subg	rade surface	assumes		
Area Cut (m ³) Fill (m ³) Balance(m ³) 67031m ² 30250 21250 9000(Cut) Existing Stripped Surface to Finished Subgrade Surface Area Cut (m ³) Fill (m ³) Balance(m ³) 67031m ² 26810 24510 2300(Cut) Notes: Cut fill contours shown are derived from the finished surface to	Existing Stripped Surface to Finished Subgrade Surface Area Cut (m³) Fill (m³) Balance(m³) 67031m² 26810 24510 2300(Cut) Notes: . Cut fill contours shown are derived from the finished surface to	existing surfa 2. Existing strip	ace. ped surface a	assumes the	e existina sur	face minus		
Area Cut (m ³) Fill (m ³) Balance(m ³) 67031m ² 30250 21250 9000(Cut) Existing Stripped Surface to Finished Subgrade Surface Area Cut (m ³) Fill (m ³) Balance(m ³) 67031m ² 26810 24510 2300(Cut) Notes:	Existing Stripped Surface to Finished Subgrade Surface Area Cut (m ³) Fill (m ³) Balance(m ³) 67031m ² 26810 24510 2300(Cut) Notes:	. Cut fill conto	urs shown are	e derived fro	om the finishe	ed surface to)	
Area Cut (m³) Fill (m³) Balance(m³) 67031m² 30250 21250 9000(Cut) Existing Stripped Surface to Finished Subgrade Surface Area Cut (m³) Fill (m³) Balance(m³) 67031m² 26810 24510	Existing Stripped Surface to Finished Subgrade Surface Area Cut (m ³) Fill (m ³) Balance(m ³) 67031m ² 26810 24510 2300(Cut)	Notes:						
Area Cut (m ³) Fill (m ³) Balance(m ³) 67031m ² 30250 21250 9000(Cut) Existing Stripped Surface to Finished Subgrade Surface Area Cut (m ³) Fill (m ³) Balance(m ³) 67034m ² 202040 202040 202040(cut)	Existing Stripped Surface to Finished Subgrade Surface Area Cut (m ³) Fill (m ³) Balance(m ³)	6703 Im	- 20010	24510	2300(0	Jut)		
Area Cut (m ³) Fill (m ³) Balance(m ³) 67031m ² 30250 21250 9000(Cut) Existing Stripped Surface to Finished Subgrade Surface	Existing Stripped Surface to Finished Subgrade Surface		Cut (m ³)	Fill (m ³)) Balance	e(m ³)		
Area Cut (m ³) Fill (m ³) Balance(m ³) 67031m ² 30250 21250 9000(Cut)		Area		e to Finishe	d Subarade 9	Surface	ľ	N
Area Cut (m ³) Fill (m ³) Ralanco(m ³)	67031m ² 30250 21250 9000(Cut)	Existing Str Area	inned Surface				~	1
EXISTING DUDACE TO FIDISOPO SUDACE	Area Cut (m ³) Fill (m ³) Balance(m ³)	67031m Existing Str Area	n ² 30250	21250	9000(Ci	ut)		

Appendix H: Geotechnical Works Specification



23 May 2022

Document Ref: AKL2019-0040AF Rev.1

Land Development Geotechnical Works Specification For: Trig & Brigham Creek Road

1 INTRODUCTION AND SCOPE

This specification covers the geotechnical remediation works and associated earthworks outlined in the CMW Investigation Report (GIR), referenced AKL2019-0040AM Rev.0. It supplements the information provided on the design drawings and GIR. It provides detail on the required specification for:

- Site clearance and preparation including topsoil stripping and stockpiling;
- Subsoil drainage installation;
- Cut to fill earthworks operations;
- Fill materials and testing requirements;
- Earthworks finishing and respread of topsoil; and,
- As-built records.

Excluded from the scope are geotextile reinforced slopes with a face steeper than 30 degrees or retaining structures covered by a building consent. Such works will be carried out in accordance with an independent structure specific specification.

Unless varied onsite by the Geotechnical Engineer, the following specification requirements must be met in order for CMW Geosciences (CMW) to provide a Geotechnical Completion Report for the works.

2 RELEVANT DOCUMENTS

2.1 Standards, Guidelines and Consents

The works shall comply with the relevant sections of the following standards, guidelines and consents:

- 1. Health and Safety at Work Act 2015 and Regulations 2016;
- 2. All Project Resource Consent Conditions and Engineering Works Approvals;
- 3. The applicable Council Infrastructure Design Standard;
- 4. The Auckland Council, Erosion and Sediment Control Guidelines Guidance document 2016/005;
- 5. NZS 4431:1989 Code of Practice for Earth Fill for Residential Development;
- 6. NZS 4402: 1986 Methods of Testing Soils for Civil Engineering Purposes; and,

7. NZS 4404: 2010 Code of Practice for Urban Land Subdivision.

2.2 Geotechnical Investigation and Design Report

Details of the geotechnical investigation, soil and rock conditions encountered, and the design of the geotechnical remedial works are contained in the CMW report AKL2019-0040AM Rev.0. The contractor should be aware of the contents and recommendations contained in that report.

The works shall comply with the recommendations contained in that report.

2.3 Construction Drawings

The works shall comply with the Neil Construction Limited plans referenced Brigham Creek Whenuapai, drawings 447-01-BE-200, 447-01-BE-201, 447-01-GE-200 and 447-01-GE-300.

2.4 Conflicting Information

Where there is any conflict or discrepancy in the requirements of this specification and the documents listed above the matter shall be referred to the Geotechnical Engineer (CMW) for clarification.

3 GEOTECHNICAL OBSERVATION REQUIREMENTS

The following items form hold points in the construction works that require observation, testing and approval by the Geotechnical Engineer (CMW):

- 1. Foundations for filling once topsoil and unsuitable materials, or existing uncertified fills, have been stripped prior to fill placement;
- 2. Shear key excavations and undercuts to confirm depth and extents prior to backfilling;
- 3. Subsoil drain excavations prior to placement of aggregate;
- 4. Any imported soil fill materials prior to placement on site;
- 5. Drainage aggregate quality prior to placement;
- 6. Geotextile layers once in place and prior to backfilling;
- 7. Filling placed at regular intervals to comply with the fill test frequency requirements below;
- 8. Compaction of backfilling in critical service trenches;
- 9. Flushing of the subsoil drainage system at the completion of earthworks;

10. Any unforeseen ground conditions that may impact on the construction works or future land use; and,

11.Installation of any settlement monitoring plates or points, application of pre-load and approval prior to its removal.

It is the contractor's responsibility to ensure that the Geotechnical Engineer is given reasonable notice and opportunity to observe the above works and that the works do not proceed until approval has been gained from the Geotechnical Engineer.

24 hours is considered reasonable notice.

4 CONSTRUCTION SPECIFICATION

4.1 Site Preparation

The Contractor shall remove all vegetation from the site of the earthworks except for trees indicated for preservation either by marking on the site or noted on the drawings, and clear the remainder of the site.

Clearing shall mean the felling of all trees, except those indicated, removal of all growth other than grass and weeds, extraction of tree stumps, demolition of fences and other minor items remaining in the way of site stripping, and the complete disposal of all items. Stumping shall mean the removal of all roots greater than 25mm in diameter.

Cleared areas shall be stripped to remove all turf and organic topsoil to depths designated by the Engineer ahead of or during the stripping operations. Stripping shall also cover picking up any old topsoil stockpiles and any buried topsoil detected during the course of the works. The depth shall be sufficient to remove all materials considered unsuitable as fill or unsuitable to remain beneath fill but will not necessarily extend to the full limit of organic penetration.

4.2 Erosion and Sediment Control

The works shall be carried out in accordance with the project Erosion and Sediment Control Management Plan and associated drawings.

The contractor shall ensure good control of surface water runoff at all times by shaping of the surface in cut and fill areas to prevent ponding during rainfall events.

The location of temporary Sediment Retention Ponds (SRP) on sloping ground shall be decided upon with input from the Geotechnical Engineer. Where comment of SRP stability is sought by Council then all fill materials used to form batters, must be placed as engineered fill and tested accordingly unless advised otherwise by the Geotechnical Engineer.

When decommissioning temporary sediment ponds, all water softened material in the bases and sides of the ponds shall be removed and undercut to the satisfaction of the Geotechnical Engineer. Backfilling of temporary ponds shall be to the compaction standard for general filling unless otherwise specified.

4.3 Stockpiles

Topsoil stockpiles can add significant driving force for slope instability when placed at or near the crest of a slope. The location of all temporary stockpiles must be approved by the Geotechnical Engineer prior to placement. Where stockpiles cannot be avoided above sloping ground they should be placed over a wide area with the height restricted under the direction of the Geotechnical Engineer.

4.4 Fill Foundations and Benching of Slopes

The foundation on which filling is to be placed must be observed by the Geotechnical Engineer following clearing and prior to the placement of any filling to confirm the strength of the underlying soils is sufficient.

Where it is found, after clearing and stripping operations as specified, that the foundation on which filling is to be placed is unstable, or in cuttings if it is found after the excavation has been cut down to the levels shown in the drawings that unstable ground is encountered, then the Engineer may direct that the soft, yielding or unstable materials causing such instability shall be removed to such depth as directed.

Benching of slopes prior to the placement and compaction of filling should be carried out in accordance with the normal requirements of NZS 4431 and related documents as mentioned above, especially on the steeper areas of the site, to ensure that the filling placed is keyed into the underlying natural ground. This would involve the cutting of benches approximately the width of a bulldozer, with a slight reverse gradient back into the slope. The optimum depth of each bench is best confirmed by careful Engineering inspections during construction.

4.5 Temporary Batters and Excavation Stability

The temporary stability of the works is the responsibility of the main contractor.

Slope instability during construction is a significant risk where earthworks may cause changes to slope geometry or groundwater conditions.

The causes of instability during earthworks may include:

- Removal of toe support due to excavation;
- Over steepening of slope angles in temporary batters;
- Geological defects in the soil or rock mass, particularly where these are exposed in excavation faces;
- Elevated groundwater levels following rainfall, perched groundwater or rapid recharge due to the reduced distance to an impermeable layer (i.e. undisturbed rock) due to cut operations; and,
- Additional loading upslope of excavations. ie. construction equipment or stockpiles.

To help mitigate these risks the contractor should consider:

- Staging excavations which reduce support to slopes or create temporarily over steepened slopes, to
 ensure large areas are not left unsupported. The allowable length of excavation to have open at any
 one time will vary and is dependent on a number of factors such as, local ground conditions,
 groundwater, length of time the excavation will be open, weather, depth of excavation, geological
 defects present and the earthworks equipment and methodology used;
- Ceasing works in excavations during rainfall and assessing stability of excavations following rainfall events prior to resuming work;
- Benching or battering back of excavation faces;
- Ensuring good control of surface water runoff above excavations and batters;
- Covering steep batters with impermeable covers where they may be left without support for any significant period of time;
- Avoiding loading the crests of slopes and excavations (including loading with working plant);
- Putting in place comprehensive risk identification and management procedures and work methodologies for temporary excavation stability;
- Carrying out regular inspections of the areas upslope of excavations and the excavation slope to look for signs of instability such as ground displacement and the development or propagation of cracks; and,
- Seeking advice from the Geotechnical Engineer where there is doubt as to the stability of a slope or excavation.

4.6 Fill Materials and Conditioning

4.6.1 Soil Fill, Rock Fill or Soil and Rock Mixed Fill

Site won materials used as engineered filling shall be free of topsoil, organic matter, rubbish and other unsuitable materials. The maximum particle size for soil and rock blended fill shall be 200mm and mixing and/ or crushing shall be carried out in a manner that ensures that significant voids are not present in the filling between rock fragments.

For rock fill without soil blending, crushing is to occur to comply with the requirements for blended fills and needs to ensure that uniform compaction can occur without significant voids between particles in the absence of the soil fill.

4.6.2 Blending of Unsuitables

The blending of 'unsuitables' into structural fills may be undertaken only at the discretion of the Geotechnical Engineer following a request by the contractor and with sufficient time for appropriate consideration. Approval for any such blending must be sought from and provided by the Geotechnical Engineer in writing prior to the commencement of any blending.

In consideration of any such requests, the Geotechnical Engineer will need to be able to assess, et. al., the composition of the materials requested to be blended, the location on the site for the proposed fills, the fill depths and the elevation of the blended materials within the fills and any environmental constraints.

As a minimum, it is expected that any blended fills will be directed to comply with the following conditions:

• All significant, solid inorganics (such as roots and stumps) to be removed prior to blending; and,

• All inclusions of suitable man-made materials (e.g. concrete) and any excavated rock must comply with the normal compaction requirements specified herein in terms of size and ability for appropriate compaction to be achieved in close vicinity to the inclusions.

• All blended materials must be appropriately mixed/ blended normal fill materials to the specified ratio. Un-mixed interlayering of normal engineered filling with unsuitables will not be accepted.

• As a preliminary indication, it is expected that the ratio of unsuitables to suitable fill will not exceed 1 in 10 by volume.

It is expected that the Geotechnical Engineer will also need to apply limits to the location/ depth of blended fills within any specified fill area.

4.6.3 Hardfill

Hardfill used as structural filling shall be a graded, unweathered, durable, crushed rock product approved by the Geotechnical Engineer, with a grading suitable for compaction.

4.6.4 Material Conditioning

The cut materials on site may require some drying prior to compaction to achieve the required specification. This may be done by harrowing (such as with discs) and air drying when conditions permit or by the addition of hydrated lime.

The addition of lime and/or cement to engineered filling in concentrations greater than 3% requires the approval of the Geotechnical Engineer.

All additives such as lime or cement proposed for use in backfill materials for Reinforced Earth Slopes or other materials in contact with geosynthetics must be approved and monitored by the Geotechnical Engineer.

4.7 Fill Placement, Compaction and Testing Requirements

4.7.1 Soil Fill

Soil placed in fills shall be conditioned and compacted until the following conditions are satisfied. Alternative methods based on specified compaction techniques may be selected by the Geotechnical Engineer if the method below is considered inappropriate due to the granular nature of the materials.

It should be noted that the surface of the fill area prior to placement of subsequent fill lifts should be in a state so as not to create a break in the consistency of the fill material between lifts. For example if surfaces are left to dry out, or rolled to seal them from rainfall infiltration then the surface must be broken up and scarified with rippers or by other means to ensure a good bond between fill lifts.

The maximum lift of filling placed before compaction is dependent on the size and nature of the compaction equipment. Typically, 300mm loose depth is considered the maximum for a Cat 815/820 type compactor. In any event the contractor must ensure that the fill is placed and compacted to achieve even and adequate compaction throughout each layer/lift.

The test criteria and frequency for cohesive materials (Clays & Silts) are set out in Table 1 and 2 below. If non cohesive soils (i.e. Sands) are to be placed as engineered fill the matter should be referred to the Geotechnical Engineer to define the testing requirements.

	Air \	Air Voids ⁽¹⁾		r Strength ⁽²⁾	Moisture Content ⁽³⁾	Dry Density ⁽³⁾	
	Average	Maximum Single Value	Average Minimum Single Value		Maximum	Minimum	
General Fill	10%	12%	140 kPa	110 kPa	40%	1.25 t/m ³	
High Strength Fill	8%	10%	150 kPa	120 kPa	40%	1.3 t/m ³	
Landscape Fill		TBC by Geotechnical Engineer of case by case basis					

Table 1 – Cohesive Materials (soil fill and soil/ rock blended fill) Compaction Test Criteria for Engineered Filling:

⁽¹⁾ Air Voids Percentage (as defined in NZS 4402:1986)

⁽²⁾ Undrained Shear Strength (Measured by hand shear vane – calibrated using NZGS 2001 method)

⁽³⁾ Moisture content and minimum dry density non-compliance may be accepted on site by the Geotechnical Engineer on a case by case basis depending on the nature of the material and the other criteria results.

	Field Density & Air Voids %	Vane Shear Strength	Solid Density	Compaction Curve
General Fill	1 test per 1500m ³ of fill placed with not less than 1 test per 500mm lift of filling for each area.	1 set of tests (4 readings within 1 metre of each other) per 500m ³ of filling placed with not less than 1 test per 500mm lift of filling for each fill area.	1 test per material type per 50,000m ³ or at least 1 test every 8 weeks.	1 test per material type per 30,000m ³ or at least 1 test every 5 weeks.
High Strength Fill	1 test per 1000m ³ of fill placed with not less than 1 test per 500mm lift of filling and for each 50m length of shear key excavation.	1 set of tests (4 readings within 1 metre of each other) per 500m ³ of filling placed with not less than 1 test per 500mm lift of filling per 25m of shear key excavation.	1 test per material type per 50,000m ³ or at least 1 test every 8 weeks.	1 test per material type per 30,000m ³ or at least 1 test every 5 weeks.
Landscape Filling	TBC by Geotechnic	cal Engineer of case by c	ase basis	<u> </u>

 Table 2 – Cohesive Materials (soil fill and soil/ rock blended fill) Compaction Testing

 Frequencies for Engineered Filling:

The test criteria and/or frequency may be relaxed at the discretion of the Geotechnical Engineer (CMW) for the project or in a discrete fill area subject to the consistency of the results achieved being acceptable over a specified period of time.

4.7.2 Compaction Testing Reporting Requirements

- 1 All test location coordinates to be recorded by hand held GPS with reference to the NZTM projection. Test location coordinates, with date and test number reference are to be provided to the Geotechnical Engineer in electronic (excel) format on a weekly basis. Alternatively, the Geotechnical Engineer may approve the use of site plans to mark the location of tests in lieu of GPS location.
- 2. The volume of filling placed for each progress claim month (typically ending 20th of the month) including all filling placed (undercut and cut to fill) to be provided to the Geotechnical Engineer monthly by the contractor or Engineer to the Contract to allow assessment of test frequency adequacy.
- 3. Interim fill test summaries are to be provided to the Geotechnical Engineer for review on a regular basis.

4.7.3 Hardfill

A plateau compaction test shall be carried out on site under the supervision of the Geotechnical Engineer, for each type of hardfill placed to determine the achievable maximum dry density (MDD) with no more than 20% total voids unless a laboratory derived MDD can be provided. The Geotechnical Engineer shall be given the opportunity to approve the size and type of compaction equipment to be used prior to any plateau testing.

Hardfill shall be placed and compacted to 95% of the MDD determined from the plateau test or laboratory MDD. If these conditions are not able to be met then appropriate adjustment of the moisture content or compaction equipment will be required.

In all cases, the dry density of the compacted fill at any one test site shall be not more than 5% below the minimum and the average of the dry densities of any ten consecutive test sites shall not be less than the specified minimum.

The Geotechnical Engineer, may at their discretion, alter the compaction specification to a method compaction specification based on the plateau test result for materials with a maximum particle size greater than 65mm.

The test frequency shall be 1 test per 500m³ of hardfill placed with not less than 1 test per 500mm lift of filling for each fill area.

The test frequency may be relaxed at the discretion of the Geotechnical Engineer (CMW) for the project or in a discrete fill area subject to the consistency of the results achieved being acceptable over a specified period of time.

4.8 Subsurface Drainage

4.8.1 General

Drainage for shear keys, fill drainage keys, buttress fills, underfill gully drains and counterfort drains shall be constructed in accordance with the design drawings and standard details.

4.8.2 Materials

4.8.2.1 Pipes

Drainage pipes used in subsoil drainage shall be 160mm diameter highway grade drain coil. Drain coil walls shall be perforated or solid as detailed in the design drawings or directed by the Geotechnical Engineer on site. Drain coils shall not have a geofabric filter sock unless requested by the Geotechnical Engineer on site.

4.8.2.2 Aggregate

Auckland Council now generally require that subsoil drainage has a 100 year design life and is essentially maintenance free, unless there is an entity such as body corporate or residents association that maintenance responsibility can be transferred to. Maintenance by individual owners is not practical as the subsoil drainage systems usually cross over, and generally benefit, multiple lots.

This requires a high quality drainage aggregate with the following properties:

- Self-filters against the soils present on site preventing loss of permeability over time; or, able to be practically wrapped in a suitable geofabric filter;
- High permeability, which translates to a low fines content; and
- Stable and not subject to crushing, weathering, internal erosion or piping, or significant loss of volume (settlement) over time.

Ideally the drainage aggregate should be a well graded self-filtering material such as a clean (free of significant cohesive fines) scoria SAP50 product or Transit F/2 specification filter media.

Alternatively, for shear key drainage, blanket drains, underfill drainage and all applications where full encapsulation with a geofabric filter cloth can be relatively simply and safely achieved, an open graded product, preferably 27/7 Scoria may be used. Care will need to be taken to ensure that the cloth fully encapsulates the aggregate. Observation of the cloth wrap should form an inspection hold point prior to backfilling over the drain. Drain coils in this instance do not require a filter sock.

For counterfort trench drains and applications where a full filter cloth wrap is not practical to construct, <u>and</u> the performance of the drain is not critical to maintaining slope stability then a SAP20 or SAP50 may be used without a filter cloth wrap. Drains which fall into this category <u>must</u> be defined and confirmed as such by the Geotechnical Engineer. Additionally, where such materials are used, regular visual inspections and approval of the aggregate quality and laboratory grading curves is required. This is to comprise visual inspection of each site stockpile prior to material being placed in the trench. One wet sieve grading curve from each site stockpile per week is required while material is being imported to site to monitor the fines content. Drain coils in this instance do not require a filter sock.

For counterfort trench drains and applications where a full filter cloth wrap is not practical to construct, <u>and</u> the performance of the drain is critical to maintaining slope stability then a TNZ/F2 or (approved) modified F2 aggregate must be used. In conjunction with this an approved high specification drainage pipe with filter cloth surround such as the Megaflo products may be specified.

Light compaction (i.e. tamping with back of excavator bucket) only is to be applied to drainage aggregates.

4.8.2.3 Filter Cloth

Any filter cloth surround specified on the drawings shall meet the requirements of Transit Specification TNZ/F7, Filtration Class 2 and Strength Class B unless otherwise specified on the drawings.

4.8.2.4 Trench Backfill in Service Trenches

It is important on all sloping land that service trenches running parallel to contours are avoided where possible as they can permit the ingress of surface water and/or lateral movement of trench sides that could lead to progressive land slippage, help develop tension cracks and possibly lead to slope and building instability.

Backfilling of all trenches should be to the general fill standard above unless specifically varied in writing by the Geotechnical Engineer and where possible the pipe bedding in all trenches on steep ground should contain a 50mm diameter perforated drain coil that is connected into each manhole on the line. This is to help prevent instability arising from the ingress of surface water and/or lateral movement of trench sides that could lead to progressive land slippage and is especially important where the lines are in close proximity to buildings.

The subdivision drain laying contractor must be made aware of these requirements and of the need to contact us when trench backfilling is to take place.

4.8.3 Depth and Extent

The location, extent and depth of the drainage shown on the design drawings may be varied on site by the Geotechnical Engineer in response to the ground conditions encountered.

4.8.4 Drainage Outlets and Inspection Points

Outlets for subsurface drainage shall be provided at regular intervals shown on the drawings or as determined on site by the Geotechnical Engineer. Pipe outlets shall be specifically formed structures with adequate protection such as a headwall and/or rock rip rap. The position of all outlets shall be recorded on the asbuilt drawings.

Where possible it is good practice to include additional inspection and/or flushing points in the subsoil drainage system in the event that their performance needs to be confirmed in the future.

In any event, at least one temporary flush point is required for each subsoil drainage system to enable flushing of the system once the earthworks are substantially complete.

The flushing of the subsoil drainage system must be witnessed by the Geotechnical Engineer.

4.9 Finishing Works and Topsoil Respread

4.9.1 Overcut

All areas cut to below finished level should be reinstated with engineered filling to the satisfaction of the Geotechnical Engineer.

4.9.2 Topsoil Depth

Topsoil respread depth should be between 100mm and 300mm, or as directed by the Engineer to the contract. On ground steeper than 1V:3H the surface should be roughened under the supervision of the Geotechnical Engineer prior to topsoil placement.

4.9.3 Unsuitable Materials

At the conclusion of earthworks all surplus unsuitable materials should be removed from site or placed in designated permanent stockpiles. The size and location of such stockpiles must be approved by the Geotechnical Engineer and recorded on the asbuilt drawings.

4.9.4 Road Subgrades

Testing and formation of road subgrades will be carried out as part of the subdivision civil works package.

5 MONITORING

5.1 Settlement

Where filling is placed over materials suspected to be of a compressible nature or where a significant depth of filling is to be placed, then settlement monitoring points should be installed on the stripped surface prior to filling and on finished surface of the filling and monitored during and post construction to ensure ongoing settlement rates are within acceptable guidelines for residential building development.

The number and position of monitoring points and the frequency of post construction settlement monitoring is to be agreed with the Geotechnical Engineer during construction.

It is the contractor's responsibility to ensure the integrity of the monitoring points is maintained during the works.

6 ASBUILT INFORMATION REQUIREMENTS

In order to provide a Geotechnical Completion Report (GCR) certain as-built information must be provided to CMW. It is the contractor's responsibility to ensure that all of the following items are surveyed prior to placing filling. The survey of these items should therefore form a hold point in the construction sequence.

- 1. The location and invert of all sub surface drainage; and,
- 2. The depth of filling placed including all benching, undercuts, shear or fill drainage keys and temporary ponds which have been backfilled.

CMW require the following as-built information to be provided for the GCR:

- 1. Cut and fill depth plan (including undercuts and shear keys);
- 2. Final contour plan;
- 3. Drainage locations and inverts (surface and subsurface);
- 4. Drainage outlet locations (surface and subsurface);
- 5. Details of any defined overland flow paths;

- 6. Location and heights of any retaining walls;
- 7. Material data for imported products used such as draincoils, aggregates and geofabrics as well as confirmation that products installed comply with the requirements of the project drawings and this specification; and,
- 8. Any settlement Monitoring Data.

Appendix I: Soakage Testing Results





LEGEND

LEGEND	
WORKS AREAS	
WORKS AREAS - EXCLUSION ZONES	
EXISTING CONTOURS	X
FINAL CONTOURS	x
EARTH BUND	
SILT FENCE	
SUPER SILT FENCE	-0000
SEDIMENT LADEN DIVERSION BUND	— R — R — R —
CLEAN WATER DIVERSION BUND	$\longrightarrow \longrightarrow \longrightarrow$
STABILISED ENTRANCEWAY	
SEDIMENT RETENTION POND OUTLETS	
EARTH BUND DECANT UPSTAND OUTLET	~
SEDIMENT RETENTION POND	

SEE 447-01-BE-225 TO 227 FOR ADDITIONAL SEDIMENT AND EROSION CONTROL NOTES, DEVICE SIZING, CALCULATIONS AND DETAILS.



Soakage Test - Approximate Locations

FOR CONSTRUCTION

	Ву	Date	Scale	Job No.	447-01	
veyed:	DS			Drawing No.		Rev
igned:	СК		1: 3000@A3	4.47 04		
wn:	СК	11/19		44/-01-	-BE-220	0
proved:	СК					
FILE	F: \ PROJECTS	BRIGHAM C	REEK TRIG\DWG`	ENG\BULK EW\FOR	CONSTRUCTION\447-01-E	E-220.

CLIENT: Neil Construction Limited PROJECT: Brigham Creek and Trig Road LOCATION: Whenuapai JOB NUMBER: AKL2019-0040 TEST DATE: 26/05/2021





Elapsed Time

(s)

1380

2640

4020

5580

7080

8640

10380

11820

13260

Ó

t2 - t1

(secs)

1380

1260

1380

1560

1500

1560

1740

1440

1440

Reference: Appendix 4, Control of Groundwater for Temporary Works (CIRIA Report No. 113)

Borehole diameter = 100 mm

Piezometric Head

h (m)

1.76

1.625

1.405

1.335

1.28

1.22

1.195

1.175

1.5

2

Hydraulic conductivity	k =	$\left(\frac{log\left(\frac{h_1}{h_2}\right) - log\left(\frac{\alpha h_1 + 1}{\alpha h_2 + 1}\right)}{(t_2 - t_1)}\right)$) x /
------------------------	-----	--	-------

where I = average piezometric head over chosen time interval

$$=\frac{(h_1+h_2)}{2}$$

h₁ = piezometric head at start of chosen interval (m) h₂ = piezometric head at end of chosen interval (m) $t_2 - t_1 =$ chosen time interval (seconds)

$$\alpha = \frac{\pi d}{\left(\frac{\pi d^2}{2}\right)} = 20.0$$

1

(m)

1.88

1.69

1.56

1.45

1.37

1.31

1.25

1.21

1.19

log (h₁/h₂) Hydraulic Conductivity k (m/sec) k (m/day) 0.06 1.96E-06 1.70E-01 1.34E-06 1.16E-01 0.03 0.03 1.22E-06 1.06E-01 0.03 8.81E-07 7.61E-02 0.02 7.14E-07 6.17E-02 0.02 5.64E-07 4.87E-02 0.02 5.76E-07 4.98E-02 3.00E-07 2.59E-02 0.01 0.01 2.44E-07 2.11E-02

> Average = 8.67E-07 8.16E-02

 CLIENT:
 Neil Construction Limited

 PROJECT:
 Brigham Creek and Trig Road

 LOCATION:
 Whenuapai

 JOB NUMBER:
 AKL2019-0040

 TEST DATE:
 26/05/2021





Reference: Appendix 4, Control of Groundwater for Temporary Works (CIRIA Report No. 113)

Borehole diameter =

100 mm

Hydraulic conductivity $k = \left(\frac{\log(\frac{h_{\star}}{h_{\star}}) - \log(\frac{ah_{\star}+1}{ah_{\star}+1})}{\sum_{k} \log(h_{\star})}\right) \times l$	Elapsed Time	t2 - t1	Piezometric Head	/ (m)	log (h ₁ /h ₂)	Hydraulic Co	onductivity
$(t_2 - t_1)$	(5)	(secs)	2	(11)		K (III/Sec)	ĸ (III/uay)
	1320	1320	1.94	1.97	0.01	4.89E-07	4.22E-02
where / = average piezometric head over chosen time interval	2520	1200	1.9	1.92	0.01	3.67E-07	3.17E-02
$(h_1 + h_2)$	3900	1380	1.88	1.89	0.00	1.62E-07	1.40E-02
$=\frac{(1+2)}{2}$	5460	1560	1.87	1.88	0.00	7.23E-08	6.25E-03
2	6780	1320	1.85	1.86	0.00	1.72E-07	1.49E-02
h ₁ = piezometric head at start of chosen interval (m)	8400	1620	1.82	1.84	0.01	2.13E-07	1.84E-02
h ₂ = piezometric head at end of chosen interval (m)	10140	1740	1.82	1.82	0.00	0.00E+00	0.00E+00
$t_2 - t_1 =$ chosen time interval (seconds)	11580	1440	1.82	1.82	0.00	0.00E+00	0.00E+00
	12960	1380	1.805	1.81	0.00	1.27E-07	1.09E-02
	14280	1320	1.8	1.80	0.00	4.44E-08	3.84E-03
πd					Average =	1.65E-07	1.59E-02
$\alpha = \frac{\pi d^2}{\left(\frac{\pi d^2}{2}\right)} = 20.0$							

CLIENT:Neil Construction LimitedPROJECT:Brigham Creek and Trig RoadLOCATION:WhenuapaiJOB NUMBER:AKL2019-0040TEST DATE:26/05/2021





Elapsed Time

(s)

1320

2640

3960

5700

7140

8580

10320

11880

13260

Ó

t2 - t1

(secs)

1320

1320

1320

1740

1440

1440

1740

1560

1380



Reference: Appendix 4, Control of Groundwater for Temporary Works (CIRIA Report No. 113)

Borehole diameter = 100 mm

Hydraulic conductivity
$$k = \left(\frac{log(\frac{h_1}{h_2}) - log(\frac{\alpha h_1 + 1}{\alpha h_2 + 1})}{(t_2 - t_1)}\right) \times l$$

where *I* = average piezometric head over chosen time interval

$$=\frac{(h_1+h_2)}{2}$$

 $h_1 = piezometric head at start of chosen interval (m)$ $h_2 = piezometric head at end of chosen interval (m)$ $t_2 - t_1 = chosen time interval (seconds)$

$$\alpha = \frac{\pi d}{\left(\frac{\pi d^2}{2}\right)} = 20.0$$

Piezometric Head log (h₁/h₂) Hydraulic Conductivity 1 h (m) (m) k (m/sec) k (m/day) 2 1.69 0.16 6.06E-06 5.24E-01 1.38 1.07E-06 9.25E-02 1.29 1.34 0.03 1.22 1.26 0.02 8.83E-07 7.63E-02 1.11 1.17 0.04 1.13E-06 9.78E-02 1.03 0.03 1.08E-06 9.32E-02 1.07 0.9 0.97 0.06 1.94E-06 1.68E-01 0.57 0.74 0.20 5.51E-06 4.76E-01 6.93E-01 0.31 0.44 0.26 8.02E-06 0.2 0.19 5.91E-06 5.10E-01 0.26 Average = 3.51E-06 2.77E-01

